

20100110		TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STATION	OFFSET	LT/RT	UNITS	
GABLES BLVD				
30+52.30	23.59	RT	8	
31+57.10	23.03	RT	9	
32+06.45	22.28	RT	10	
32+45.94	34.71	RT	12	
MANCHESTER ROAD				
15+89.12	37.59	RT	12	
16+09.12	34.69	RT	14	
FRONT STREET				
53+29.96	13.83	RT	9	
WESLEY STREET				
41+18.53	29.06	LT	6	
41+23.21	28.88	LT	6	
41+30.08	22.70	LT	6	
41+35.02	13.38	LT	6	
41+87.10	23.53	LT	6	
41+95.28	22.06	LT	10	
41+99.24	27.82	LT	10	
42+24.75	18.96	LT	12	
42+57.56	22.17	LT	8	
42+68.23	19.72	LT	12	
42+69.76	18.80	LT	12	
WESLEY STREET				
44+77.34	20.94	LT	12	
44+98.59	20.51	LT	10	
45+28.56	20.28	LT	10	
46+10.40	20.53	RT	10	
46+33.97	19.08	RT	6	
WESTERN AVENUE				
6473.22	37.57	RT	14.00	
			TOTAL	230

20100210		TREE REMOVAL (OVER 15 UNITS DIAMETER)		
STATION	OFFSET	LT/RT	UNITS	
WESLEY STREET				
41+45.95	10.43	LT	16	
42+33.48	26.86	LT	42	
45+25.20	24.08	RT	30	
45+69.18	23.24	RT	18	
45+88.29	20.21	LT	36	
WESTERN AVENUE				
64+62.45	28.83	LT	20	
65+05.04	20.31	RT	18	
			TOTAL	180

20100500		TREE REMOVAL, ACRES			
STATION	STATION	OFFSET	AREA		
			(SQ FT)	(ACRE)	
ILLINOIS PRAIRIE PATH					
15+65.00	19+18.59	LT	12872	0.30	
15+65.00	19+18.59	RT	9665	0.22	
			TOTAL	0.52	
			TOTAL (ROUNDED)	0.75	

20101000		TEMPORARY FENCE			
STATION	OFFSET	LT/RT	FEET		
MANCHESTER ROAD					
15+13.69	100.33	RT	48		
17+96.56	41.31	RT	48		
18+21.96	41.53	RT	48		
18+46.59	41.53	RT	48		
18+72.20	39.52	RT	48		
18+96.58	40.26	RT	48		
WESLEY STREET					
46+32.91	22.66	LT	48		
WESTERN AVE					
65+54.05	18.09	RT	48		
CONTINGENCY					
3 additional trees			144		
			TOTAL	576	

20101200		TREE ROOT PRUNING			
STATION	OFFSET	LT/RT	EACH		
MANCHESTER ROAD					
15+13.69	100.33	RT	1		
17+96.56	41.31	RT	1		
18+21.96	41.53	RT	1		
18+46.59	41.53	RT	1		
18+72.20	39.52	RT	1		
18+96.58	40.26	RT	1		
WESTERN AVE					
65+54.05	18.09	RT	1		
			TOTAL	7	

20700220		POROUS GRANULAR EMBANKMENT		
LOCATION	PLAN	AVE DEPTH	VOLUME	
	(SQ FT)	(FT)	(CU YD)	
Roadway Areas				
Manchester Road 11+00 to 15+00	14380	1	532.6	
Manchester Road 22+00 to 24+75	9162	1	339.3	
Gables Blvd 30+25 to 32+00	4976	1	184.3	
Wesley St 45+50 to 46+40	1980	1	73.3	
Front St 53+75 to 54+70	2090	1	77.4	
Western Ave 63+75 to 65+40	5116	1	189.5	
Structural (See Structural Plans)				
			TOTAL	1396

21301052		EXPLORATION TRENCH 52-INCH DEPTH		
LOCATION	STATION	STATION	LENGTH	
			FT	
MANCHESTER ROAD				
	11+00.00	24+75.00	687.50	
GABLES BOULEVARD				
	30+25.00	32+76.60	125.80	
WESLEY STREET				
	40+00.00	40+30.62	15.31	
	41+26.85	46+40.00	256.58	
WESTERN AVENUE				
	60+00.00	65+40.00	270.00	
FRONT STREET				
	50+00.00	54+70.00	235.00	
			TOTAL	1590

25000100		SEEDING, CLASS 1					
STREET	STATION	STATION	OFFSET	SQ FT	ADJUST FACTOR	ACRE	
MANCHESTER ROAD							
	16+00.00	22+22.98	RT	6599.95	1.03	0.156	
WESLEY STREET							
	40+89.96	42+87.77	LT	2813.37	1.03	0.067	
	43+91.99	45+55.33	RT	3079.12	1.03	0.073	
WESTERN AVENUE							
	61+15.77	62+28.31	LT	1181.03	1.00	0.027	
FRONT STREET							
	52+43.87	53+85.26	LT	3472.03	1.03	0.082	
ILLINOIS PRAIRIE PAT							
	16+65.06	19+05.69	LT	1562.70	1.20	0.043	
	16+99.97	18+49.93	RT	1127.88	1.20	0.031	
				TOTAL		19836	
				TOTAL (ROUNDED)		0.48	
				TOTAL (ROUNDED)		0.50	

25000210		SEEDING, CLASS 2A				
STREET	STATION	STATION	OFFSET	SQ FT	ACRE	
MANCHESTER ROAD						
	11+00.00	15+00.00	LT	2028.74	0.05	
				TOTAL	2028.74	
				TOTAL (ROUNDED)	0.25	

25000300		SEEDING CLASS 3					
STREET	STATION	STATION	OFFSET	SQ FT	ADJUST. FACTOR	ACRE	
MANCHESTER ROAD							
	15+00.00	22+80.57	LT	13204.06	1.12	0.339	
MANCHESTER ROAD TO FRONT STREET							
	19+00.00	55+25.00	RT	23034.90	1.12	0.592	
ILLINOIS PRAIRIE PATH							
	16+64.54	18+99.93	LT	3428.49	1.20	0.094	
	16+64.54	19+18.59	RT	3890.10	1.20	0.107	
WESTERN AVENUE							
	63+22.67	64+70.42	RT	2025.50	1.20	0.056	
				TOTAL	45583.05		1.19
				TOTAL (ROUNDED)			1.25

REVISIONS	
NAME	DATE

CITY OF WHEATON
 MANCHESTER ROAD / WESLEY STREET
 OVER UNION PACIFIC RAILROAD
 SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY DW
 HORIZ. CHECKED BY JLC
 DATE 6/4/2008