

42400100		PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH				
STATION	STATION	LOCATION	WIDTH	LENGTH	AREA	COMMENT
					SQ FT	
<b>MANCHESTER ROAD</b>						
11+00.00	11+52.80	RT	6.00	52.8	287	
11+80.73	12+47.66	RT	6.00	66.9	371	
12+86.58	13+15.80	RT	6.00	29.2	161	
15+34.22	15+99.99	RT	6.00	65.8	358	
22+53.30	22+81.11	LT	6.00	27.8	195	
22+22.98	23+00.37	RT	6.00	77.4	322	
23+07.12	23+29.30	LT	6.00	22.2	126	
23+39.30	24+18.51	RT	6.00	79.2	445	
23+44.30	23+89.44	LT	6.00	45.1	242	
24+34.47	24+75.00	RT	6.00	40.5	233	
22+83.12	22+98.55	LT	3.60	15.4	112	
<b>GABLES BOULEVARD</b>						
30+25.00	30+44.92	LT	6.00	19.9	98	
30+25.00	30+82.20	RT	6.00	57.2	327	
30+84.46	31+67.29	LT	6.00	82.8	482	
31+11.99	32+25.45	RT	6.00	113.5	661	
<b>WESLEY STREET</b>						
43+91.99	45+87.10	RT	5.00	195.1	976	
45+99.10	46+40.00	RT	5.00	40.9	205	
43+97.03	44+58.02	LT	10.00	61.0	417	
44+70.02	45+45.07	LT	5.00	75.0	364	
45+11.00	45+15.00	LT	4.00	4.0	120	Carriage walk
45+57.07	45+93.70	LT	6.00	36.6	196	
46+05.70	46+40.00	LT	5.00	34.3	153	
44+87.62	44+92.62	RT	5.00	5.0	65	Carriage walk
45+55.54	45+60.54	RT	5.00	5.0	65	Carriage walk
45+55.33	45+60.33	RT	5.00	5.0	15	Carriage walk
46+17.18	46+22.18	RT	5.00	5.0	65	Carriage walk
<b>FRONT STREET</b>						
52+26.69	52+43.87	LT	5.00	17.2	303	
52+43.87	53+85.08	LT	5.00	141.2	705	
54+09.24	54+70.00	LT	5.00	60.8	301	
<b>WESTERN AVENUE</b>						
61+95.92	63+22.67	RT	10.00	126.8	1268	
63+23.67	64+44.09	RT	6.00	120.4	745	
64+44.09	65+40.00	RT	5.50	99.5	761	
64+82.23	65+07.68	LT	4.00	12.0	36	
62+37.72	62+76.18	LT	5.00	39.0	189	
<b>MANCHESTER/GABLES INTERSECTION</b>						
13+15.80	13+43.80	SW	6.00	122.0	582	
13+92.00	14+75.45	SE	6.00	90.0	527	
<b>WESLEY/WESTERN INTERSECTION</b>						
61+10.80	61+95.92	NE	10.00	110.0	1108	
60+10.41	60+75.75	SE	5.00	65.3	327	
<b>Curb Ramps In Moment Slab</b>						
20+68.35	20+81.35	RT	6.00	13.0	44	
20+71.67	20+80.03	LT	6.00	8.4	48	
52+18.45	52+31.45	RT	6.00	13.0	48	
					TOTAL	14051.67
					TOTAL (ROUNDED)	14052.0

42400800		DETECTABLE WARNINGS			
	STATION	LOCATION	AREA		
			SQ FT		
<b>MANCHESTER ROAD</b>					
	11+46.00	RT	12		
	11+87.00	RT	12		
	12+41.00	RT	12		
	12+93.00	RT	12		
	13+40.00	RT	6		
	14+15.00	RT	7		
	14+66.00	RT	6		
	15+42.00	RT	6		
	20+75.00	RT	6		
	20+75.00	LT	6		
	22+92.00	RT	12		
	23+46.00	RT	12		
	24+12.00	RT	12		
	24+36.00	RT	12		
	22+76.00	LT	13		
	23+09.00	LT	12		
	23+80.00	LT	12		
<b>GABLES BOULEVARD</b>					
	30+78.00	RT	6		
	31+17.00	RT	6		
	30+40.00	LT	10		
	30+91.00	LT	12		
<b>WESLEY STREET</b>					
	43+83.00	RT	8		
	43+90.00	LT	6		
<b>FRONT STREET</b>					
	52+25.00	RT	6		
	52+29.50	LT	6		
<b>WESTERN AVENUE</b>					
	64+52.00	RT	6		
	64+92.00	LT	7		
				TOTAL	243
				TOTAL (ROUNDED)	243

44000100		PAVEMENT REMOVAL				
STREET	STATION	STATION	LENGTH	WIDTH	SQ FT	SQ YD
			FT			
<b>MANCHESTER ROAD</b>						
	11+00.00	13+32.00	232	28.0	6496	722
	13+32.00	14+20.00	88	28	2486	276
	14+20.00	14+53.00	33	29	957	106
	14+53.00	15+59.00	106	28	2968	330
	15+59.00	16+50.00	91	26	2351	261
	16+50.00	16+59.00	9	26	233	26
	16+59.00	17+17.00	58	27	1542	171
	17+17.00	17+80.00	63	26	1638	182
	17+80.00	20+43.00	263	23	5918	658
	20+43.00	21+33.00	90	23	2039	226
	21+33.00	22+27.00	94	23	2162	240
	22+27.00	23+31.00	104	29	2964	329
	23+31.00	23+78.00	47	34	1586	176
	23+78.00	24+46.00	68	33	2270	252
	24+46.00	24+57.00	11	36	397	44
	24+57.00	24+75.00	18	39	698	78
<b>GABLES BOULEVARD</b>						
	30+25.00	31+67.00	142	28	3965	441
	31+67.00	32+72.00	105	0	3222	358

ISLAND ABOUT WESLEY/FRONT/ WESTERN				14983	1665
STREET	STATION	STATION	AREA	AREA	AREA
			SQ FT	SQ YD	
<b>WESTERN AVENUE</b>					
	61+28.00	61+50.00	22	48	1050
	61+50.00	62+59.00	109	48	3722
	62+59.00	63+18.00	59	48	2832
	63+18.00	64+17.00	99	49	3402
	64+17.00	65+40.00	123	0	4937
<b>WESLEY STREET</b>					
	43+86.00	46+40.00	254	21	5437
<b>FRONT STREET</b>					
	52+36.00	54+70.00	234	22	5148
				TOTAL	9490

44000200		DRIVEWAY PAVEMENT REMOVAL			
STREET	STATION	OFFSET	AREA	AREA	
			SQ FT	SQ YD	
<b>GABLES BOULEVARD</b>					
	30+96.17	RT	612	68	
	32+34.00	LT	438	49	
<b>MANCHESTER ROAD</b>					
	11+66.77	RT	343	38	
	12+67.12	RT	1162	129	
	14+77.72	RT	7796	866	
	17+00.00	RT	1348	150	
	22+91.52	LT	1891	210	
	23+19.83	RT	2657	295	
	23+36.80	LT	546	61	
	24+09.00	LT	920	102	
	24+27.47	RT	127	14	
<b>FRONT STREET</b>					
	53+97.02	LT	231	26	
<b>WESLEY STREET</b>					
	44+64.02	LT	1724	192	
	45+51.07	LT	294	33	
	45+93.10	RT	246	27	
	45+99.70	LT	203	23	
<b>WESTERN AVENUE</b>					
	61+34.50	LT	255	28	
	62+90.13	LT	5698	633	
	64+59.82	RT	284	32	
	65+25.78	RT	179	20	
				TOTAL	2996

REVISIONS	
NAME	DATE

CITY OF WHEATON  
 MANCHESTER ROAD / WESLEY STREET  
 OVER UNION PACIFIC RAILROAD  
 SCHEDULE OF QUANTITIES

SCALE: VERT.      DRAWN BY DW  
 HORIZ.              CHECKED BY JLC  
 DATE 6/4/2008