

44201759	CLASS D PATCHES, TYPE IV, 9-INCH				
STATION	STATION	WIDTH	AREA		
			SQ FT	SQ YD	
GABLES BOULEVARD					
30+17.00	30+25.00	30.00	240.00	26.67	
BRIDGE STREET (MANCHESTER ROAD)					
24+75.00	24+83.00	39.00	312.00	34.67	
TOTAL				61.33	
TOTAL (ROUNDED)				62	

50104600	CONCRETE RETAINING WALL REMOVAL			
STATION	STATION	LOCATION	LENGTH	
			FT	
MANCHESTER ROAD				
17+35.37	22+22.98	RT	487.61	
22+22.98	22+42.92	RT	19.94	
TOTAL			507.55	
TOTAL (ROUNDED)			508	

55100100	STORM SEWER REMOVAL 4"			
STATION	STATION	LT/RT	LENGTH	
			FT	
MANCHESTER ROAD				
11+97.72	11+97.09	RT	8	
TOTAL			8	

55100200	STORM SEWER REMOVAL 6"			
STATION	STATION	LT/RT	LENGTH	
			FT	
WESTERN AVENUE				
20+99.49	21+01.70	RT	12	
TOTAL			12	

44213200	SAW CUTS		
STATION	STATION	LENGTH	
		FT	
MANCHESTER ROAD			
10+52.00	11+00.00	72.00	
GABLES BOULEVARD			
30+17.00	30+25.00	76.00	
FRONT STREET			
54+70.00	54+78.00	60.00	
WESLEY STREET			
46+40.00	46+48.00	58.00	
WESTERN AVENUE			
65+40.00	65+48.00	62.00	
BRIDGE STREET (MANCHESTER ROAD)			
24+75.00	24+83.00	94.00	
Contingency			50.00
TOTAL			472

50901720	BICYCLE RAILING		
STATION	STATION	LENGTH	
		FT	
IPP			
16+66.12	19+00.00	234.00	
16+66.31	19+18.59	252.00	
STRUCTURAL (See structural Plans)			
TOTAL			486
TOTAL (ROUNDED)			486

54248510	CONCRETE COLLARS						
Drawling *	Pipe No.	DIA. FT	PIPE THICKNESS, FT	LENGTH, FT	HEIGHT, FT	WIDTH, FT	VOLUME, CU YD
Manchester Sheet 1	SS-141	1.50	0.21	2	2.92	2.92	0.4
Manchester Sheet 1	SS-139	1.00	0.17	2	2.34	2.34	0.3
Manchester Sheet 3	SS-144	1.25	0.19	2	2.63	2.63	0.4
Manchester Sheet 3	SS-154	0.83	0.15	2	2.13	2.13	0.3
Manchester Sheet 3	SS-155	0.33	0.14	2	1.61	1.61	0.2
Western Sheet 1	SS-148	0.67	0.14	2	1.95	1.95	0.2
Gables Sheet 1	SS-151	1.00	0.17	2	2.34	2.34	0.3
Gables Sheet 1	SS-153	1.00	0.17	2	2.34	2.34	0.3
Front Sheet 1	SS-152	0.67	0.14	2	1.95	1.95	0.2
TOTAL					2.6	CU YD	

55100300	STORM SEWER REMOVAL 8"			
STATION	STATION	LT/RT	LENGTH	
			FT	
GARBLES BLV.				
30+29.12	30+42.14	RT	23	
WESLEY STREET.				
45+56.02	45+56.27	LT/RT	27	
44+26.40	46+40.00	RT	214	
FRONT STREET				
56+56.16	53+55.92	LT/RT	24	
53+55.33	54+57.58	LT	112	
WESTERN AVE.				
64+45.64	64+46.41	LT/RT	8	
64+96.67	64.83+83	LT	33	
TOTAL			441	

48100300	AGGREGATE SHOULDERS, TYPE A 4"				
STATION	STATION	LT/RT	WIDTH	AREA	
			FT	SQ FT	SQ YD
IPP					
11+48.00	11+98.00	RT	2.00	100.00	11.11
11+48.00	11+98.00	LT	2.00	100.00	11.11
16+66.00	19+19.00	RT	2.00	506.00	56.22
16+66.00	19+06.00	LT	2.00	480.00	53.33
TOTAL					131.78
TOTAL (ROUNDED)					132

55039700	STORM SEWERS TO BE CLEANED			
LOCATION	STATION	STATION	LENGTH	
			FT	
Contingency Item				
			100	
TOTAL			100	

55100400	STORM SEWER REMOVAL 10"			
STATION	STATION	LT/RT	LENGTH	
			FT	
WESLEY STREET				
44+19.55	44+23.77	LT/RT	22	
44+23.77	44+26.40	RT	5	
FRONT STREET				
55+55.92	53+55.33	LT	8	
MANCHESTER ROAD				
22+83.48	22+02.19	RT	28	
23+02.33	23+02.19	LT/RT	30	
WESTERN AVE.				
62+91.63	63+12.61	LT	22	
TOTAL			115	

REVISIONS	
NAME	DATE

CITY OF WHEATON
 MANCHESTER ROAD / WESLEY STREET
 OVER UNION PACIFIC RAILROAD
 SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY DW
 HORIZ. CHECKED BY JLC
 DATE 6/4/2008