

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)					
LOCATION	STATION	STATION	LENGTH FT	EACH	EACH
WESLEY STREET	40+54.19	41+63.77	54.79	1,369.75	2
	43+45.22			8	8
			TOTAL		10

X0323564 INSTALL WATER VALVES			
STATION	OFFSET	LT/RT	EACH
MANCHESTER ROAD			
23+60.51	13'	RT	1
GABLES BLVD			
32+40.00	11'	LT	1
32+51.00	12'	LT	1
WESTERN AVE			
61+02.00	25'	RT	1
61+25.00	9'	LT	1
64+78.29	24'	RT	1
	TOTAL		6

X0323988 TEMPORARY SOIL RETENTION SYSTEM			
LENGTH/WIDTH	DEPTH	SHAPE FACTOR	AREA SF
JACKING AND RECEIVING PITS			
23' DEPTH see Manchester XS at sta 21+75 elev approx 740.00			
19' DEPTH see Wesley XS at sta 43+00 elev approx 740.00			
RECEIVING PIT			
24	23	1	552.00
15	23	1	345.00
15	23	1	345.00
24	23	1	552.00
JACKING PIT			
20	20	1	400.00
20	20	1	400.00
20	20	1	400.00
20	20	1	400.00
	TOTAL		3394

X0321556 SANITARY MANHOLES TO BE ADJUSTED			
STATION	OFFSET	LT/RT	EACH
Manchester Road			
11+54.57	22.6'	RT	1
15+13.42	31.1	RT	1
22+97.27	21.2	LT	1
23+50.15	13.6	LT	1
Wesley Street			
45+70.83	10.6	RT	1
45+72.13	3.9	LT	1
Western Avenue			
64+83.64	13.7	RT	1
	Total		7

X0323973 SEDIMENT CONTROL, SILT FENCE				
STREET	STATION	STATION	OFFSET	LENGTH
MANCHESTER ROAD				
	15+50.00	19+50.00	RT	401.83
	23+10.11	23+29.30	LT	52.11
	23+44.30	23+96.50	LT	81.88
WESLEY STREET				
	40+89.96	42+89.16	LT	221.25
	44+25.57	44+50.00	RT	75.18
WESTERN AVENUE				
	61+21.49	62+28.07	LT	107.95
FRONT STREET				
	52+64.44	53+83.64	LT	121.56
ILLINOIS PRAIRIE PATH				
	16+16.33	19+18.59	RT	321.21
	14+45.04	14+67.43	RT	22.72
		South Side IPP RT		200.00
		South Side IPP LT		200.00
		TOTAL		1806

X0322859 WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE		
Project Area	LB	
	300	
	TOTAL	300

X0324451 INSTALL WATER SERVICE COMPLETE			
ADDRESS	MEASUREMENT	FROM	EACH
WESLEY STREET			
616 W.	44' N 9' W	NE corner of the house	1
619 W.	29' S 16' W	SW corner of the house	1
622 W.	42' N 7' E	NE corner of the porch	1
623 W.	34' S 11' E	SE corner of the house	1
626 W.	38' N	NW corner of the porch	1
627 W.	32' S 12' W	SW corner of the house	1
631 W.	43' S 14' E	SE corner of the house	1
703 W.	87' N 73' E	NE corner of the building	1
FRONT STREET			
617 W.	14' S 7' E	SW corner of the house	1
621 W.	25' S 4' W	SW corner of the house	1
BRIDGE STREET			
100	34' E 62' S	NE corner of the building	1
101	32' W 12' N	SW corner of the house	1
105	43' W 3' S	SW corner of the house	1
	TOTAL		13

X0323449 REMOVE EXISTING WATER VALVE			
STATION	OFFSET	LT/RT	EACH
GABLES BLVD			
32+40.00	11'	LT	1
32+51.00	12'	LT	1
WESTERN AVE			
61+02.00	25'	RT	1
61+25.00	9'	LT	1
	TOTAL		4

REVISIONS	
NAME	DATE

CITY OF WHEATON
 MANCHESTER ROAD / WESLEY STREET
 OVER UNION PACIFIC RAILROAD
 SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY DW
 HORIZ. CHECKED BY JLC
 DATE 6/4/2008