

P:\2005\LE05055A.dwg LE05055-TYP SECTION.dwg 5/8/2009 3:23:19 PM CDT

STORM SEWER PIPE SCHEDULE															
LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS			GRATING FOR CONC. FLARED END SEC. 30" EQUIV. (EACH)	STORM SEWERS, CLASS A, TYPE 1								STORM SEWERS, TYPE 1 REIN. CONC. ELLIPTICAL PIPE		STORM SEWERS CLASS A, TYPE 2
	15" (EACH)	30" EQUIV. (EACH)	42" EQUIV. (EACH)		12" (FOOT)	15" (FOOT)	18" (FOOT)	24" (FOOT)	30" (FOOT)	36" (FOOT)	42" (FOOT)	SPAN 38, RISE 24 (FOOT)	SPAN 53, RISE 34 (FOOT)	24" (FOOT)	
STA 33+58 TO 34+00 RT						42									
STA 34+00					75										
STA 34+00 TO 34+90 RT						90									
STA 34+90						68									
STA 34+90 TO 36+45 RT							155								
STA 36+45						75									
STA 36+45 TO 38+20 RT							175								
STA 38+20						75									
STA 38+20 TO 39+54 RT							134								
STA 39+54			1			20						95			
STA 39+54 TO 40+60 RT										106					
STA 40+60						75									
STA 40+60 TO 41+90 RT										130					
STA 41+90						75									
STA 41+90 TO 42+75 RT										85					
STA 42+75											16				
STA 42+75 TO 43+20 RT													45		
STA 43+20						75									
STA 43+20 TO 44+40 RT													120		
STA 44+40						75									
STA 44+40 TO 46+00 RT														160	
STA 46+00 TO 48+75 RT														275	
STA 48+75						75									
STA 48+75 TO 50+55 RT													180		
STA 50+55						83									
STA 50+55 TO 51+70 RT													115		
STA 51+70						57									
STA 51+70 TO 52+30 RT							63								
STA 52+30 TO 52+86 RT							84								
STA 52+86 RT	1						33								
STA 53+74	1	1					51					168			
STA 53+74 TO 54+02 RT												28			
STA 54+55						50									
TOTAL	2	1	1	1	878	363	579	345	16	215	106	196	95	435	

PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING					
		LETTERS AND SYMBOLS (SQ FT)	LINE 4" (FOOT)	LINE 6" (FOOT)	LINE 8" (FOOT)	LINE 12" (FOOT)	
STA 34+17					104		CROSS WALK WHITE
STA 34+48 LT					60		CROSS WALK WHITE
STA 34+48 RT					60	14	CROSS WALK WHITE AND STOP BAR
STA 35+08						12	STOP BAR WHITE
STA 35+08 TO 36+23					115		LINE WHITE
STA 35+08 TO 36+76				442		6	LINE YELLOW
STA 35+32		15.6					LEFT ARROW WHITE
STA 35+99		15.6					LEFT ARROW WHITE
STA 36+23 TO 37+23					25		DOTTED LINE WHITE
STA 46+48					106	102	CROSS WALK WHITE
STA 46+77 RT					60	60	CROSS WALK WHITE AND STOP BAR
STA 47+07					100	96	CROSS WALK WHITE
STA 47+38						12	STOP BAR WHITE
STA 47+38 TO 48+76						138	LINE WHITE
STA 47+38 TO 52+60					1044		LINE YELLOW
STA 47+82		15.6					LEFT ARROW WHITE
STA 48+52		15.6					LEFT ARROW WHITE
STA 48+76 TO 50+20						36	DOTTED LINE WHITE
STA 48+86 TO 50+30						36	DOTTED LINE WHITE
STA 48+95 TO 50+15 RT						30	DOTTED LINE WHITE
STA 50+15 TO 52+54 RT						239	LINE WHITE
STA 50+30 TO 52+70						240	LINE WHITE
STA 50+54		15.6					LEFT ARROW WHITE
STA 50+54		11.5					THRU ARROW WHITE
STA 50+54		15.6					RIGHT ARROW WHITE
STA 51+45		15.6					LEFT ARROW WHITE
STA 51+45		11.5					THRU ARROW WHITE
STA 51+45		15.6					RIGHT ARROW WHITE
STA 52+36		15.6					LEFT ARROW WHITE
STA 52+36		11.5					THRU ARROW WHITE
STA 52+36		15.6					RIGHT ARROW WHITE
STA 52+54 TO 53+05 RT					81	45	LINE YELLOW
STA 52+60						12	STOP BAR WHITE
STA 52+70						12	STOP BAR WHITE
STA 52+72 TO 52+88 RT					48	48	CROSS WALK WHITE
STA 52+73						17	STOP BAR WHITE
STA 52+73 TO 53+15 LT						132	LINE YELLOW
STA 52+80 TO 52+96 LT					48	48	CROSS WALK WHITE
STA 52+91 LT						17	STOP BAR WHITE
STA 52+94					98	96	CROSS WALK WHITE
STA 53+83					138	132	CROSS WALK WHITE
STA 53+90						20	STOP BAR WHITE
STA 53+90 TO 55+00						110	LINE WHITE
STA 54+00						12	STOP BAR WHITE
STA 54+00 TO 57+88					1352	69	LINE YELLOW
STA 54+24		26					THRU/RIGHT ARROW WHITE

PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING					
		LETTERS AND SYMBOLS (SQ FT)	LINE 4" (FOOT)	LINE 6" (FOOT)	LINE 8" (FOOT)	LINE 12" (FOOT)	
STA 54+24		15.6					LEFT ARROW WHITE
STA 54+76		26					THRU/RIGHT ARROW WHITE
STA 54+76		15.6					LEFT ARROW WHITE
STA 55+00 TO 56+32						33	DOTTED LINE WHITE
STA 193+64 TO 194+79						115	LINE WHITE
STA 193+64 TO 197+41 LT					377		LINE WHITE
STA 193+64 TO 198+27 RT					463		LINE WHITE
STA 193+64 TO 198+35					942		LINE YELLOW
STA 193+64 TO 203+74	500						SKIP DASH YELLOW
STA 193+88		15.6					LEFT ARROW WHITE
STA 194+55		15.6					LEFT ARROW WHITE
STA 194+79 TO 196+23						36	DOTTED LINE WHITE
STA 194+91 TO 196+35						36	DOTTED LINE WHITE
STA 196+35 TO 198+45						210	LINE WHITE
STA 196+59		15.6					LEFT ARROW WHITE
STA 196+59		26					THRU/RIGHT ARROW WHITE
STA 197+35		15.6					LEFT ARROW WHITE
STA 197+35		26					THRU/RIGHT ARROW WHITE
STA 198+11		15.6					LEFT ARROW WHITE
STA 198+11		26					THRU/RIGHT ARROW WHITE
STA 198+35						12	STOP BAR WHITE
STA 198+45						16	STOP BAR WHITE
STA 198+76					147	144	CROSS WALK WHITE
STA 199+48					145	144	CROSS WALK WHITE
STA 199+75						12	STOP BAR WHITE
STA 199+75 TO 201+70 LT						195	LINE WHITE
STA 199+85						12	STOP BAR WHITE
STA 199+85 TO 202+68					762	14	LINE YELLOW
STA 199+90 TO 201+70						180	LINE WHITE
STA 200+09		15.6					RIGHT ARROW WHITE
STA 200+09		11.5					THRU ARROW WHITE
STA 200+09		15.6					LEFT ARROW WHITE
STA 200+24 TO 203+74 LT					350		LINE WHITE
STA 200+53 TO 202+68 RT					215		LINE WHITE
STA 200+78		15.6					RIGHT ARROW WHITE
STA 200+78		11.5					THRU ARROW WHITE
STA 200+78		15.6					LEFT ARROW WHITE
STA 201+46		15.6					RIGHT ARROW WHITE
STA 201+46		11.5					THRU ARROW WHITE
STA 201+46		15.6					LEFT ARROW WHITE
STA 201+70 TO 202+58						22	DOTTED LINE WHITE
STA 201+70 TO 203+74 LT						51	DOTTED LINE WHITE
STA 203+26 TO 203+74						48	LINE WHITE
STA 203+26 TO 203+74 RT					48		LINE WHITE
STA 203+26 TO 203+74					96		LINE YELLOW
STA 203+50		15.6					LEFT ARROW WHITE
TOTAL	500	573.4	6091	1114	2108	1290	194

FAU. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	41	6

CONTRACT NO. 87414
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

* BURNS ROAD WEST - FAU 6212
 ** 03-00058-00-FP

TYSON ENGINEERING, INC.

CONSULTING CIVIL ENGINEERS
 LAND SURVEYORS
 DESIGN FIRM LICENSE #04-001136

367 SOUTH SCHUYLER AVENUE
 KANKAKEE, ILLINOIS 60901
 PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only. Contractor shall be responsible for verifying all dimensions.

Information herein and herein is confidential.

REVISIONS			
NO.	DATE	BY	DESCRIPTION
1	3/12/07	MRG	PER IDOT REVIEW
2	4/13/07	MRG	PER IDOT REVIEW
3	4/9/09	MRG	PHASING
4	5/8/09	MRG	PER IDOT REVIEW

SCHEDULE OF QUANTITIES

PROPOSED IMPROVEMENTS FOR
BURNS ROAD WEST
 FROM BURNING BUSH DRIVE
 TO U.S. ROUTE 45/52

SECTION
 03-00058-00-FP

DATE:	1/29/07	JOB NO.	E05055
SCALE:	N/A	FILE NO.	
DRAWN BY:	MRG	SHEET	6
CHECKED BY:	SRM		41