

NOTE 1: WHEN (31) OR (33) IS SPECIFIED (40) AND (51) SHALL ALSO BE CONSTRUCTED. HMA BASE COURSE SHALL BE USED >1.8 m TO 3.66 m WIDTH. HMA PAVEMENT (FULL DEPTH) SHALL BE USED FOR WIDTHS >3.66 m.

STATION 17+300± TO 17+420±

NOTE 1

- OR AS SHOWN ON CROSS SECTIONS (1:4 MAX)
- ** OR AS SHOWN ON CROSS SECTIONS (1:3 MAX)
- *** 460 mm THICKNESS
- + VARIABLE SLOPE, 3.80% MAXIMUM

- LEGEND - EXISTING**
- ① P.C.C. PAVEMENT
 - ② P.C.C. WIDENING
 - ③ FLEXIBLE PAVEMENT
 - ④ HOT-MIX ASPHALT OVERLAY, VARIABLE DEPTH
- REMOVAL** [XXXXXX]
- ⑧ PAVEMENT REMOVAL
 - ⑨ PAVED SHOULDER REMOVAL (SPECIAL)
 - ⑪ MEDIAN REMOVAL
 - ⑫ COMBINATION CURB & GUTTER REMOVAL
 - ⑬ HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)

- LEGEND - PROPOSED SHOULDERS**
- ⑳ AGGREGATE SHOULDERS, TYPE B 150MM
 - ㉑ AGGREGATE SHOULDERS, TYPE B, (METRIC TON)
 - ㉒ HOT-MIX ASPHALT SHOULDERS, 200MM
 - ㉓ HOT-MIX ASPHALT SHOULDERS (M TON)


- BASE COURSE**
- ㉔ HOT-MIX ASPHALT BASE COURSE, 200MM
 - ㉕ HOT-MIX ASPHALT BASE COURSE, 250MM
 - ㉖ HOT-MIX ASPHALT BASE COURSE WIDENING, 250MM
 - ㉗ HOT-MIX ASPHALT BASE COURSE WIDENING, 200MM

- BINDER COURSE & LEVELING BINDER COURSE**
- ㉘ POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (38 mm)
 - ㉙ POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (51 mm)
 - ㉚ POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 (VARIABLE DEPTH)
 - ㉛ POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (VARIABLE DEPTH)

- SURFACE COURSE**
- ㉜ POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (38 mm)
 - ㉝ POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (51 mm)

- FULL DEPTH PAVEMENT**
- ㉞ HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 290MM

- MISC & STANDARDS**
- ㉟ TOPSOIL FURNISH AND PLACE, 100MM
 - ㊱ SUB-BASE GRANULAR MATERIAL, TYPE A
 - ㊲ COMBINATION CONC C&G, TYPE B-15.60
 - ㊳ PIPE UNDERDRAINS 100MM
 - ㊴ REFER TO STANDARD 482001 (TYPE C SUBBASE)
 - ㊵ STRIP REFLECTIVE CRACK CONTROL



NOTE 1

STATION 17+420 TO 17+673

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS ILLINOIS ROUTE 40

SCALE: NONE
DATE: 3/13/09

DRAWN BY: JRC, JDU
CHECKED BY: ECM