

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7768	09-00075-00-RS	CASS	12	1

CONTRACT NO. 93489

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
PLANS FOR PROPOSED  
SURFACE TRANSPORTATION / URBAN PROGRAM (W/TARP)

**CITY OF BEARDSTOWN**  
**SECTION 09-00075-00-RS**

F.A.U ROUTE 7768  
PROJECT ARA-M-5002(021)

4th STREET  
FROM STATE STREET  
EASTERLY TO THE CORPORATE LIMITS

JOB NO C-96-234-09

INDEX OF SHEETS

1	COVER SHEET & REQUIRED STANDARDS
2	GENERAL NOTES AND LEGEND
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	SCHEDULE OF QUANTITIES
6-11	PLAN SHEETS
12	SPECIAL DETAILS

STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 606001-04 CONCRETE CURB, TYPE B, AND COMBINATION CONCRETE CURB AND GUTTER
- 701301-03 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701311-03 LANE CLOSURE, 2L, 2W MOVING OPERATIONS-DAY ONLY
- 701501-05 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701801-04 LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAILS
- 720006-02 SIGN PANEL ERECTIONS DETAILS
- 728001-01 TELESCOPING STEEL SIGN SUPPORT
- 780001-02 TYPICAL PAVEMENT MARKINGS
- BLR 24-2 MAILBOX TURNOUTS FOR LOCAL ROADS

GAS & ELECTRIC

AMEREN CIPS  
104 EAST 3rd ST ST  
BEARDSTOWN, ILLINOIS 62618

TELEPHONE

AMERITECH  
306 WEST 3rd ST  
BEARDSTOWN, ILLINOIS 62618

CABLE T.V.

CASS CABLE CO TV INC  
1 REDBIRD RD  
VIRGINIA, ILLINOIS 62691

WATER & SEWER



CITY OF BEARDSTOWN  
CITY HALL  
105 WEST 3rd ST  
BEARDSTOWN, ILLINOIS 62618

RAILROAD OMISSION  
STA 21+27.70 to  
STA 21+37.70

RAILROAD OMISSION  
STA 19+19.60 to  
STA 19+28.60

SECTION 09-00075-00-RS  
BEGINS  
STA 1+18.00

SECTION 09-00075-00-RS  
ENDS  
STA 66+50.00




FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.  
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION  
1-800-892-0123 OR 811

DESIGN DESIGNATION  
FAU 7768  
URBAN COLLECTOR (LAPP)  
ADT = 7,750 (2029)  
% PV = 88  
% SU = 7  
% MU = 5

TOTAL LENGTH OF PROJECT = 6,532.00 FEET = 1.237 MILES  
NET LENGTH OF PROJECT = 6,513.00 FEET = 1.234 MILES

DESCRIPTION OF WORK  
THIS PROJECT CONSISTS OF RESURFACING 4th STREET TO PROVIDE A 32' AND VARIABLE WIDE STREET. THE EXISTING HOT-MIX ASPHALT SURFACE WILL BE MILLED AT A VARIABLE DEPTH TO CORRECT THE ROADWAY CROWN. THE PROPOSED SURFACE CONSISTS OF 1 1/2" OF HOT-MIX ASPHALT SURFACE OVER AN 1 1/2" AND VARIABLE THICKNESS OF HOT-MIX ASPHALT LEVELING BINDER COURSE. ALSO INCLUDED IS AGGREGATE SHOULDERS, CURB AND GUTTER REMOVAL AND REPLACEMENT, SIDEWALK REMOVAL AND REPLACEMENT, DRIVEWAYS AND OTHER RELATED WORK.



Hutchison Engineering, Inc.  
1801 West Lafayette  
PO Box 850  
Jacksonville, Illinois 62651  
PHONE : (217)245-7164 FAX (217)243-0468

APPROVED	<u>3/21/09</u> <i>Robert Walter</i> MAYOR - CITY OF BEARDSTOWN
PASSED	<u>5/21/09</u> <i>Jimmy Lee</i> DISTRICT SIX ENGINEER OF LOCAL ROADS & STREETS
PASSED	<u>5/21/2009</u> <i>Ken Schamber</i> DISTRICT SIX ENGINEER OF CONSTRUCTION
RELEASING FOR BID BASED ON LIMITED REVIEW	<u>5/21/09</u> <i>Roger D. Suskell</i> DEPUTY DIRECTOR OF HIGHWAYS, REGION FOUR ENGINEER

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION