

SCHEDULE OF QUANTITIES  
ITEM

CODE NO.	ITEM	UNIT	TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,753
40600300	AGGREGATE (PRIME COAT)	TON	1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	388
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	321
40600990	TEMPORARY RAMP	SQ YD	84
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,221
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5,220
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	99
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	90
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	199
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,000
48101200	AGGREGATE SHOULDERS, TYPE B	TON	27
60255500	MANHOLES TO BE ADJUSTED	EACH	9
60266600	VALVE BOXES TO BE ADJUSTED	EACH	14
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,121
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	159
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,884
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	113
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	115
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	187
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,035
72000100	SIGN PANEL - TYPE 1	SQ FT	15
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	32
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,884
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	113
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	115
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	127
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	160
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

• SEE SPECIAL PROVISIONS  
NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE I000  
Δ SPECIALTY ITEMS

FILE NAME = VA\2713\2713S001.dgn	USER NAME = russell	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EAST VANDALIA ROAD (FAU ROUTE 8178) SUMMARY OF QUANTITIES</b>			F.A.U. RTE. 8178	SECTION 09-00020-00-RS	COUNTY MORGAN	TOTAL SHEETS 9	SHEET NO. 3
	PLOT SCALE = 1.0000' / IN.	DRAWN - RLR	REVISED -		SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. N/A TO STA. N/A	CONTRACT NO 93491				
	PLOT DATE = 5/5/2009	CHECKED - JRB	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - 2009	REVISED -									