

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9124	05-00085-01-FP 05-00085-02-FP	MADISON	61	3
SUMMARY OF QUANTITIES - SPRING STREET				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	86
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	158
20100500	TREE REMOVAL, ACRES	ACRE	0.1
S 20200100	EARTH EXCAVATION	CU YD	7,918
S 20800150	TRENCH BACKFILL	CU YD	1,403
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7,260
25000110	SEEDING, CLASS 1A	ACRE	1.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135
25100115	MULCH, METHOD 2	ACRE	1.5
25100630	EROSION CONTROL BLANKET	SQ YD	1077
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300
28000300	TEMPORARY DITCH CHECKS	EACH	9
28000400	PERIMETER EROSION BARRIER	FOOT	1,334
28000500	INLET AND PIPE PROTECTION	EACH	75
28100105	STONE RIPRAP, CLASS A3	SQ YD	25
28100107	STONE RIPRAP, CLASS A4	SQ YD	816
28200200	FILTER FABRIC	SQ YD	841
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	11,286
30201500	LIME	TON	217
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	395
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	169
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	400
40600895	CONSTRUCTING TEST STRIP	EACH	1
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	187
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	10,229
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	761
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	381
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	13,663
42400800	DETECTABLE WARNINGS	SQ FT	48
44000100	PAVEMENT REMOVAL	SQ YD	14
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,500
44000400	GUTTER REMOVAL	FOOT	708

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
44000600	SIDEWALK REMOVAL	SQ FT	4,650
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
S 50104400	CONCRETE HEADWALL REMOVAL	EACH	3
50105220	PIPE CULVERT REMOVAL	FOOT	1,233
S 50901760	PIPE HANDRAIL	FOOT	143
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	1
S 54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	24
S 54010905	PRECAST CONCRETE BOX CULVERT 9' X 5'	FOOT	1,517
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	716
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	8
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	62
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	57
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	105
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	11
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	309
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	647
60100905	PIPE DRAINS 4"	FOOT	100
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	8
S 60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	8
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	17
S 60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	7
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	3
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	19
S 60242400	INLETS, SPECIAL	EACH	3
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	11
60500060	REMOVING INLETS	EACH	5
S 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,914

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	417
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	200
67100100	MOBILIZATION	L SUM	1
S 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	732
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	285
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	69
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
S X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	128
S X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	76
S XX004102	CONCRETE RIPRAP REMOVAL	SQ YD	266
S Z0012450	CONCRETE STEPS	CU YD	16
S XX003086	BLOCK RETAINING WALL	SQ FT	497

NOTES:

- S SEE SPECIAL PROVISIONS
- * SPECIALTY ITEM