

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9124	05-00085-01-PP 05-00085-02-PP	MADISON	61	7
SCHEDULES - SPRING STREET				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

CONCRETE STEP SCHEDULE

STATION (NOTE 1)	OFFSET	SIDEWALK WIDTH (FOOT)	NUMBER OF STEPS	TREAD DIMENSION (INCH)	RISER DIMENSION (INCH)	PIPE HANDRAIL (FT)	CONCRETE STEPS (CU YD)
12+38.50	RT	3.5	2	12	6 3/4		1.0
12+74.50	LT	5.0	3	12	6		1.6
14+64	RT	3.5	3	12	6 1/4		1.2
14+78.50	LT	4.0	2	12	5 1/2		0.9
15+18	LT	4.5	2	12	6		1.1
15+72.5	RT	3.0	2	12	4 1/2		0.5
16+18	RT	3.5	2	12	7 1/2		1.1
16+64	RT	3.0	2	12	6 3/4		0.8
18+76.50	LT	3.5	2	12	5		0.7
18+89	LT	2.0	2	12	8		0.6
19+56	LT	2.5	5	12	6 1/4	14	1.3
20+70.50	RT	4.5	5	12	7	13	2.6
20+80	RT	4.0	8	12	7 1/4	20	2.3
TOTAL						47	16

ENTRANCE NOTES:

- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONTACT EACH PROPERTY OWNER AND VERIFY THE LOCATION AND WIDTH OF ALL APPROACH SIDEWALKS.

TREE REMOVAL SCHEDULE

STATION	STATION	OFFSET	TREE REMOV 6-15 (UNIT)	TREE REMOV OVER 15 (UNIT)	TREE REMOV ACRES (ACRE)
18+09		LT	8		
19+74		LT	8		
22+18		RT		24	
22+60		RT		16	
22+81		RT		20	
23+10	23+48	RT			0.02
24+69	25+48	LT			0.03
27+04		LT		30	
27+42		LT	10		
28+03		LT		16	
29+53		LT	10		
29+54		LT	10		
29+55		LT		18	
29+89		LT	14		
29+94		LT	8		
30+24		LT	10		
30+69		LT		18	
31+27		LT		16	
38+14	41+10	LT			0.08
40+55		LT	8		
TOTAL			86	158	0.1

EARTHWORK SCHEDULE

STATION	STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (NOTE 1) (CU YD)	EMBANKMENT (NOTE 2) (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (NOTE 3) (CU YD)	TOPSOIL FURNISH & PLACE 4" (SQ YD)
11+76	41+50	7,918	5,939		5,939	7,260
TOTAL		7,918	5,939		5,939	7,260

EARTHWORK NOTES:

- ESTIMATED SHRINKAGE FACTOR = 25%.
- APPROXIMATE EMBANKMENT QUANTITY IS SHOWN FOR INFORMATION ONLY.
- APPROXIMATE EARTHWORK BALANCE IS SHOWN FOR INFORMATION ONLY.

SIDEWALK SCHEDULE

STATION	STATION	OFFSET	PC CONC SIDEWALK 4 (NOTE 1) (SQ FT)	DETECTABLE WARNINGS (NOTE 1) (SQ FT)
12+25	17+07	RT	2,135	8
12+25	17+06	LT	2,029	8
17+44	25+00	LT	2,643	16
17+45	21+99	RT	2,264	8
25+75	37+39	LT	4,592	8
TOTAL			13,663	48

SIDEWALK NOTES:

- SIDEWALK RAMPS ACCESSIBLE TO THE DISABLED ARE REQUIRED. SEE PLAN SHEETS FOR LOCATIONS AND TYPES. SEE HIGHWAY STANDARD 424001 FOR SIDEWALK RAMP DETAILS. RAMPS ARE MEASURED AND PAID FOR AS PC CONC SIDEWALK, 4"

PAVEMENT MARKING SCHEDULE

STATION	STATION	LT/RT	THPL PVT MK LINE 4 (YELLOW) (NOTE 1 & 2) (FOOT)	THPL PVT MK LINE 12 (WHITE) (NOTE 1) (FOOT)	THPL PVT MK LINE 24 (WHITE) (NOTE 1) (FOOT)
12+25	41+53	CL	732		
16+98	17+52	LT		54	
16+98	17+52	RT		54	
17+06	17+44	LT		38	
17+06	17+44	RT		38	
17+09	17+25	LT			16
17+25	17+41	RT			16
25+22	25+78	LT		59	
25+33	25+72	LT		42	
25+38	25+52	LT			13
41+46	41+47	RT			24
TOTAL			732	285	69

PAVEMENT MARKING NOTES:

- SEE HIGHWAY STANDARD 780001 FOR PAVEMENT MARKING DETAILS.
- THE 4" YELLOW LINE WILL BE A SKIP DASH 10' LONG FOLLOWED BY A 30' GAP