

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
20200100	EARTH EXCAVATION	CU YD	2,385
20400800	FURNISHED EXCAVATION	CU YD	18,966
20800150	TRENCH BACKFILL	CU YD	191
25000200	SEEDING, CLASS 2	ACRE	9
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	810
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	810
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	810
25100115	MULCH, METHOD 2	ACRE	9.0
25100630	EROSION CONTROL BLANKET	SQ YD	2,937
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900
28000300	TEMPORARY DITCH CHECKS	EACH	29
28000400	PERIMETER EROSION BARRIER	FOOT	12,241
28000500	INLET AND PIPE PROTECTION	EACH	113
28100105	STONE RIPRAP, CLASS A3	SQ YD	249
28200200	FILTER FABRIC	SQ YD	249
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3,946
30201500	LIME	TON	114
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	3,946
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	19
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	460
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3
42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	2,970
42001200	PAVEMENT FABRIC	SQ YD	2,970
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	405
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	36
44000100	PAVEMENT REMOVAL	SQ YD	77
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	26
44000300	CURB REMOVAL	FOOT	103
44000400	GUTTER REMOVAL	FOOT	3,004
44004250	PAVED SHOULDER REMOVAL	SQ YD	4,598
48101200	AGGREGATE SHOULDERS, TYPE B	TON	47
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,286
50105220	PIPE CULVERT REMOVAL	FOOT	466
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	18
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	20

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
54207156	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	28
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	11
54213668	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	7
54223450	REMOVE AND RELAY PIPE CULVERTS 15"	FOOT	44
54248515	CONCRETE COLLAR	EACH	2
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS M 12"	FOOT	2,572
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS M 15"	FOOT	2,300
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS M 24"	FOOT	617
55020300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 36"	FOOT	15
55020400	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II 42"	FOOT	9
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	4,033
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	17
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	88
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	93
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	15,477
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	28
72900200	METAL POST - TYPE B	FOOT	69
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	20,500
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	502
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	177
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	164
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	382
78300100	PAVEMENT MARKING REMOVAL	SQ FT	9,742
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	161
81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	3
X0320547	REMOVE AND REINSTALL END SECTION	EACH	14
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1,939
X0322090	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	10
Δ Z0076800	TRAINEES	HOUR	500

* SPECIALTY ITEMS
Δ YOSCO

FILE NAME = 789SQ01.DWG	USER NAME = SAM WRIGLEY	DESIGNED - SSM	REVISED -	CITY OF BELLEVILLE, ILLINOIS 101 S. Illinois Street Belleville, IL 62220-2105	FRANK SCOTT PARKWAY WEST SUMMARY OF QUANTITIES	F.A.U. RTE. 9256	SECTION 09-00212-00-CG	COUNTY ST. CLAIR	TOTAL SHEETS 90	SHEET NO. 2	
PLOT SCALE = 1" = 1'	CHECKED - AJG	REVISIONS -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 97379			
PLOT DATE = 2009-04-30	DATE - 2009-01-30	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								