

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9249	09-00015-01-SW	ST. CLAIR	15	9
STA. 40+00.00		TO STA. 46+00.00		
FEDERAL AID PROJECT		CONTRACT 97385		

STA. 40+57, 22.5' LT.
30" CROSSWALK WARNING SIGN W11-2
WITH SUPPLEMENTAL PLAQUE W-16-7p (ARROW)
SIGN PANEL - TYPE 1, 8.25 S.F.
METAL POST - TYPE A, 12 FT.

COMBINATION CURB AND GUTTER REMOVAL, 14 FT.
COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18, 14 FT.

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x8'), 12 S.F.

RONALD R. HALL JR.
& JOY L. HALL
05-18-306-011

PCC SIDEWALK, 4" (TYP.)

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x4'), 8 S.F.

CLOVER DRIVE

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x4'), 8 S.F.

JOYCE L. FURTKAMP
& JAMES F. FURTKAMP
05-18-304-014

PCC SIDEWALK, 4" (TYP.)

LARRY D. SMITH &
LISA K. SMITH
05-18-304-007

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x4'), 8 S.F.

HILLCREST DRIVE

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x4'), 8 S.F.

MATCH LINE 40+00

MATCH LINE 46+00

EXISTING CONCRETE SIDEWALK

PEARL STREET

E. LUCILLE STEVENSON TRUST
05-19-114-001

THERMOPLASTIC PAVEMENT MARKING - LINE 6"
56 FT. (WHITE-CROSSWALK)

THERMOPLASTIC PAVEMENT MARKING - LINE 24"
30 FT. (WHITE-CROSSWALK) (TYP.)

THERMOPLASTIC PAVEMENT MARKING - LINE 6"
92 FT. (WHITE-CROSSWALK)

EXISTING SIGN TO BE REMOVED
AND REINSTALLED (TYP.)
INCLUDED IN COST OF PCC SIDEWALK

THERMOPLASTIC PAVEMENT MARKING - LINE 6"
90 FT. (WHITE-CROSSWALK)

PROPOSED TYPE B CURB RAMP
W/DETECTABLE WARNINGS (2'x4'), 8 S.F.

STA. 41+77, 22.5' LT.
30" CROSSWALK WARNING SIGN W11-2
WITH SUPPLEMENTAL PLAQUE W-16-9p (AHEAD)
SIGN PANEL - TYPE 1, 8.25 S.F.
METAL POST - TYPE A, 12 FT.

WELCH ENTERPRISES LP
05-18-300-020

STA. 40+40, 22.5' RT.
30" CROSSWALK WARNING SIGN W11-2
WITH SUPPLEMENTAL PLAQUE W-16-7p (ARROW)
SIGN PANEL - TYPE 1, 8.25 S.F.
METAL POST - TYPE A, 12 FT.

EXISTING CURB RAMP
W/DETECTABLE WARNINGS (TYP.)

SCALE:
PLAN: 1" = 20'
PROFILE: 1" = 20' HORIZ.
1" = 5' VERT.

NOTE: SEE SCHEDULES FOR QUANTITIES

