

SBI ROUTE 150 (OLD IL ROUTE 3)				FUNDING (HBP) 80% FEDERAL 20% STATE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL	X032-2A
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	30	30
42001300	PROTECTIVE COAT	SQ. YD.	210	210
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ. YD.	160	160
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ. YD.	37	37
44000100	PAVEMENT REMOVAL	SQ. YD.	37	37
44000700	APPROACH SLAB REMOVAL	SQ. YD.	186	186
50102400	CONCRETE REMOVAL	CU. YD.	40.4	40.4
50104800	REMOVAL OF EXISTING CONCRETE DECK	L. SUM	1	1
50157300	PROTECTIVE SHIELD	SQ. YD.	1275	1275
50200100	STRUCTURE EXCAVATION	CU. YD.	28.5	28.5
50300100	FLOOR DRAINS	EACH	21	21
50300225	CONCRETE STRUCTURES	CU. YD.	48.7	48.7
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	197.8	197.8
50300260	BRIDGE DECK GROOVING	SQ. YD.	774	774
50300300	PROTECTIVE COAT	SQ. YD.	953	953
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	36	36
50501130	STRUCTURAL STEEL REPAIR	POUND	34110	34110
50600300	CLEANING AND PAINTING STEEL BRIDGE	L. SUM	1	1
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L. SUM	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	54210	54210
50800515	BAR SPLICERS	EACH	51	51
51500100	NAME PLATES	EACH	1	1

SBI 150 (OLD IL ROUTE 3)				FUNDING (HBP) 80% FEDERAL 20% STATE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL	X032-2A
52000110	PREFORMED JOINT STRIP SEAL	FOOT	106	106
52100510	ANCHOR BOLTS, 3/4"	EACH	72	72
58700300	CONCRETE SEALER	SQ. FT.	986	986
59000200	EPOXY CRACK INJECTION	FOOT	80	80
* 63300115	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, SINGLE RAIL	FOOT	400	400
* 63300640	REMOVAL AND REPLACEMENT OF TERMINAL SECTION, SINGLE RAIL	EACH	4	4
* 63500105	DELINEATORS	EACH	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	9	9
67100100	MOBILIZATION	L. SUM	1	1
70101855	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 (SPECIAL)	L. SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL. MO.	2	2
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3300	3300
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	10	10
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ. FT.	21.0	21.0
Z0053800	RIVET REMOVAL AND REPLACEMENT	EACH	350	350
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	8	8

*Specialty Items

FILE NAME = ...\\W01\Roadway\Sheets\summary.dgn	USER NAME = Plotted by Administrator	DESIGNED - KHH	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES OLD IL ROUTE 3 OVER SEXTON CREEK				S.B.I. RTE. 150	SECTION (133A)D, I	COUNTY ALEXANDER	TOTAL SHEETS 32	SHEET NO. 3
	PLOT SCALE = 1/2" = 100' IN.	DRAWN - KHH	REVISED - ---		SCALE: N.T.S.	SHEET NO. ___ OF ___ SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
	PLOT DATE = 4/16/2009	CHECKED - FML	REVISED - ---		CONTRACT NO. 98910								
		DATE - 11/2008	REVISED - ---										