

SUMMARY OF QUANTITIES

90% FED. / 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY												TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
				ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS					
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F				
4400500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,333	2,236					30	67									
4400600	SIDEWALK REMOVAL	SQ FT	2,626	2,626															
44003100	MEDIAN REMOVAL	SQ FT	334	334															
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	2,608	2,608															
44004000	PAVED DITCH REMOVAL	FOOT	75			75													
44004250	PAVED SHOULDER REMOVAL	SQ YD	12,059	221	9,165	2,673													
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	32	32															
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	39	39															
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	1,083	831					252										
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	71						71										
44201869	CLASS D PATCHES, TYPE IV, 18 INCH	SQ YD	352	352															
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,118		1,118														
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	3,968	1,360						2,608									
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	4,020			338	903	171	2,608										
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	9,150	393	372	4,339	3,642	290	114										
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	7,695		7,695														
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1							1									
50102400	CONCRETE REMOVAL	CU YD	123								69					54			
50104400	CONCRETE HEADWALL REMOVAL	EACH	10	3		3		2	2										
50105220	PIPE CULVERT REMOVAL	FOOT	3090	1,626		245		1,104	115										
50200100	STRUCTURE EXCAVATION	CU YD	2,276							1,104					272	900			
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2,619	2,520												99			
50300225	CONCRETE STRUCTURES	CU YD	563.4							137.8					140.7	264.9			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	347							341	6								
50300260	BRIDGE DECK GROOVING	SQ YD	1579							1,042	337								
50300300	PROTECTIVE COAT	SQ YD	2,153							1,453	590				54	56			
50300510	RUSTICATION FINISH	SQ FT	2,591												1,422	1,169			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1							1									
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,640													1,640			
50500505	STUD SHEAR CONNECTORS	EACH	3,204							3,204									
50800105	REINFORCEMENT BARS	POUND	57,500							21,690						35,810			

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 3

SCALE: _____ DRAWN BY: JB
DATE: 03/14/08 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS & ARCHITECTS/PLANNERS
260 N. MICHIGAN AVE. CHICAGO, IL 60611
TEL: (312) 281-2000 FAX: (312) 281-2001

Rev. 7-17-08

Rev.

\S:\0000055.DGN... \S:\0000055.DGN... \T:\0000055.DGN...
 3-24-2008 10:37:49
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63