F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
* (26, 26HB-1&114) R-2		CONTRACT NO. 60363		

SUMMARY OF QUANTITIES

90% FED./10% STATE

				WILL COUNTY														
			URBAN	ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	90% FED./10% STATE RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F	J000-2A	Y007	J000-2A
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4														
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	2					2										
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3														
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2					2										
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	10	9			1	8										
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1					1										
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	1				1										
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	39	35				4										
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1														
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1															1
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2															2
60266600	VALVE BOXES TO BE ADJUSTED	EACH	7															7
60400105	FRAMES, TYPE 1	EACH	7														7	
60403800	LIDS, TYPE 1, CLOSED LID	EACH	7														7	
60600605	CONCRETE CURB, TYPE B	FOOT	909	909														
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	32					32										
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	13,993	11,276		704	283	1,730										
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	75			75												
60616110	PAVED DITCH, TYPE A-30	FOOT	45	45														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	486	486														
X0326017	CONCRETE MEDIAN SURFACE, 5 INCH (SPECIAL)	SQ FT	13,720	9,192														4,528
60624600	CORRUGATED MEDIAN	SQ FT	458	458														
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	6268 △1		342	3,450	485		235 △1						1,756		
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	357		357													
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	11 △1	1	4	1	2		1 △1						2		
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2			2											
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4			2									2		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8 △1		4		1		1 △1						2		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	3			2	1										
* 63200600	STEEL PLATE BEAM GUARD RAIL REMOVAL, SINGLE RAIL	FOOT	4,321	113	1,103	3,105											
* 63200700	STEEL PLATE BEAM GUARD RAIL REMOVAL, DOUBLE RAIL	FOOT	217			217											
63500105	DELINEATORS	EACH	206	14	24	63	45	8	52								

* DENOTES SPECIALTY ITEMS

△1 Rev. 7-17-09

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 7

SCALE:
DRAWN BY: JB
DATE: 03/14/08
CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
200 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/856-0900

..\SU000R55.DGN,..\SU000RR3.DGN,..\TTB00RRN.DGN
3-24-2008,063748 T:\DOCUMENT\932790\CIVIL\DGN\SU000500.DGN
BONDHULO