F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

SUMMARY OF QUANTITIES

90% FED./10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	WILL COUNTY: ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	90% FED./10% STATE: RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
				CONSTRUCTION TYPE CODE														
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F	J000-2A	Y007	J000-2A
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,333	2,236				30	67									
44000600	SIDEWALK REMOVAL	SQ FT	2,626	2,626														
44003100	MEDIAN REMOVAL	SQ FT	334	334														
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	2,608	2,608														
44004000	PAVED DITCH REMOVAL	FOOT	75			75												
44004250	PAVED SHOULDER REMOVAL	SQ YD	12,059	221	9,165	2,673												
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	32	32														
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	39	39														
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	1,083	831				252										
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	71					71										
44201869	CLASS D PATCHES, TYPE IV, 18 INCH	SQ YD	352	352														
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,118		1,118													
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	3,968	1,360					2,608									
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	4,020			338	903	171	2,608									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	9,036	393	372	4,339	3,642	290										
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	7,695		7,695													
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1							1								
50102400	CONCRETE REMOVAL	CU YD	123								69						54	
50104400	CONCRETE HEADWALL REMOVAL	EACH	10	3		3		2	2									
50105220	PIPE CULVERT REMOVAL	FOOT	3,131	1,626		286		1,104	115									
50200100	STRUCTURE EXCAVATION	CU YD	2,276							1,104						272	900	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2,619	2,520													99	
50300225	CONCRETE STRUCTURES	CU YD	563.4							137.8						160.7	264.9	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	347							341	6							
50300260	BRIDGE DECK GROOVING	SQ YD	1379							1,042	337							
50300300	PROTECTIVE COAT	SQ YD	2,153							1,453	590					54	56	
50300510	RUSTICATION FINISH	SQ FT	2,591													1,422	1,169	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1							1								
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,640														1,640	
50500505	STUD SHEAR CONNECTORS	EACH	3,204							3,204								
50800105	REINFORCEMENT BARS	POUND	56,310							21,690							34,620	

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 3

SCALE: DRAWN BY: JB

DATE: 03/14/08 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE 312/616-0000

..\SU000RS5.DGN..\SU000RR3.DGN..\TTB00RR.DGN T:\DOCUMENT\932790\CIVIL\DGN\SU000SU08.DGN BONDHUJO
3-24-2008, 10:37:49