F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

SUMMARY OF QUANTITIES

90% FED./10% STATE

				WILL COUNTY												90% FED./10% STATE		
			URBAN	ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE														
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F	J000-2A	Y007	J000-2A
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	118,750							88,220	880					15,210	14,440	
50800515	BAR SPLICERS	EACH	60							56	4							
51205200	TEMPORARY SHEET PILING	SQ FT	120	120														
* 51603000	DRILLED SHAFT IN SOIL	CU YD	114							114								
* 51604000	DRILLED SHAFT IN ROCK	CU YD	4.2							4.2								
~~52000050~~	~~PREFORMED JOINT SEAL 4"~~	~~FOOT~~	~~162~~								~~162~~							
52000110	PREFORMED JOINT STRIP SEAL	FOOT	60							60								
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12							12								
52100520	ANCHOR BOLTS, 1"	EACH	24							24								
52100540	ANCHOR BOLTS, 1 1/2 "	EACH	12							12								
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2														2	
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2														2	
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	2			1	1											
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	2													2		
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	718			202										516		
54020402	PRECAST CONCRETE BOX CULVERT 4' X 2' (M273)	FOOT	252														252	
54020503	PRECAST CONCRETE BOX CULVERT 5' X 3' (M273)	FOOT	104														104	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	39	24		1		10	4									
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	11	6		2	1	2										
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2				2											
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	4			2											
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	3	1		2												
54213865	STEEL END SECTIONS 10"	EACH	2					2										
54213870	STEEL END SECTIONS 15"	EACH	2					2										
54213873	STEEL END SECTIONS 18"	EACH	1	1														
54213891	STEEL END SECTIONS 36"	EACH	4					4										
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1					1										
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	11				2	9										
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	3					1	2									
54215967	REINFORCED CONCRETE PIPE ELBOW 12"	EACH	6	6														
54215970	REINFORCED CONCRETE PIPE ELBOW 15"	EACH	2	2														

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 4

SCALE:
DATE: 03/14/08
DRAWN BY: JB
CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-616-0300

\\SU000R55.DGN \\SU000R53.DGN \\TTB00RW.DGN
3-24-2008 13:07:50 T:\DOCUMENT\B32790\CIVIL\DGN\SU000S09.DGN
BONDHULO 6575859 6096 6263