F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	27
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

LOCATION STATION TO STATION		TOPSOIL EXCAVATION (CU YD)				EARTH EXCAVATION (ALL SUITABLE) (CU YD)				EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)				EMBANKMENT (CU YD)				EARTHWORK BALANCE (CU YD)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)			
INTERSTATE 55		STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4
83+00.00	84+00.00	98.2	0.0	0.0	0.0	108.9	0.0	0.0	0.0	92.6	0.0	0.0	0.0	21.6	0.0	0.0	0.0	71.0	0.0	0.0	0.0	89.1	0.0	0.0	0.0
84+00.00	85+00.00	149.2	0.0	0.0	0.0	143.7	0.0	0.0	0.0	122.1	0.0	0.0	0.0	46.4	0.0	0.0	0.0	75.7	0.0	0.0	0.0	136.3	0.0	0.0	0.0
85+00.00	86+00.00	228.6	0.0	0.0	0.0	205.5	0.0	0.0	0.0	174.7	0.0	0.0	0.0	52.4	0.0	0.0	0.0	122.3	0.0	0.0	0.0	213.0	0.0	0.0	0.0
86+00.00	87+00.00	240.8	0.0	0.0	0.0	162.3	0.0	0.0	0.0	138.0	0.0	0.0	0.0	71.4	0.0	0.0	0.0	66.5	0.0	0.0	0.0	229.6	0.0	0.0	0.0
87+00.00	88+00.00	219.5	0.0	0.0	0.0	139.5	0.0	0.0	0.0	118.6	0.0	0.0	0.0	124.1	0.0	0.0	0.0	-5.6	0.0	0.0	0.0	206.0	0.0	0.0	0.0
88+00.00	89+00.00	266.9	0.0	0.0	0.0	138.4	0.0	0.0	0.0	117.6	0.0	0.0	0.0	196.0	0.0	0.0	0.0	-78.3	0.0	0.0	0.0	240.4	0.0	0.0	0.0
89+00.00	90+00.00	308.7	0.0	0.0	0.0	137.7	0.0	0.0	0.0	117.0	0.0	0.0	0.0	234.4	0.0	0.0	0.0	-117.3	0.0	0.0	0.0	271.1	0.0	0.0	0.0
90+00.00	91+00.00	340.3	0.0	0.0	0.0	151.6	0.0	0.0	0.0	128.9	0.0	0.0	0.0	243.3	0.0	0.0	0.0	-114.4	0.0	0.0	0.0	294.4	0.0	0.0	0.0
91+00.00	92+00.00	381.9	0.0	0.0	0.0	176.8	0.0	0.0	0.0	150.2	0.0	0.0	0.0	268.4	0.0	0.0	0.0	-118.2	0.0	0.0	0.0	324.9	0.0	0.0	0.0
92+00.00	93+00.00	395.2	0.0	0.0	0.0	187.0	0.0	0.0	0.0	159.0	0.0	0.0	0.0	281.3	0.0	0.0	0.0	-122.3	0.0	0.0	0.0	335.1	0.0	0.0	0.0
93+00.00	94+00.00	381.3	0.0	0.0	0.0	179.8	0.0	0.0	0.0	152.8	0.0	0.0	0.0	279.8	0.0	0.0	0.0	-127.0	0.0	0.0	0.0	325.1	0.0	0.0	0.0
94+00.00	95+00.00	283.8	0.0	0.0	0.0	129.7	0.0	0.0	0.0	110.2	0.0	0.0	0.0	182.9	0.0	0.0	0.0	-72.6	0.0	0.0	0.0	242.9	0.0	0.0	0.0
95+00.00	96+00.00	96.6	0.0	0.0	0.0	42.3	0.0	0.0	0.0	35.9	0.0	0.0	0.0	44.2	0.0	0.0	0.0	-8.3	0.0	0.0	0.0	82.9	0.0	0.0	0.0
96+00.00	97+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
97+00.00	98+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
98+00.00	99+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
99+00.00	100+00.00	39.0	0.0	0.0	0.0	51.2	0.0	0.0	0.0	43.5	0.0	0.0	0.0	38.9	0.0	0.0	0.0	4.6	0.0	0.0	0.0	32.6	0.0	0.0	0.0
100+00.00	101+00.00	78.0	0.0	0.0	0.0	100.5	0.0	0.0	0.0	85.4	0.0	0.0	0.0	75.6	0.0	0.0	0.0	9.8	0.0	0.0	0.0	64.6	0.0	0.0	0.0
101+00.00	102+00.00	74.9	0.0	0.0	0.0	76.6	0.0	0.0	0.0	65.1	0.0	0.0	0.0	72.6	0.0	0.0	0.0	-7.4	0.0	0.0	0.0	60.2	0.0	0.0	0.0
102+00.00	103+00.00	73.0	0.0	0.0	0.0	53.7	0.0	0.0	0.0	45.7	0.0	0.0	0.0	74.6	0.0	0.0	0.0	-28.9	0.0	0.0	0.0	56.4	0.0	0.0	0.0
103+00.00	104+00.00	37.2	0.0	0.0	0.0	26.4	0.0	0.0	0.0	22.4	0.0	0.0	0.0	38.7	0.0	0.0	0.0	-16.3	0.0	0.0	0.0	28.1	0.0	0.0	0.0
104+00.00	105+00.00	10.2	0.0	0.0	0.0	24.4	0.0	0.0	0.0	20.7	0.0	0.0	0.0	5.4	0.0	0.0	0.0	15.4	0.0	0.0	0.0	10.2	0.0	0.0	0.0
105+00.00	106+00.00	26.4	0.0	0.0	0.0	49.0	0.0	0.0	0.0	41.6	0.0	0.0	0.0	18.1	0.0	0.0	0.0	23.6	0.0	0.0	0.0	25.5	0.0	0.0	0.0
106+00.00	107+00.00	50.5	0.0	0.0	0.0	49.8	0.0	0.0	0.0	42.3	0.0	0.0	0.0	28.4	0.0	0.0	0.0	13.9	0.0	0.0	0.0	43.9	0.0	0.0	0.0
107+00.00	108+00.00	71.5	0.0	0.0	0.0	49.7	0.0	0.0	0.0	42.3	0.0	0.0	0.0	31.4	0.0	0.0	0.0	10.8	0.0	0.0	0.0	59.7	0.0	0.0	0.0
108+00.00	109+00.00	37.2	0.0	0.0	0.0	24.5	0.0	0.0	0.0	20.9	0.0	0.0	0.0	15.8	0.0	0.0	0.0	5.1	0.0	0.0	0.0	31.1	0.0	0.0	0.0
112+00.00	113+00.00	0.0	0.0	0.0	100.5	0.0	0.0	0.0	77.7	0.0	0.0	0.0	66.1	0.0	0.0	0.0	49.7	0.0	0.0	0.0	16.4	0.0	0.0	0.0	83.1
113+00.00	114+00.00	0.0	0.0	0.0	134.3	0.0	0.0	0.0	104.6	0.0	0.0	0.0	88.9	0.0	0.0	0.0	49.5	0.0	0.0	0.0	39.4	0.0	0.0	0.0	109.4
114+00.00	115+00.00	0.0	0.0	0.0	119.4	0.0	0.0	0.0	115.0	0.0	0.0	0.0	97.7	0.0	0.0	0.0	19.6	0.0	0.0	0.0	78.1	0.0	0.0	0.0	93.1
115+00.00	116+00.00	0.0	0.0	0.0	97.3	0.0	0.0	0.0	137.0	0.0	0.0	0.0	116.5	0.0	0.0	0.0	9.8	0.0	0.0	0.0	106.6	0.0	0.0	0.0	68.9
116+00.00	117+00.00	0.0	0.0	0.0	79.3	0.0	0.0	0.0	151.9	0.0	0.0	0.0	129.1	0.0	0.0	0.0	10.2	0.0	0.0	0.0	118.9	0.0	0.0	0.0	49.3
117+00.00	118+00.00	0.0	0.0	0.0	57.4	0.0	0.0	0.0	140.9	0.0	0.0	0.0	119.7	0.0	0.0	0.0	16.7	0.0	0.0	0.0	103.0	0.0	0.0	0.0	30.2
118+00.00	119+00.00	0.0	0.0	0.0	63.9	0.0	0.0	0.0	134.4	0.0	0.0	0.0	114.3	0.0	0.0	0.0	20.4	0.0	0.0	0.0	93.9	0.0	0.0	0.0	31.7
119+00.00	120+00.00	0.0	0.0	0.0	75.7	0.0	0.0	0.0	145.5	0.0	0.0	0.0	123.7	0.0	0.0	0.0	16.2	0.0	0.0	0.0	107.5	0.0	0.0	0.0	35.9
120+00.00	121+00.00	0.0	0.0	0.0	65.1	0.0	0.0	0.0	169.1	0.0	0.0	0.0	143.7	0.0	0.0	0.0	14.6	0.0	0.0	0.0	129.1	0.0	0.0	0.0	24.0
121+00.00	122+00.00	0.0	0.0	0.0	74.6	0.0	0.0	0.0	219.6	0.0	0.0	0.0	186.7	0.0	0.0	0.0	14.2	0.0	0.0	0.0	172.5	0.0	0.0	0.0	27.9
122+00.00	123+00.00	0.0	0.0	0.0	99.5	0.0	0.0	0.0	288.0	0.0	0.0	0.0	244.8	0.0	0.0	0.0	14.3	0.0	0.0	0.0	230.4	0.0	0.0	0.0	43.1
123+00.00	124+00.00	0.0	0.0	0.0	156.1	0.0	0.0	0.0	342.0	0.0	0.0	0.0	290.7	0.0	0.0	0.0	14.6	0.0	0.0	0.0	276.0	0.0	0.0	0.0	87.5
124+00.00	125+00.00	0.0	0.0	0.0	196.9	0.0	0.0	0.0	431.5	0.0	0.0	0.0	366.8	0.0	0.0	0.0	17.2	0.0	0.0	0.0	349.6	0.0	0.0	0.0	112.4
125+00.00	126+00.00	0.0	0.0	0.0	258.2	0.0	0.0	0.0	558.7	0.0	0.0	0.0	474.9	0.0	0.0	0.0	21.4	0.0	0.0	0.0	453.5	0.0	0.0	0.0	145.5
126+00.00	127+00.00	0.0	0.0	0.0	232.2	0.0	0.0	0.0	464.0	0.0	0.0	0.0	394.4	0.0	0.0	0.0	17.1	0.0	0.0	0.0	377.3	0.0	0.0	0.0	139.2
127+00.00	128+00.00	0.0	0.0	0.0	144.2	0.0	0.0	0.0	367.0	0.0	0.0	0.0	312.0	0.0	0.0	0.0	25.7	0.0	0.0	0.0	286.3	0.0	0.0	0.0	84.5
128+00.00	129+00.00	0.0	0.0	0.0	145.9	0.0	0.0	0.0	423.0	0.0	0.0	0.0	359.6	0.0	0.0	0.0	57.7	0.0	0.0	0.0	301.9	0.0	0.0	0.0	75.9
129+00.00	130+00.00	0.0	0.0	0.0	164.2	0.0	0.0	0.0	439.9	0.0	0.0	0.0	373.9	0.0	0.0	0.0	64.7	0.0	0.0	0.0	309.2	0.0	0.0	0.0	76.5
130+00.00	131+00.00	0.0	0.0	0.0	91.0	0.0	0.0	0.0	225.6	0.0	0.0	0.0	191.8	0.0	0.0	0.0	27.1	0.0	0.0	0.0	164.6	0.0	0.0	0.0	40.9
131+00.00	END	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	TOTALS	3,888.9	0.0	0.0	2,387.4	2,409.1	0.0	0.0	4,960.4	2,047.7	0.0	0.0	4,216.4	2,445.8	0.0	0.0	495.9	-398.0	0.0	0.0	3,720.5	3,403.4	0.0	0.0	1,385.6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 2

SCALE:
DATE: 03/14/08
DRAWN BY: JB
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL. 60601
TELEPHONE: 312/616-0033

ROADWAY
-\TTBOURNLD6N,..\SC0002_LLD.DGN
1:\DOCUMENT\N32790\CIVIL\DGN\SC0002TLD.DGN