F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	48
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH — TOTAL 9,457 FOOT

LOCATION LANE	"FROM STATION" LINES	"TO STATION" - 10'	"LENGTH " FT DASH	COLOR 30'	X SKIP	LENGTH	%	MOT STAGE	SUBTOTALS FOOT
I55 SB	79+24.96	98+00.00	1875.04	WHITE	2	3750.08	25%	STAGE 1	937.52
	98+00.00	111+00.00	1300.00	WHITE	2	2600.00	25%	STAGE 1	650.00
	111+00.00	113+74.07	274.07	WHITE	2	548.14	25%	STAGE 1	137.04
I55 NB	71+59.22	98+00.00	2640.78	WHITE	2	5281.56	25%	STAGE 1	1,320.39
	98+00.00	107+42.48	942.48	WHITE	2	1884.96	25%	STAGE 1	471.24
I55 SB	108+19.30	111+00.00	280.70	WHITE	2	561.40	25%	STAGE 4A	140.35
	111+00.00	126+00.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4A	750.00
	126+00.00	145+19.00	1,919.00	WHITE	2	3,838.00	25%	STAGE 4A	959.50
I55 NB	108+09.00	111+00.00	291.00	WHITE	2	582.00	25%	STAGE 4A	145.50
	111+00.00	126+00.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4A	750.00
	126+00.00	142+71.00	1,671.00	WHITE	2	3,342.00	25%	STAGE 4A	835.50
I55 SB	134+50.00	149+50.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4B	750.00
I55 NB	130+50.00	145+50.00	1,500.00	WHITE	2	3,000.00	25%	STAGE 4B	750.00

X0325841

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH — TOTAL 407 FOOT

LOCATION	"FROM STATION"	"TO STATION"	OFFSET	"LINE TYPE"	LENGTH FT	MEASURED BY CAD FT	"LINE WIDTH" FT	COLOR	MOT STAGE	SUBTOTALS FOOT
IL 59	7528+77.00		RT	SOLID		39	2	WHITE	STAGE 2A	39
SEIL	4010+52.70	4010+97.00	RT	SOLID	44.30		2	WHITE	STAGE 2A	44.3
SEIL	4010+89.00		LT	SOLID		14	2	WHITE	STAGE 2A	14
IL 59	7496+00.00		RT	SOLID		18	2	WHITE	STAGE 2A	18
IL 59	7496+00.00		RT	SOLID		23	2	WHITE	STAGE 2A	23
IL 59	2983+56.00		LT	SOLID		37	2	WHITE	STAGE 2B	37
SEIL	4009+25.00		RT	SOLID		20	2	WHITE	STAGE 3B	20
SEIL	4010+44.00	4010+87.00	RT	SOLID	43		2	WHITE	STAGE 3B	43
SEIL	4010+99.00		RT	SOLID		13	2	WHITE	STAGE 3B	13
SEIL	4018+10.00		RT	SOLID		61	2	WHITE	STAGE 3B	61
IL 59	7475+34.00		RT	SOLID		25	2	WHITE	STAGE 3B	25
IL 59	7476+32.00		LT	SOLID		33	2	WHITE	STAGE 3B	33
	PAVEMENT MARKING WEAR AND TEAR 10%									37

X0325837

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH — TOTAL 1,762 FOOT

STA.	STA.	LENGTH	TYPE OF LINE	STAGE	SUBTOTALS FOOT
7525+17.00	7527+68.00	251	2D-6S	PRESTAGE A	63
7525+17.00	7527+68.00	251	2D-6S	PRESTAGE A	63
7527+68.00	7528+77.00	109	SOLID	PRESTAGE A	109
7527+68.00	7528+77.00	109	SOLID	PRESTAGE A	109
7525+00.00	7527+68.00	268	2D-6S	PRESTAGE B	67
7525+00.00	7527+68.00	268	2D-6S	PRESTAGE B	67
1002+00.57	1003+33.61	133	2D-6S	PRESTAGE B	33
7525+17.00	7527+00.00	183	2D-6S	STAGE 1	46
7525+17.00	7527+00.00	183	2D-6S	STAGE 1	46
7527+00.00	7527+68.00	68	SOLID	STAGE 1	68
7527+00.00	7527+68.00	68	SOLID	STAGE 1	68
7525+26.00	7527+00.00	174	2D-6S	STAGE 2A	44
7527+00.00	7528+77.00	177	SOLID	STAGE 2A	177
7527+00.00	7528+77.00	177	SOLID	STAGE 2A	177
2983+56.00	2985+11.00	155	SOLID	STAGE 2B	155
7525+64.00	7527+00.00	136	2D-6S	STAGE 2B	34
7476+32.00	7477+50.00	118	SOLID	STAGE 3B	118
4016+50.00	4018+09.00	159	SOLID	STAGE 3B	159
	PAVEMENT MARKING WEAR AND TEAR 10%				160

70400100

TEMPORARY CONCRETE BARRIER — TOTAL 7,375 FOOT

STAGE	LOCATION	STA	STA	LENGTH	NEW WALL NEEDED	WALL FROM PREVIOUS STAGE	"WALL FROM ON-SITE STAGE"	"RELOCATE WALL TO STORAGE"	"RELOCATED TO AND REMAINING IN STORAGE"	SUBTOTALS FOOT
PRESTAGE B1	IL59	7520+45.00	7522+40.00	210	210					210
PRESTAGE B2	IL59	7520+10.00	7522+47.00	240	30	210				30
STAGE 1	I55 NB	82+47.00	85+00.00	260	260					260
STAGE 1	I55 NB	85+00.00	105+00.00	2000	2000					2000
STAGE 1	I55 NB	105+00.00	108+10.00	310	310					310
STAGE 1	I55 NB	108+10.00	115+90.00	780	780					780
STAGE 1	I55 SB	119+00.00	120+12.00	110	110					110
STAGE 1	I55 SB	110+65.00	119+00.00	835	835					835
STAGE 1	I55 SB	109+00.00	110+65.00	165	165					165
STAGE 1	I55 SB	82+25.00	109+00.00	2675	2675					2675
STAGE 2A	I55 NB	95+65.00	101+09.00	544		544				
STAGE 2A	I55 SB	103+70.00	109+25.00	555		555				
WINTER STAGE (SURPLUS STORE WINTER)								3475	3475	
STAGE 2A1	NBRP	150+12.00	152+48.00	240			240		3235	
STAGE 2A2	NBRP	148+60.00	152+45.00	390		240	150		3085	
WINTER STAGE (SURPLUS STORE WINTER)								390	3475	
STAGE 3 PRE	RUNAROUND/SEIL	1011+87.00	1013+42.00	155			155		3320	
STAGE 3A	I55 SB	103+70.00	109+25.00	REMOVE				555	3875	
STAGE 3B	I55 NB	95+65.00	101+09.00	REMOVE				544	4419	
STAGE 4A	I55 SB	111+00.00	130+55.00				1955		2464	
STAGE 4A	I55 NB	130+55.00	131+80.00				130		2334	
STAGE 4A	I55 NB	111+09.00	112+50.00				144		2190	
STAGE 4A	I55 NB	112+50.00	127+50.00				1500		690	
STAGE 4A	I55 NB	136+65.00	137+05.00				40		650	
STAGE 4A	I55 NB	137+05.00	140+45.00				340		310	
STAGE 4A	I55 SB	139+65.00	141+25.00				160		150	
STAGE 4A	I55 SB	141+25.00	142+75.00				150			
STAGE 4B	I55 NB	137+14.00	141+00.00			386				
STAGE 4B	I55 SB	139+00.00	142+86.00			386				

X0325840

WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH — TOTAL 6299 FOOT

DIRECTION	LOCATION	"FROM STATION"	"TO STATION"	OFFSET	"LINE WIDTH" FT	COLOR	MOT STAGE	SUBTOTALS FOOT
NB	IL 59	7519+20.00	7528+78.00	LT & RT	1	YELLOW	PRESTAGE A	540
EB	SEIL RD	4008+69.26	4010+06.13	LT	1	WHITE	PRESTAGE B	78
EB	SEIL RD	4010+90.22	4012+01.31	LT	1	WHITE	PRESTAGE B	41
EB	SEIL RD	4011+53.58	4014+00.00	LT & RT	1	WHITE	PRESTAGE B	103
NB	IL 59	7523+00.00	7528+77.00	LT & RT	1	YELLOW	PRESTAGE B	644
NB	IL 59	7522+42.00	7528+77.00	LT & RT	1	YELLOW	PRESTAGE B	690
NB	IL 59	7520+44.00	7528+77.00	LT & RT	1	YELLOW	STAGE 1	1714
SB	I-55	85+00	110+00	LT	1	YELLOW	STAGE 1	25
NB	I-55	85+00	110+00	RT	1	YELLOW	STAGE 1	29
NB	I-55	110+00	110+00	RT	1	WHITE	STAGE 1	15
NB	IL 59	7522+32	7528+77	LT & RT	2	YELLOW	STAGE 2A	837
NB	IL 59	7522+00	7528+77	LT & RT	2	YELLOW	STAGE 2B	420
NB	IL 59	7476+24	7479+60	LT & RT	1	YELLOW	STAGE 3B	319
NB	IL 59	7489+00	7492+22	RT	1	YELLOW	STAGE 3B	17
NB	IL 59	7488+50	7493+50	RT	1	WHITE	STAGE 3B	254
		PAVEMENT MARKING WEAR AND TEAR 10%						572

70300550

WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 8 INCH — TOTAL 4,135 FOOT

DIRECTION	LOCATION	STA.	STA	CALC LENGTH (FT)	MOT STAGE	SUBTOTALS FOOT
NB	I-55	68+29.00	77+01.00		STAGE 1	843
NB	I-55	71+59.00	77+01.00	542.00	STAGE 1	542
NB	I-55	71+59.00	81+76.00	1,017.00	STAGE 1	1,017
SB	I-55	74+30.00	75+06.00	76.00	STAGE 1	76
SB	I-55	74+30.00	75+06.00	76.00	STAGE 1	76
SB	I-55	75+03.00	78+03.00	300.00	STAGE 1	300
SB	I-55	78+03.00	82+00.00	397.00	STAGE 1	397
NB	IL 59	7493+17.00	7498+25.00	508.00	STAGE 3B	508
			PAVEMENT MARKING WEAR AND TEAR 10%			376

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 23

SCALE: DRAWN BY: JB
DATE: 03/14/08 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TEL.(312)616-2000

..\SCD00\TF2.DGN...\TTBORKN.DGN
4-14-2008,10:49:44 T:\DOCUMENT\93279\CWL\DGN\SCD00182.DGN
LEEAC
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63