

X6060500				TOTAL	785	SQ. FT.
CORRUGATED MEDIAN REMOVAL						
STATION	STATION	AREA				SUBTOTALS
2996+48.46	2998+47.00	785	MEASURED			SQ. FT. 785.3

XX005715						TOTAL	300	SQ. YD.
SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE								
LOCATION	STATION	MOT	STAGE	AREA (SF)		AREA (SY)		SUBTOTALS
				L (FT)	W (FT)			SQ. YD.
EAST FR	6025+08	PRE	ST A	15	30	450	50	50
EAST FR	6035+95	PRE	ST A	15	30	450	50	50
SEIL	4015+13	PRE	ST A	15	30	450	50	50
SEIL	4016+28	PRE	ST B	15	30	450	50	50
IL 59	7486+65		STAGE 2A	15	30	450	50	50
IL 59	7489+47		STAGE 3B	15	30	450	50	50

Z0030250						TOTAL	6	EACH
IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3								
STAGE	LOCATION	STA	STA	"NEW TEMP IMPACT ATTEN"				SUBTOTALS
								EACH
PRESTAGE B1	IL59	7520+45.00	7522+40.00	A				1
PRESTAGE B2	IL59	7520+10.00	7522+47.00	B				1
STAGE 1	I55 NB	82+47.00	85+00.00	C				1
STAGE 1	I55 SB	119+00.00	120+12.00	D				1
STAGE 4A	I55 NB	136+65.00	137+05.00	F				1
STAGE 4A	I55 SB	139+65.00	141+25.00	E				1

Z0001050			TOTAL	86,009	SQ. YD.
AGGREGATE SUBGRADE 12"					
LOCATION			AREA		SUBTOTALS
			SQ. FT.		SQ. YD.
SEIL			14,587		1,621
SEIL			44,230		4,914
SB RAMP			66,939		7,438
NB RAMP			40,543		4,505
NB RAMP			30,989		3,443
NB RAMP			34,902		3,878
SEIL			312,268		34,696
WEST FR			67,397		7,489
EAST FR			48,511		5,390
WEST FR			22,113		2,457
EAST FR			16,707		1,856
EAST FR			1,582		176
NB RAMP			1,425		158
EAST FR			71,892		7,988

T:\DOCUMENTS\1932790\DWG\106\106A\106A000887.DWG
 3-14-2008 13:26:44
 2,3,4,56,78,9,10,11,12,13,14,15,16,17,18,19,20,21,22,23,24,25,26,27,28,29,30,31,32,33,34,35,36,37,38,39,40,41,42,43,44,45,46,47,48,49,50,51,52,53,54,55,56,57,58,59,60,61,62,63
 TAMJZZ
 \S0000\F2.DWG, \YTB00R\MJ.DWG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 AT FAP 338 ILLINOIS ROUTE 59
 SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 28

SCALE: DRAWN BY: JB
 DATE: 03/14/08 CHECKED BY: ACL

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 210 N. MICHIGAN AVE., CHICAGO, IL 60601
 TELEPHONE: 312.953.0000