

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 80% FED. 20% STATE 1000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12.2	12.2				
40600300	AGGREGATE (PRIME COAT)	TON	61.1	61.1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9.2	9.2				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1757	1757				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	488.5	488.5				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	560	560				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2636	2636				
42001300	PROTECTIVE COAT	SO YD	256	256				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	30562	30562				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1150	1150				
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SO YD	2611	2611				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	570	570				
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SO YD	5	5				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	387	387				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	19	19				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	153	153				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1230	1230				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	466	466				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	599	599				
** 55039700	STORM SEWERS TO BE CLEANED	FOOT	1300	1300				
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	13	13				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	12	12				

* SPECIALTY ITEMS
** NON PARTICIPATING ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 80% FED. 20% STATE 1000				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	57	57				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4103	4103				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	193	193				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11281	11281				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	563	563				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	273	273				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	136	136				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1227	1227				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	193	193				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11281	11281				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	563	563				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	273	273				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	193	193				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	388	388				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	173	173				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	393	393				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
** Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	130	130				

X4067107 POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N 50 TON 1757 1757

FILE NAME =	USER NAME = auky	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ca\projects\dl09498\design.ee.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	2746	3215A-RS	COOK	27	3
		CHECKED -	REVISED -		CONTRACT NO. 60559										
		DATE -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT										

Rev.