



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 23, 2008

SUBJECT: FAP Route 346  
Project CMM-F-0346 (014)  
Section 125X-HB (1 & 2) R-1  
Lake County  
Contract No. 60826  
Item No. 102, August 1, 2008 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the entire Schedule of Prices.
2. Revised the entire Table of Contents to the Special Provisions.
3. Added pages 245 - 247 to the Special Provisions.
4. Revised sheets 4, 5, 7, 8, 10, 11, 12A, 144, 146, 147, 171, 172, 208, 208A, 211, 211A, 212 – 215 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; R. E. Anderson;  
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| A2002816    | T-CATALPA SPEC 2      | EACH            | 14.000    |   |            |   |             |
| A2004716    | T-GLED TRI-I SM 2     | EACH            | 14.000    |   |            |   |             |
| A2005016    | T-GYMNOCLA DIO 2      | EACH            | 14.000    |   |            |   |             |
| A2006716    | T-QUERCUS MACR 2      | EACH            | 14.000    |   |            |   |             |
| A2016616    | T-QUERCUS ELLIP 2     | EACH            | 14.000    |   |            |   |             |
| E20200G1    | V-PARTHEN QUINQ 1G    | EACH            | 520.000   |   |            |   |             |
| E20210G1    | V-PARTHEN QUIN EM 1G  | EACH            | 185.000   |   |            |   |             |
| K1005481    | SHRED BARK MULCH 3    | SQ YD           | 689.000   |   |            |   |             |
| XX001429    | FORM LINER TEX SURF   | SQ YD           | 937.000   |   |            |   |             |
| XX002112    | TEMP LUM SV HR MT 400 | EACH            | 16.000    |   |            |   |             |
| XX002113    | TEMP LIGHT CONTROLLER | EACH            | 1.000     |   |            |   |             |
| XX003686    | REM EX CONC END SEC   | EACH            | 2.000     |   |            |   |             |
| XX004056    | MECH ST EARTH RET WL  | SQ FT           | 4,418.000 |   |            |   |             |
| XX006937    | GROUND ROD 5/8 X 10   | EACH            | 66.000    |   |            |   |             |
| XX172700    | MAN TA 8 DIA T1F CL   | EACH            | 3.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|----------|---|------------|---|-------------|
| X0300057    | MAN TA 6D T1FCL R-PLT | EACH            | 3.000    |   |            |   |             |
| X0301407    | PERENNIAL PLT-GAL POT | UNIT            | 8.000    |   |            |   |             |
| X0321193    | TEMP CATCH BASINS     | EACH            | 3.000    |   |            |   |             |
| X0321781    | MECHANICAL SPLICE     | EACH            | 22.000   |   |            |   |             |
| X0322035    | STORM SEW WM REQ 18   | FOOT            | 135.000  |   |            |   |             |
| X0322054    | REM PRC FL END SEC    | EACH            | 1.000    |   |            |   |             |
| X0322125    | STORM SEW WM REQ 24   | FOOT            | 50.000   |   |            |   |             |
| X0322127    | STORM SEW WM REQ 30   | FOOT            | 342.000  |   |            |   |             |
| X0322256    | TEMP INFO SIGNING     | SQ FT           | 864.000  |   |            |   |             |
| X0322400    | PILE EXTRACTION       | EACH            | 11.000   |   |            |   |             |
| X0322643    | SS WM REQ S68 R43     | FOOT            | 150.000  |   |            |   |             |
| X0322782    | SAN SEW PVC SDR 26 8  | FOOT            | 60.000   |   |            |   |             |
| X0323003    | TEMP ELECT SERV INST  | EACH            | 1.000    |   |            |   |             |
| X0323045    | STONE OUTCROPPING     | SQ FT           | 37.000   |   |            |   |             |
| X0323236    | TEMPORARY INLET       | EACH            | 1.000    |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| X0323426    | SED CONT DR ST INL CL | EACH            | 1,332.000  |   |            |   |             |
| X0323574    | MAINTAIN LIGHTING SYS | CAL MO          | 8.000      |   |            |   |             |
| X0323670    | PREFORM DETECT LOOP   | FOOT            | 1,021.000  |   |            |   |             |
| X0323674    | STORM SEW WM REQ 60   | FOOT            | 238.000    |   |            |   |             |
| X0323830    | DRAINAGE SCUPPR DS-11 | EACH            | 16.000     |   |            |   |             |
| X0323973    | SED CONT SILT FENCE   | FOOT            | 6,883.000  |   |            |   |             |
| X0323974    | SED CONT SILT FN MAIN | FOOT            | 1,729.000  |   |            |   |             |
| X0323988    | TEMP SOIL RETEN SYSTM | SQ FT           | 2,679.000  |   |            |   |             |
| X0324097    | COARSE SAND PLACE 2   | SQ YD           | 224.000    |   |            |   |             |
| X0324455    | DRILL/SET SOLD P SOIL | CU FT           | 46,920.000 |   |            |   |             |
| X0325170    | PLANT BED PREPARATION | SQ FT           | 224.000    |   |            |   |             |
| X0325604    | WEED CONT PRE-EM HBCD | GALLON          | 0.270      |   |            |   |             |
| X0325847    | IMP ATTEN FRD RES TL3 | EACH            | 6.000      |   |            |   |             |
| X0326148    | TEMP WP 60 CL4 15 MA  | EACH            | 16.000     |   |            |   |             |
| X0326149    | UD W/O CAB TR 2"      | FOOT            | 8,100.000  |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description   | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|------------------------|-----------------|------------|---|------------|---|-------------|
| X0326150    | ERECT MOD EX JT 6      | FOOT            | 99.000     |   |            |   |             |
| X0326151    | CONC ACC PAVER RM/STR  | SQ FT           | 156.000    |   |            |   |             |
| X0326152    | CONC ACC PAVER REINST  | SQ FT           | 156.000    |   |            |   |             |
| X0326153    | SS T1 RC EL P S42 R27  | FOOT            | 164.000    |   |            |   |             |
| X0326154    | SS WM REQ 72           | FOOT            | 599.000    |   |            |   |             |
| X0326155    | SS WM REQ 78           | FOOT            | 543.000    |   |            |   |             |
| X0326156    | SAN SEW PVC SDR 26 12  | FOOT            | 20.000     |   |            |   |             |
| X0326157    | TEMP ELECT SERV DISCN  | EACH            | 1.000      |   |            |   |             |
| X0326158    | ER HLMR BRG GD EX 250  | EACH            | 20.000     |   |            |   |             |
| X0326159    | ER HLMR BRG GD EX 850  | EACH            | 10.000     |   |            |   |             |
| X0326160    | POR GRAN EMB SUB SPEC  | CU YD           | 829.000    |   |            |   |             |
| X0545000    | BOX CULVERT REMOV      | FOOT            | 136.000    |   |            |   |             |
| X0712400    | TEMP PAVEMENT          | SQ YD           | 4,800.000  |   |            |   |             |
| X3120050    | STAB SUBBASE HMA 4 1/2 | SQ YD           | 48,941.000 |   |            |   |             |
| X4021000    | TEMP ACCESS- PRIV ENT  | EACH            | 12.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| X4022000    | TEMP ACCESS- COM ENT  | EACH            | 6.000     |   |            |   |             |
| X4023000    | TEMP ACCESS- ROAD     | EACH            | 9.000     |   |            |   |             |
| X5421472    | PRCF END S EL EQRS 33 | EACH            | 2.000     |   |            |   |             |
| X5424815    | GRT-C FL END S EQV 33 | EACH            | 2.000     |   |            |   |             |
| X6021040    | CB TC SPL T20F&G      | EACH            | 2.000     |   |            |   |             |
| X6022110    | MAN TA 10 DIA T1F CL  | EACH            | 6.000     |   |            |   |             |
| X6022120    | MAN DT 7 DIA T1F CL   | EACH            | 1.000     |   |            |   |             |
| X6064201    | COMB CC&G TM4.06      | FOOT            | 108.000   |   |            |   |             |
| X6065760    | CONC MED SURF 8       | SQ FT           | 2,185.000 |   |            |   |             |
| X6370015    | CONC BARRIER SP 32    | FOOT            | 649.000   |   |            |   |             |
| X6640050    | CH LK FENCE 42 ATS SP | FOOT            | 1,170.000 |   |            |   |             |
| X6700410    | ENGR FLD OFF A SPL    | CAL MO          | 15.000    |   |            |   |             |
| X6700600    | ENGR FIELD LAB SPL    | CAL MO          | 15.000    |   |            |   |             |
| X8040310    | ELECT SERV DISCONNECT | EACH            | 1.000     |   |            |   |             |
| X8050010    | SERV INSTALL GRND MT  | EACH            | 1.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| X8110115    | CON ATS 2 GALVS PVC   | FOOT            | 510.000    |   |            |   |             |
| X8110140    | CON ATS 3/4 RGS PVC   | FOOT            | 600.000    |   |            |   |             |
| X8250110    | LTG CT RCD C-TY SCADA | EACH            | 1.000      |   |            |   |             |
| X8620020    | UNINTER POWER SUPPLY  | EACH            | 2.000      |   |            |   |             |
| X8730027    | ELCBL C GROUND 6 1C   | FOOT            | 11,506.000 |   |            |   |             |
| X8730250    | ELCBL C 20 3C TW SH   | FOOT            | 1,455.000  |   |            |   |             |
| X8770230    | S MAA & P DMA 24&36SP | EACH            | 1.000      |   |            |   |             |
| X8770440    | S C MAA&P DMA 28 & 34 | EACH            | 1.000      |   |            |   |             |
| X8808118    | OPSH LED 1F 3S BM     | EACH            | 3.000      |   |            |   |             |
| X8808120    | OPSH LED 1F 3S MAM    | EACH            | 5.000      |   |            |   |             |
| X8809045    | CSH LED 2F 3SOP 3S BM | EACH            | 2.000      |   |            |   |             |
| Z0001050    | AGG SUBGRADE 12       | SQ YD           | 65,192.000 |   |            |   |             |
| Z0007601    | BLDG REMOV NO 1       | L SUM           | 1.000      |   |            |   |             |
| Z0007602    | BLDG REMOV NO 2       | L SUM           | 1.000      |   |            |   |             |
| Z0013798    | CONSTRUCTION LAYOUT   | L SUM           | 1.000      |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| Z0018800    | DRAINAGE SYSTEM       | L SUM           | 1.000      |   |            |   |             |
| Z0030260    | IMP ATTN TEMP FRN TL3 | EACH            | 12.000     |   |            |   |             |
| Z0030330    | IMP ATTN REL FRD TL3  | EACH            | 9.000      |   |            |   |             |
| Z0048665    | RR PROT LIABILITY INS | L SUM           | 1.000      |   |            |   |             |
| Z0067500    | STEEL CASINGS 16      | FOOT            | 60.000     |   |            |   |             |
| Z0067700    | STEEL CASINGS 20      | FOOT            | 20.000     |   |            |   |             |
| Z0076600    | TRAINEES              | HOUR            | 7,500.000  |   | 0.800      |   | 6,000.000   |
| 20100110    | TREE REMOV 6-15       | UNIT            | 862.000    |   |            |   |             |
| 20100210    | TREE REMOV OVER 15    | UNIT            | 1,159.000  |   |            |   |             |
| 20101100    | TREE TRUNK PROTECTION | EACH            | 90.000     |   |            |   |             |
| 20200100    | EARTH EXCAVATION      | CU YD           | 88,824.000 |   |            |   |             |
| 20201200    | REM & DISP UNS MATL   | CU YD           | 4,227.000  |   |            |   |             |
| 20700220    | POROUS GRAN EMBANK    | CU YD           | 580.000    |   |            |   |             |
| 20700400    | POROUS GRAN EMB SPEC  | CU YD           | 934.000    |   |            |   |             |
| 20700420    | POROUS GRAN EMB SUBGR | CU YD           | 19,864.000 |   |            |   |             |



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 20800150    | TRENCH BACKFILL       | CU YD           | 11,504.000 |   |            |   |             |
| 21101615    | TOPSOIL F & P 4       | SQ YD           | 43,086.000 |   |            |   |             |
| 21101645    | TOPSOIL F & P 12      | SQ YD           | 689.000    |   |            |   |             |
| 21101805    | COMPOST F & P 2       | SQ YD           | 43,775.000 |   |            |   |             |
| 25000210    | SEEDING CL 2A         | ACRE            | 6.500      |   |            |   |             |
| 25000312    | SEEDING CL 4A         | ACRE            | 0.040      |   |            |   |             |
| 25000400    | NITROGEN FERT NUTR    | POUND           | 730.000    |   |            |   |             |
| 25000500    | PHOSPHORUS FERT NUTR  | POUND           | 730.000    |   |            |   |             |
| 25000600    | POTASSIUM FERT NUTR   | POUND           | 730.000    |   |            |   |             |
| 25000750    | MOWING                | ACRE            | 8.900      |   |            |   |             |
| 25100630    | EROSION CONTR BLANKET | SQ YD           | 17,776.000 |   |            |   |             |
| 25200110    | SODDING SALT TOLERANT | SQ YD           | 11,485.000 |   |            |   |             |
| 25200200    | SUPPLE WATERING       | UNIT            | 5,259.000  |   |            |   |             |
| 28000200    | EARTH EXC - EROS CONT | CU YD           | 115.000    |   |            |   |             |
| 28000250    | TEMP EROS CONTR SEED  | POUND           | 976.000    |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 28000300    | TEMP DITCH CHECKS     | EACH            | 53.000    |   |            |   |             |
| 28000510    | INLET FILTERS         | EACH            | 111.000   |   |            |   |             |
| 28001000    | AGGREGATE - EROS CONT | TON             | 2.000     |   |            |   |             |
| 28100107    | STONE RIPRAP CL A4    | SQ YD           | 215.000   |   |            |   |             |
| 28200200    | FILTER FABRIC         | SQ YD           | 178.000   |   |            |   |             |
| 35102100    | AGG BASE CSE B 9      | SQ YD           | 1,333.000 |   |            |   |             |
| 35300500    | PCC BSE CSE 10        | SQ YD           | 1,208.000 |   |            |   |             |
| 35501308    | HMA BASE CSE 6        | SQ YD           | 192.000   |   |            |   |             |
| 40300100    | BIT MATLS PR CT       | GALLON          | 5,043.000 |   |            |   |             |
| 40600300    | AGG PR CT             | TON             | 42.000    |   |            |   |             |
| 40600635    | LEV BIND MM N70       | TON             | 729.000   |   |            |   |             |
| 40600895    | CONSTRUC TEST STRIP   | EACH            | 2.000     |   |            |   |             |
| 40603080    | HMA BC IL-19.0 N50    | TON             | 203.000   |   |            |   |             |
| 40603310    | HMA SC "C" N50        | TON             | 189.000   |   |            |   |             |
| 40603595    | P HMA SC "F" N90      | TON             | 850.000   |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|------------|---|------------|---|-------------|
| 42000411    | PCC PVT 9 1/2 JOINTD | SQ YD           | 6,266.000  |   |            |   |             |
| 42000501    | PCC PVT 10 JOINTED   | SQ YD           | 29,696.000 |   |            |   |             |
| 42001300    | PROTECTIVE COAT      | SQ YD           | 50,778.000 |   |            |   |             |
| 42001400    | BR APPROACH PAVT SPL | SQ YD           | 474.000    |   |            |   |             |
| 42300200    | PCC DRIVEWAY PAVT 6  | SQ YD           | 377.000    |   |            |   |             |
| 42300400    | PCC DRIVEWAY PAVT 8  | SQ YD           | 611.000    |   |            |   |             |
| 42400200    | PC CONC SIDEWALK 5   | SQ FT           | 9,497.000  |   |            |   |             |
| 42400610    | TEMP SIDEWALK        | SQ FT           | 3,334.000  |   |            |   |             |
| 42400800    | DETECTABLE WARNINGS  | SQ FT           | 215.000    |   |            |   |             |
| 44000100    | PAVEMENT REM         | SQ YD           | 31,722.000 |   |            |   |             |
| 44000155    | HMA SURF REM 1 1/2   | SQ YD           | 8,131.000  |   |            |   |             |
| 44000200    | DRIVE PAVEMENT REM   | SQ YD           | 1,186.000  |   |            |   |             |
| 44000500    | COMB CURB GUTTER REM | FOOT            | 6,800.000  |   |            |   |             |
| 44000600    | SIDEWALK REM         | SQ FT           | 10,978.000 |   |            |   |             |
| 44004250    | PAVED SHLD REMOVAL   | SQ YD           | 7,314.000  |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|------------|---|------------|---|-------------|
| 44201807    | CL D PATCH T3 13     | SQ YD           | 22.000     |   |            |   |             |
| 44201809    | CL D PATCH T4 13     | SQ YD           | 73.000     |   |            |   |             |
| 44300200    | STRIP REF CR CON TR  | FOOT            | 2,429.000  |   |            |   |             |
| 48101600    | AGGREGATE SHLDS B 8  | SQ YD           | 4,976.000  |   |            |   |             |
| 48203021    | HMA SHOULDERS 6      | SQ YD           | 568.000    |   |            |   |             |
| 48300500    | PCC SHOULDERS 10     | SQ YD           | 17,549.000 |   |            |   |             |
| 50100300    | REM EXIST STRUCT N1  | EACH            | 1.000      |   |            |   |             |
| 50100400    | REM EXIST STRUCT N2  | EACH            | 1.000      |   |            |   |             |
| 50102400    | CONC REM             | CU YD           | 7.000      |   |            |   |             |
| 50157300    | PROTECTIVE SHIELD    | SQ YD           | 466.000    |   |            |   |             |
| 50200100    | STRUCTURE EXCAVATION | CU YD           | 16,681.000 |   |            |   |             |
| 50300225    | CONC STRUCT          | CU YD           | 2,537.000  |   |            |   |             |
| 50300255    | CONC SUP-STR         | CU YD           | 3,094.000  |   |            |   |             |
| 50300260    | BR DECK GROOVING     | SQ YD           | 6,488.000  |   |            |   |             |
| 50300300    | PROTECTIVE COAT      | SQ YD           | 10,856.000 |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity    | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------|---|------------|---|-------------|
| 50500305    | ERECT STRUCT STEEL    | L SUM           | 1.000       |   |            |   |             |
| 50500405    | F & E STRUCT STEEL    | POUND           | 20,440.000  |   |            |   |             |
| 50500505    | STUD SHEAR CONNECTORS | EACH            | 13,156.000  |   |            |   |             |
| 50700209    | UNTREATED TIMBER LAG  | SQ FT           | 13,906.000  |   |            |   |             |
| 50800105    | REINFORCEMENT BARS    | POUND           | 323,320.000 |   |            |   |             |
| 50800205    | REINF BARS, EPOXY CTD | POUND           | 970,520.000 |   |            |   |             |
| 50800515    | BAR SPLICERS          | EACH            | 6,188.000   |   |            |   |             |
| 51200960    | FUR M S PILE 14X0.375 | FOOT            | 14,959.000  |   |            |   |             |
| 51202210    | FUR SOLDIER PILES HP  | FOOT            | 168.000     |   |            |   |             |
| 51202230    | FUR SOLDIER PILES WS  | FOOT            | 8,051.000   |   |            |   |             |
| 51202305    | DRIVING PILES         | FOOT            | 14,959.000  |   |            |   |             |
| 51203200    | TEST PILE MET SHELLS  | EACH            | 4.000       |   |            |   |             |
| 51204650    | PILE SHOES            | EACH            | 626.000     |   |            |   |             |
| 51500100    | NAME PLATES           | EACH            | 1.000       |   |            |   |             |
| 51603000    | DRILLED SHAFT IN SOIL | CU YD           | 1,387.000   |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|----------|---|------------|---|-------------|
| 52000110    | PREF JT STRIP SEAL    | FOOT            | 99.000   |   |            |   |             |
| 52100540    | ANCHOR BOLTS 1 1/2    | EACH            | 120.000  |   |            |   |             |
| 54002020    | EXPAN BOLTS 3/4       | EACH            | 28.000   |   |            |   |             |
| 54003000    | CONC BOX CUL          | CU YD           | 15.000   |   |            |   |             |
| 54010603    | PCBC 6X3              | FOOT            | 450.000  |   |            |   |             |
| 54200427    | P CUL 1 RCCP 12       | FOOT            | 113.000  |   |            |   |             |
| 54200430    | P CUL 1 RCCP 15       | FOOT            | 50.000   |   |            |   |             |
| 54200439    | P CUL 1 RCCP 24       | FOOT            | 72.000   |   |            |   |             |
| 54213657    | PRC FLAR END SEC 12   | EACH            | 5.000    |   |            |   |             |
| 54213660    | PRC FLAR END SEC 15   | EACH            | 2.000    |   |            |   |             |
| 54213669    | PRC FLAR END SEC 24   | EACH            | 2.000    |   |            |   |             |
| 54247100    | GRATING-C FL END S 15 | EACH            | 2.000    |   |            |   |             |
| 54247130    | GRATING-C FL END S 24 | EACH            | 2.000    |   |            |   |             |
| 550A0050    | STORM SEW CL A 1 12   | FOOT            | 246.000  |   |            |   |             |
| 550A0090    | STORM SEW CL A 1 18   | FOOT            | 3.000    |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-----------|---|------------|---|-------------|
| 550A0120    | STORM SEW CL A 1 24  | FOOT            | 49.000    |   |            |   |             |
| 550A0140    | STORM SEW CL A 1 30  | FOOT            | 3.000     |   |            |   |             |
| 550A0330    | STORM SEW CL A 2 10  | FOOT            | 19.000    |   |            |   |             |
| 550A0340    | STORM SEW CL A 2 12  | FOOT            | 2,434.000 |   |            |   |             |
| 550A0360    | STORM SEW CL A 2 15  | FOOT            | 1,010.000 |   |            |   |             |
| 550A0380    | STORM SEW CL A 2 18  | FOOT            | 708.000   |   |            |   |             |
| 550A0400    | STORM SEW CL A 2 21  | FOOT            | 241.000   |   |            |   |             |
| 550A0410    | STORM SEW CL A 2 24  | FOOT            | 1,131.000 |   |            |   |             |
| 550A0430    | STORM SEW CL A 2 30  | FOOT            | 202.000   |   |            |   |             |
| 550A0450    | STORM SEW CL A 2 36  | FOOT            | 13.000    |   |            |   |             |
| 550A0680    | STORM SEW CL A 3 18  | FOOT            | 135.000   |   |            |   |             |
| 550A0710    | STORM SEW CL A 3 24  | FOOT            | 450.000   |   |            |   |             |
| 550A0750    | STORM SEW CL A 3 36  | FOOT            | 235.000   |   |            |   |             |
| 55035600    | SS 2 RCEP S38 R24    | FOOT            | 109.000   |   |            |   |             |
| 55035800    | SS 2 RCEP S53 R34    | FOOT            | 262.000   |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description   | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|------------------------|-----------------|-----------|---|------------|---|-------------|
| 55035900    | SS 2 RCEP S60 R38      | FOOT            | 157.000   |   |            |   |             |
| 55100400    | STORM SEWER REM 10     | FOOT            | 708.000   |   |            |   |             |
| 55100500    | STORM SEWER REM 12     | FOOT            | 2,731.000 |   |            |   |             |
| 55100700    | STORM SEWER REM 15     | FOOT            | 138.000   |   |            |   |             |
| 55100900    | STORM SEWER REM 18     | FOOT            | 990.000   |   |            |   |             |
| 55101200    | STORM SEWER REM 24     | FOOT            | 576.000   |   |            |   |             |
| 55101400    | STORM SEWER REM 30     | FOOT            | 1,250.000 |   |            |   |             |
| 56400100    | FIRE HYDNITS TO BE MVD | EACH            | 1.000     |   |            |   |             |
| 58700300    | CONCRETE SEALER        | SQ FT           | 523.000   |   |            |   |             |
| 59100100    | GEOCOMPOSITE WALL DR   | SQ YD           | 2,554.000 |   |            |   |             |
| 59300100    | CONTR LOW-STRENG MATL  | CU YD           | 119.000   |   |            |   |             |
| 60100060    | CONC HDWL FOR P DRAIN  | EACH            | 3.000     |   |            |   |             |
| 60100085    | GEO FAB-FRENCH DRAIN   | SQ YD           | 4,976.000 |   |            |   |             |
| 60107700    | PIPE UNDERDRAINS 6     | FOOT            | 510.000   |   |            |   |             |
| 60108200    | PIPE UNDERDRAIN 6 SP   | FOOT            | 39.000    |   |            |   |             |



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-----------|---|------------|---|-------------|
| 60109580    | P UNDR FOR STRUCT 4  | FOOT            | 2,215.000 |   |            |   |             |
| 60109582    | P UNDR FOR STRUCT 6  | FOOT            | 261.000   |   |            |   |             |
| 60200105    | CB TA 4 DIA T1F OL   | EACH            | 8.000     |   |            |   |             |
| 60201310    | CB TA 4 DIA T20F&G   | EACH            | 67.000    |   |            |   |             |
| 60206905    | CB TC T1F OL         | EACH            | 9.000     |   |            |   |             |
| 60207005    | CB TC T1F CL         | EACH            | 8.000     |   |            |   |             |
| 60208210    | CB TC T20F&G         | EACH            | 2.000     |   |            |   |             |
| 60209600    | CB TC SPL T1F OL     | EACH            | 3.000     |   |            |   |             |
| 60218400    | MAN TA 4 DIA T1F CL  | EACH            | 12.000    |   |            |   |             |
| 60221000    | MAN TA 5 DIA T1F OL  | EACH            | 1.000     |   |            |   |             |
| 60221100    | MAN TA 5 DIA T1F CL  | EACH            | 14.000    |   |            |   |             |
| 60223800    | MAN TA 6 DIA T1F CL  | EACH            | 6.000     |   |            |   |             |
| 60224446    | MAN TA 7 DIA T1F CL  | EACH            | 2.000     |   |            |   |             |
| 60226600    | MAN DT 5 DIA T1F CL  | EACH            | 2.000     |   |            |   |             |
| 60226730    | MAN DT 6 DIA T1F CL  | EACH            | 1.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-----------|---|------------|---|-------------|
| 60247160    | DR STR T1 W/2 T20F&G | EACH            | 10.000    |   |            |   |             |
| 60247800    | JUNCTION CHAMBER     | EACH            | 2.000     |   |            |   |             |
| 60250200    | CB ADJUST            | EACH            | 1.000     |   |            |   |             |
| 60255500    | MAN ADJUST           | EACH            | 6.000     |   |            |   |             |
| 60500040    | REMOV MANHOLES       | EACH            | 42.000    |   |            |   |             |
| 60500050    | REMOV CATCH BAS      | EACH            | 57.000    |   |            |   |             |
| 60500060    | REMOV INLETS         | EACH            | 9.000     |   |            |   |             |
| 60500105    | FILL MANHOLES        | EACH            | 1.000     |   |            |   |             |
| 60600605    | CONC CURB TB         | FOOT            | 387.000   |   |            |   |             |
| 60602200    | CONC GUTTER          | FOOT            | 270.000   |   |            |   |             |
| 60603800    | COMB CC&G TB6.12     | FOOT            | 2,155.000 |   |            |   |             |
| 60605000    | COMB CC&G TB6.24     | FOOT            | 2,828.000 |   |            |   |             |
| 60608250    | COMB CC&G TM2.06     | FOOT            | 66.000    |   |            |   |             |
| 60618300    | CONC MEDIAN SURF 4   | SQ FT           | 8,987.000 |   |            |   |             |
| 60618760    | CONC MED TM4.12      | SQ FT           | 184.000   |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 63000000    | SPBGR TY A            | FOOT            | 1,700.000 |   |            |   |             |
| 63100045    | TRAF BAR TERM T2      | EACH            | 3.000     |   |            |   |             |
| 63100085    | TRAF BAR TERM T6      | EACH            | 1.000     |   |            |   |             |
| 63100167    | TR BAR TRM T1 SPL TAN | EACH            | 2.000     |   |            |   |             |
| 63200310    | GUARDRAIL REMOV       | FOOT            | 1,154.000 |   |            |   |             |
| 63700155    | CONC BAR 1F 32HT      | FOOT            | 4,620.000 |   |            |   |             |
| 63700255    | CONC BAR 2F 32HT      | FOOT            | 3,041.000 |   |            |   |             |
| 66410300    | CH LK FENCE REMOV     | FOOT            | 186.000   |   |            |   |             |
| 67100100    | MOBILIZATION          | L SUM           | 1.000     |   |            |   |             |
| 70101800    | TRAF CONT & PROT SPL  | L SUM           | 1.000     |   |            |   |             |
| 70101900    | TRAF CONT & PROT D1   | L SUM           | 1.000     |   |            |   |             |
| 70102000    | TRAF CONT & PROT D2   | L SUM           | 1.000     |   |            |   |             |
| 70103815    | TR CONT SURVEILLANCE  | CAL DA          | 550.000   |   |            |   |             |
| 70106800    | CHANGEABLE MESSAGE SN | CAL MO          | 15.000    |   |            |   |             |
| 70400100    | TEMP CONC BARRIER     | FOOT            | 7,480.000 |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE- -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 70400200    | REL TEMP CONC BARRIER | FOOT            | 8,162.000 |   |            |   |             |
| 72000100    | SIGN PANEL T1         | SQ FT           | 326.000   |   |            |   |             |
| 72000200    | SIGN PANEL T2         | SQ FT           | 143.000   |   |            |   |             |
| 72000300    | SIGN PANEL T3         | SQ FT           | 898.000   |   |            |   |             |
| 72400310    | REMOV SIGN PANEL T1   | SQ FT           | 294.000   |   |            |   |             |
| 72400320    | REMOV SIGN PANEL T2   | SQ FT           | 101.000   |   |            |   |             |
| 72400330    | REMOV SIGN PANEL T3   | SQ FT           | 449.000   |   |            |   |             |
| 72700100    | STR STL SIN SUP BA    | POUND           | 3,204.000 |   |            |   |             |
| 72800100    | TELES STL SIN SUPPORT | FOOT            | 323.000   |   |            |   |             |
| 73000100    | WOOD SIN SUPPORT      | FOOT            | 163.000   |   |            |   |             |
| 73100100    | BASE TEL STL SIN SUPP | EACH            | 5.000     |   |            |   |             |
| 73302110    | OSS CANT 1CA 2-0X4-6  | FOOT            | 19.000    |   |            |   |             |
| 73305000    | OVHD SIN STR WALKWAY  | FOOT            | 17.000    |   |            |   |             |
| 73400100    | CONC FOUNDATION       | CU YD           | 10.000    |   |            |   |             |
| 73400200    | DRILL SHAFT CONC FDN  | CU YD           | 5.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 78005110    | EPOXY PVT MK LINE 4   | FOOT            | 88,493.000 |   |            |   |             |
| 78008200    | POLYUREA PM T1 LTR-SY | SQ FT           | 820.000    |   |            |   |             |
| 78008210    | POLYUREA PM T1 LN 4   | FOOT            | 34,966.000 |   |            |   |             |
| 78008230    | POLYUREA PM T1 LN 6   | FOOT            | 2,222.000  |   |            |   |             |
| 78008240    | POLYUREA PM T1 LN 8   | FOOT            | 7,915.000  |   |            |   |             |
| 78008250    | POLYUREA PM T1 LN 12  | FOOT            | 2,553.000  |   |            |   |             |
| 78008270    | POLYUREA PM T1 LN 24  | FOOT            | 223.000    |   |            |   |             |
| 78100100    | RAISED REFL PAVT MKR  | EACH            | 362.000    |   |            |   |             |
| 78200410    | GUARDRAIL MKR TYPE A  | EACH            | 28.000     |   |            |   |             |
| 78201000    | TERMINAL MARKER - DA  | EACH            | 2.000      |   |            |   |             |
| 80400200    | ELECT UTIL SERV CONN  | L SUM           | 1.000      |   | 4,500.000  |   | 4,500.000   |
| 81000500    | CON T 1 1/2 GALVS     | FOOT            | 20.000     |   |            |   |             |
| 81000600    | CON T 2 GALVS         | FOOT            | 1,156.000  |   |            |   |             |
| 81000700    | CON T 2 1/2 GALVS     | FOOT            | 534.000    |   |            |   |             |
| 81000800    | CON T 3 GALVS         | FOOT            | 37.000     |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 81000900    | CON T 3 1/2 GALVS     | FOOT            | 13.000     |   |            |   |             |
| 81001100    | CON T 5 GALVS         | FOOT            | 20.000     |   |            |   |             |
| 81018500    | CON P 2 GALVS         | FOOT            | 45.000     |   |            |   |             |
| 81018600    | CON P 2 1/2 GALVS     | FOOT            | 108.000    |   |            |   |             |
| 81018700    | CON P 3 GALVS         | FOOT            | 160.000    |   |            |   |             |
| 81018900    | CON P 4 GALVS         | FOOT            | 1,323.000  |   |            |   |             |
| 81300220    | JUN BX SS AS 6X6X4    | EACH            | 16.000     |   |            |   |             |
| 81300420    | JUN BX SS AS 10X8X6   | EACH            | 3.000      |   |            |   |             |
| 81400100    | HANDHOLE              | EACH            | 12.000     |   |            |   |             |
| 81400300    | DBL HANDHOLE          | EACH            | 5.000      |   |            |   |             |
| 81400700    | HANDHOLE PCC          | EACH            | 11.000     |   |            |   |             |
| 81400720    | DBL HANDHOLE PCC      | EACH            | 6.000      |   |            |   |             |
| 81701315    | EC C EPR USE 3-1C 2   | FOOT            | 30,000.000 |   |            |   |             |
| 81702110    | EC C XLP USE 1C 10    | FOOT            | 3,210.000  |   |            |   |             |
| 81800300    | A CBL 3-1C2 MESS WIRE | FOOT            | 4,300.000  |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity   | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|------------|---|------------|---|-------------|
| 81900200    | TR & BKFIL F ELECT WK | FOOT            | 10,143.000 |   |            |   |             |
| 82102400    | LUM SV HOR MT 400W    | EACH            | 64.000     |   |            |   |             |
| 82107100    | UNDERPAS LUM 70W HPS  | EACH            | 16.000     |   |            |   |             |
| 83050770    | LT P A 47.5MH 10MA    | EACH            | 64.000     |   |            |   |             |
| 83600200    | LIGHT POLE FDN 24D    | FOOT            | 735.000    |   |            |   |             |
| 83600215    | LIGHT POLE FDN 24D OS | FOOT            | 60.000     |   |            |   |             |
| 83800105    | BKWY DEV TR B 11.5BC  | EACH            | 52.000     |   |            |   |             |
| 84200500    | REM EX LT UNIT SALV   | EACH            | 10.000     |   |            |   |             |
| 84200700    | LIGHTING FDN REMOV    | EACH            | 6.000      |   |            |   |             |
| 84500110    | REMOV LIGHTING CONTR  | EACH            | 1.000      |   |            |   |             |
| 85000200    | MAIN EX TR SIG INSTAL | EACH            | 1.000      |   |            |   |             |
| 85700300    | FAC T5 CAB            | EACH            | 1.000      |   |            |   |             |
| 87301215    | ELCBL C SIGNAL 14 2C  | FOOT            | 1,882.000  |   |            |   |             |
| 87301225    | ELCBL C SIGNAL 14 3C  | FOOT            | 3,650.000  |   |            |   |             |
| 87301245    | ELCBL C SIGNAL 14 5C  | FOOT            | 6,307.000  |   |            |   |             |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity  | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 87301255    | ELCBL C SIGNAL 14 7C  | FOOT            | 740.000   |   |            |   |             |
| 87301305    | ELCBL C LEAD 14 1PR   | FOOT            | 6,004.000 |   |            |   |             |
| 87301805    | ELCBL C SERV 6 2C     | FOOT            | 166.000   |   |            |   |             |
| 87502440    | TS POST GALVS 10      | EACH            | 1.000     |   |            |   |             |
| 87502480    | TS POST GALVS 14      | EACH            | 4.000     |   |            |   |             |
| 87502500    | TS POST GALVS 16      | EACH            | 4.000     |   |            |   |             |
| 87502510    | TS POST GALVS 17      | EACH            | 4.000     |   |            |   |             |
| 87502520    | TS POST GALVS 18      | EACH            | 1.000     |   |            |   |             |
| 87700190    | S MAA & P 30          | EACH            | 1.000     |   |            |   |             |
| 87700220    | S MAA & P 36          | EACH            | 1.000     |   |            |   |             |
| 87701200    | S MAA & P 32 SPL      | EACH            | 1.000     |   |            |   |             |
| 87701220    | S MAA & P 36 SPL      | EACH            | 1.000     |   |            |   |             |
| 87701230    | S MAA & P 38 SPL      | EACH            | 1.000     |   |            |   |             |
| 87702310    | S MAA & P DMA 24 & 36 | EACH            | 1.000     |   |            |   |             |
| 87702980    | STL COMB MAA&P 50     | EACH            | 1.000     |   |            |   |             |



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60826

State Job # - C-91-404-99  
 PPS NBR - 1-02770-1600  
 County Name - LAKE - -  
 Code - 97 - -  
 District - 1 - -  
 Section Number - 125X-HB(1&2)R-1

Project Number  
 CMM-F-0346/014/

Route  
 FAP 346

\* REVISED : JULY 22, 2008

| Item Number | Pay Item Description  | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|----------|---|------------|---|-------------|
| 87800100    | CONC FDN TY A         | FOOT            | 24.000   |   |            |   |             |
| 87800150    | CONC FDN TY C         | FOOT            | 4.000    |   |            |   |             |
| 87800415    | CONC FDN TY E 36D     | FOOT            | 90.000   |   |            |   |             |
| 88030012    | SH LED 1F 1S BM       | EACH            | 1.000    |   |            |   |             |
| 88030020    | SH LED 1F 3S MAM      | EACH            | 12.000   |   |            |   |             |
| 88030050    | SH LED 1F 3S BM       | EACH            | 5.000    |   |            |   |             |
| 88030080    | SH LED 1F 4S MAM      | EACH            | 2.000    |   |            |   |             |
| 88030210    | SH LED 2F 3S BM       | EACH            | 2.000    |   |            |   |             |
| 88030230    | SH LED 2F 1-3 1-4 BM  | EACH            | 2.000    |   |            |   |             |
| 88102710    | PED SH LED 1F BM      | EACH            | 7.000    |   |            |   |             |
| 88102740    | PED SH LED 2F BM      | EACH            | 2.000    |   |            |   |             |
| 88102760    | PED SH LED 3F BM      | EACH            | 1.000    |   |            |   |             |
| 88200110    | TS BACKPLATE LOUVERED | EACH            | 19.000   |   |            |   |             |
| 88500100    | INDUCTIVE LOOP DETECT | EACH            | 14.000   |   |            |   |             |
| 88600100    | DET LOOP T1           | FOOT            | 67.000   |   |            |   |             |



**TABLE OF CONTENTS**

LOCATION OF PROJECT ..... 1

DESCRIPTION OF PROJECT ..... 1

MAINTENANCE OF ROADWAYS ..... 2

WATER ..... 3

RESIDENTIAL WATER SERVICES ..... 3

STORM SEWER ..... 3

STREET LIGHTING ..... 3

CONTRACTOR COOPERATION ..... 4

COMPLETION DATE PLUS WORKING DAYS ..... 4

WORK RESTRICTIONS ..... 5

CONTRACTOR'S DAILY WORK SCHEDULE ..... 5

PROGRESS SCHEDULE ..... 6

WINTER WORK ..... 11

POROUS GRANULAR EMBANKMENT, SUBGRADE ..... 11

POROUS GRANULAR EMBANKMENT, SUBGRADE (SPECIAL) ..... 13

AGGREGATE SUBGRADE, 12" ..... 13

RECLAIMED ASPHALT PAVEMENT FOR NON-POROUS EMBANKMENT AND BACKFILL ..... 15

AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS ..... 15

STORM SEWER ADJACENT TO OR CROSSING WATER MAIN ..... 16

BACKFILLING STORM SEWER UNDER ROADWAY ..... 17

CLEANING EXISTING DRAINAGE STRUCTURES ..... 17

AGGREGATE FOR CONCRETE BARRIER (DISTRICT ONE) ..... 17

WORK ZONE TRAFFIC CONTROL (LUMP SUM PAYMENT) ..... 18

TRAFFIC CONTROL PLAN ..... 18

FINE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (DISTRICT ONE) ..... 19

HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1) ..... 19

TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE) ..... 20

RECLAIMED ASPHALT PAVEMENT (RAP) (DISTRICT ONE) ..... 21

DRILLED SHAFTS FOR LIGHT POLE AND TRAFFIC SIGNAL FOUNDATIONS (DIST-1) ..... 26

TEMPORARY PAVEMENT ..... 26

COARSE SAND PLACEMENT ..... 27

Revised 07/23/2008

WEED CONTROL, PRE-EMERGENT HERBICIDE..... 28  
 CHANGEABLE MESSAGE SIGN..... 29  
 COMPOST FURNISH AND PLACE ..... 29  
 CONCRETE BARRIER SPECIAL, 32" HEIGHT..... 30  
 CONCRETE ACCENT PAVER REMOVE AND STORE ..... 30  
 CONCRETE ACCENT PAVER RE-INSTALLATION..... 30  
 COMPACTION FORCE ..... 35  
 ENGINEER'S FIELD OFFICE TYPE A (SPECIAL) ..... 36  
 ENGINEER'S FIELD LABORATORY (SPECIAL) ..... 36  
 BOX CULVERT REMOVAL ..... 38  
 JUNCTION CHAMBER ..... 39  
 MANHOLES, DROP TYPE, TYPE 1 FRAME, CLOSED LID ..... 41  
 MANHOLE, TYPE A, 8 FT DIAMETER, TYPE 1 FRAME, CLOSED LID..... 42  
 MANHOLE, TYPE A, 10 FT DIAMETER, TYPE 1 FRAME, CLOSED LID..... 42  
 MANHOLE, TYPE A, 6 FT. DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE..... 42  
 SANITARY SEWER MANHOLE ADJUSTMENT..... 42  
 MOWING..... 43  
 PLANTING BED PREPARATION..... 44  
 PLANTING PERENNIAL PLANTS..... 46  
 REMOVING EXISTING CONCRETE END SECTIONS ..... 47  
 REMOVING PRECAST FLARED END SECTIONS ..... 47  
 SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING ..... 48  
 SHREDDED BARK MULCH, 3" ..... 48  
 STONE OUTCROPPING ..... 49  
 STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 42, RISE 27 ..... 52  
 SUPPLEMENTAL WATERING ..... 52  
 TEMPORARY DITCH CHECKS ..... 53  
 TEMPORARY INFORMATION SIGNING..... 53  
 TEMPORARY INLETS..... 54  
 TEMPORARY CATCH BASINS..... 54  
 TOPSOIL..... 55

Revised 07/23/2008

|  |    |
|--|----|
| AGGREGATE SHOULDERS TYPE B, 8" .....                         | 57 |
| PIPE UNDERDRAINS, 6" (SPECIAL).....                          | 58 |
| CATCH BASINS, TYPE C, SPECIAL, TYPE 1 FRAME, OPEN LID .....  | 58 |
| TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) .....     | 58 |
| CHAIN LINK FENCE REMOVAL .....                               | 59 |
| POLYUREA PAVEMENT MARKING, TYPE 1 – LETTERS AND SYMBOLS..... | 59 |
| PERENNIAL PLANTS, GALLON POT.....                            | 59 |
| SEDIMENT CONTROL, SILT FENCE .....                           | 60 |
| SEDIMENT CONTROL, SILT FENCE MAINTENANCE.....                | 60 |
| CONCRETE MEDIAN SURFACE, 8 INCH.....                         | 61 |
| STABILIZED SUBBASE – HOT-MIX ASPHALT, 4 ½" .....             | 62 |
| SANITARY SEWER, PVC (D3034) SDR 26.....                      | 62 |
| STEEL CASING .....   | 62 |
| TRAFFIC CONTROL AND PROTECTION (DETOUR 1) .....              | 63 |
| TRAFFIC CONTROL AND PROTECTION (DETOUR 2) .....              | 63 |
| DRAINAGE SYSTEM.....   | 64 |
| HIGH LOAD MULTI-ROTATIONAL BEARINGS .....                    | 65 |
| MODULAR EXPANSION JOINT.....                                 | 68 |
| CLEANING AND PAINTING NEW METAL STRUCTURES.....              | 72 |
| MECHANICALLY STABILIZED EARTH RETAINING WALLS .....          | 78 |
| DRILLED SOLDIER PILE RETAINING WALL.....                     | 86 |
| TEMPORARY SOIL RETENTION SYSTEM .....                        | 90 |
| PIPE UNDERDRAINS FOR STRUCTURES .....                        | 92 |
| POROUS GRANULAR EMBANKMENT (SPECIAL) .....                   | 93 |
| MECHANICAL SPLICE.....                                       | 93 |
| DEMOLITION PLANS FOR REMOVAL OF EXISTING STRUCTURES.....     | 93 |
| BRIDGE APPROACH PAVEMENT (SPECIAL) .....                     | 94 |
| REMOVAL OF EXISTING STRUCTURES .....                         | 94 |
| PILE EXTRACTION .....  | 94 |
| ERECTING STRUCTURAL STEEL.....                               | 95 |
| CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL).....   | 95 |
| FORM LINER TEXTURED SURFACE .....                            | 96 |
| GENERAL ELECTRICAL REQUIREMENTS .....                        | 97 |

Revised 07/23/2008

ELECTRIC UTILITY SERVICE CONNECTION..... 99  
 GROUND ROD ..... 100  
 ELECTRIC CABLE IN CONDUIT, GROUNDING ..... 101  
 UNIT DUCT WITHOUT CABLE IN TRENCH, 2” ..... 101  
 CONDUIT ATTACHED TO STRUCTURE ..... 102  
 DIRECTIONAL BORING..... 102  
 ELECTRICAL SERVICE DISCONNECT ..... 103  
 TEMPORARY ELECTRIC SERVICE INSTALLATION..... 105  
 TEMPORARY ELECTRIC SERVICE DISCONNECTION ..... 105  
 LUMINAIRE..... 106  
 MAINTENANCE OF LIGHTING SYSTEMS..... 113  
 REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE ..... 116  
 LIGHT POLE FOUNDATION, 24” DIAMETER, OFFSET ..... 117  
 LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA..... 117  
 TEMPORARY LIGHTING CONTROLLER ..... 118  
 TEMPORARY WOOD POLE WITH MAST ARM..... 119  
 TEMPORARY LUMINAIRE..... 120  
 TRAFFIC SIGNAL SPECIFICATIONS..... 121  
 STEEL MAST ARM ASSEMBLY AND POLE (OF THE MAST ARM LENGTH SPECIFIED) SPECIAL.. 167  
 BUILDING REMOVAL - CASE IV (NO ASBESTOS) (BDE)..... 167  
 RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE)..... 169  
 ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE) ..... 170  
 CEMENT (BDE) ..... 172  
 CONCRETE BARRIER (BDE) ..... 175  
 DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 175  
 DOWEL BARS (BDE) ..... 182  
 ENGINEER’S FIELD OFFICE TYPE A (BDE) ..... 183  
 EQUIPMENT RENTAL RATES (BDE)..... 185  
 EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) ..... 186  
 HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE) ..... 186  
 HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE)..... 188  
 HOT-MIX ASPHALT – TRANSPORTATION (BDE) ..... 189

Revised 07/23/2008

IMPACT ATTENUATORS (BDE) ..... 190

IMPACT ATTENUATORS, TEMPORARY (BDE) ..... 191

MAST ARM ASSEMBLY AND POLE (BDE) ..... 193

MULTILANE PAVEMENT PATCHING (BDE) ..... 194

PAYMENTS TO SUBCONTRACTORS (BDE) ..... 194

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) ..... 195

POLYUREA PAVEMENT MARKING (BDE) ..... 195

PORTLAND CEMENT CONCRETE PLANTS (BDE) ..... 202

PRECAST CONCRETE HANDLING HOLES (BDE) ..... 203

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) ..... 204

REINFORCEMENT BARS (BDE) ..... 205

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE) ..... 206

SEEDING (BDE) ..... 207

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE) ..... 208

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) ..... 212

SILT FILTER FENCE (BDE) ..... 213

STEEL PLATE BEAM GUARDRAIL (BDE) ..... 213

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 214

SURFACE TESTING OF PAVEMENTS (BDE) ..... 214

TEMPORARY EROSION CONTROL (BDE) ..... 220

TRAINING SPECIAL PROVISIONS ..... 221

TYPE ZZ RETROREFLECTIVE SHEETING, NONREFLECTIVE SHEETING, AND TRANSLUCENT  
 OVERLAY FILM FOR HIGHWAY SIGNS (BDE) ..... 223

VARIABLY SPACED TINING (BDE) ..... 228

WATER BLASTER WITH VACUUM RECOVERY (BDE) ..... 228

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 229

STORM WATER POLLUTION PREVENTION PLAN ..... 233

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) ..... 245

Revised 07/23/2008

**BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)**

Effective: November 2, 2006

Revised: January 2, 2007

Description. For projects with at least 1200 tons (1100 metric tons) of work involving applicable bituminous materials, cost adjustments will be made to provide additional compensation to the Contractor, or credit to the Department, for fluctuations in the cost of bituminous materials when optioned by the Contractor. The adjustments shall apply to permanent and temporary hot-mix asphalt (HMA) mixtures, bituminous surface treatments (cover and seal coats), and pavement preservation type surface treatments. The adjustments shall not apply to bituminous prime coats, tack coats, crack filling/sealing, or joint filling/sealing.

The bidder shall indicate on the attached form whether or not this special provision will be part of the contract and submit the completed form with his/her bid. Failure to submit the form, or failure to fill out the form completely, shall make this contract exempt of bituminous materials cost adjustments.

Method of Adjustment. Bituminous materials cost adjustments will be computed as follows.

$$CA = (BPI_P - BPI_L) \times (\%AC_V / 100) \times Q$$

Where: CA = Cost Adjustment, \$.

BPI<sub>P</sub> = Bituminous Price Index, as published by the Department for the month the work is performed, \$/ton (\$/metric ton).

BPI<sub>L</sub> = Bituminous Price Index, as published by the Department for the month prior to the letting, \$/ton (\$/metric ton).

%AC<sub>V</sub> = Percent of virgin Asphalt Cement in the Quantity being adjusted. For HMA mixtures, the % AC<sub>V</sub> will be determined from the adjusted job mix formula. For bituminous materials applied, a performance graded or cutback asphalt will be considered to be 100% AC<sub>V</sub> and undiluted emulsified asphalt will be considered to be 65% AC<sub>V</sub>.

Q = Authorized construction Quantity, tons (metric tons) (see below).

For HMA mixtures measured in square yards:  $Q, \text{ tons} = A \times D \times (G_{mb} \times 46.8) / 2000$ . For HMA mixtures measured in square meters:  $Q, \text{ metric tons} = A \times D \times (G_{mb} \times 24.99) / 1000$ . When computing adjustments for full-depth HMA pavement, separate calculations will be made for the binder and surface courses to account for their different  $G_{mb}$  and % AC<sub>V</sub>.

For bituminous materials measured in gallons:  $Q, \text{ tons} = V \times 8.33 \text{ lb/gal} \times SG / 2000$

For bituminous materials measured in liters:  $Q, \text{ metric tons} = V \times 1.0 \text{ kg/L} \times SG / 1000$

Where: A = Area of the HMA mixture, sq yd (sq m).

D = Depth of the HMA mixture, in. (mm).

G<sub>mb</sub> = Average bulk specific gravity of the mixture, from the approved mix design.

V = Volume of the bituminous material, gal (L).

SG = Specific Gravity of bituminous material as shown on the bill of lading.

Added 07/23/2008



Basis of Payment. Bituminous materials cost adjustments may be positive or negative but will only be made when there is a difference between the  $BPI_L$  and  $BPI_P$  in excess of five percent, as calculated by:

$$\text{Percent Difference} = \{(BPI_L - BPI_P) \div BPI_L\} \times 100$$

Bituminous materials cost adjustments will be calculated for each calendar month in which applicable bituminous material is placed; and will be paid or deducted when all other contract requirements for the items of work are satisfied. The adjustments shall not apply during contract time subject to liquidated damages for completion of the entire contract.

Added 07/23/2008

Return With Bid

**ILLINOIS DEPARTMENT  
OF TRANSPORTATION**

**OPTION FOR  
BITUMINOUS MATERIALS COST ADJUSTMENTS**

The bidder shall submit this completed form with his/her bid. Failure to submit the form, or failure to fill out the form completely, shall make this contract exempt of bituminous materials cost adjustments. After award, this form, when submitted, shall become part of the contract.

**Contract No.:** \_\_\_\_\_

**Company Name:** \_\_\_\_\_

**Contractor's Option:**

Is your company opting to include this special provision as part of the contract?

Yes  No

**Signature:** \_\_\_\_\_ **Date:** \_\_\_\_\_

Added 07/23/2008