

PROJECT: GATEWAYS AND CORNER GARDENS AT 79TH STREET  
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-070 LS	COOK	65	4
STA. 2308+17 (NB I-94) TO STA. 2316+90 (NB I-94)				
1308+46 (SB I-94)		TO STA. 1318+61 (SB I-94)		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60A76

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE
				DAN RYAN Y003
20101000	TEMPORARY FENCE	FOOT	74	74
20200100	EARTH EXCAVATION	CU YD	35	35
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	35	35
20700220	POROUS GRANULAR EMBANKMENT	CU YD	10	10
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	85	85
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	85	85
25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	115	115
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	78	78
25100630	EROSION CONTROL BLANKET	SQ YD	2827	2827
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60
28000510	INLET FILTERS	EACH	32	32
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9	9
42001300	PROTECTIVE COAT	SQ YD	136	136
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	788	788
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	102	102
44000300	CURB REMOVAL	FOOT	30	30
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	143	143
44000600	SIDEWALK REMOVAL	SQ FT	786	786
44003100	MEDIAN REMOVAL	SQ FT	16	16
44004250	PAVED SHOULDER REMOVAL	SQ YD	3	3
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	3	3
50200100	STRUCTURAL EXCAVATION	CU YD	33	33
50300225	CONCRETE STRUCTURES	CU YD	9	9
50300300	PROTECTIVE COAT	SQ YD	14	14
50300510	RUSTICATION FINISH	SQ FT	28	28
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2600	2600
56104600	WATER VALVES 2"	EACH	2	2
56200700	WATER SERVICE LINE 2 1/2"	FOOT	395	395
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5
60600605	CONCRETE CURB, TYPE B	FOOT	50.0	50
66410300	CHAIN LINK FENCE REMOVAL	FOOT	63.0	63.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION,(SPECIAL)	L SUM	1	1

\* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES  
 SHEET 1 OF 2

SCALE: NONE  
 DATE: MAY 1, 2008  
 DRAWN BY: JDF  
 CHECKED BY: JPM