

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2721	2006-023RS	COOK	26	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60858

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	190	190				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14				
40600300	AGGREGATE (PRIME COAT)	TON	67	67				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	10				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	248	248				
40600990	TEMPORARY RAMP	SO YD	248	248				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	398	398				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2781	2781				
42001300	PROTECTIVE COAT	SO YD	35	35				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	33100	33100				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	112	112				
44002236	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 9"	SO YD	788	788				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	361	361				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	35	35				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	350	350				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	758	758				
<input type="checkbox"/> 55039700	STORM SEWERS TO BE CLEANED	FOOT	1050	1050				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4				
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	850	850				
*63100167	TRAFFIC BARRIER TERMINAL, TYPE I (SPECIAL) TANGENT	EACH	4	4				
63200310	GUARDRAIL REMOVAL	FOOT	850	850				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000-2A				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6444	6444				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	37	37				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14493	14493				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	102	102				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	582	582				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	155	155				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5990	5990				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	37	37				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14493	14493				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	102	102				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	582	582				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155	155				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	490	490				
*78200405	GUARDRAIL MARKERS	EACH	12	12				
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	416	416				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	202	202				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1304	1304				
<input type="checkbox"/> Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4				

* SPECIALITY ITEMS
 NON-PARTICIPATING ITEMS 100% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.U. 2721 (KEAN AVE.)
111TH ST. TO US 12/20 (95TH ST.)

PLOT DATE: 5/21/2008

5/21/2008 09:00:00 AM C:\projects\60858\1110858.dwg