

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	12R - 4	WILL	199	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY 1000-1A	SIGNALS Y031-1F	FIRE HYDRANT Y060	DETOUR 1000-1A	BIKE PATH Y046
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2				
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3				
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	6	6				
60500040	REMOVING MANHOLES	EACH	3	3				
60500050	REMOVING CATCH BASINS	EACH	10	10				
60500060	REMOVING INLETS	EACH	7	7				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8.2	8.2				
60600605	CONCRETE CURB, TYPE B	FOOT	217	217				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	432	432				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6868	6868				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1842	1842				
60620200	CONCRETE MEDIAN, TYPE SB-6.24 (MODIFIED)	SQ FT	2725	2725				
63200310	GUARDRAIL REMOVAL	FOOT	276	276				
66400105	CHAIN LINK FENCE, 4'	FOOT	409					409
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	2				2	
70103817	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	28	28				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1629	1629				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2485	2485				
72000100	SIGN PANEL - TYPE 1	SQ FT	247	235	12			
72000200	SIGN PANEL - TYPE 2	SQ FT	50	20	30			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	407	407				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1128.4	1128.4				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17442	17442				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4234	4234				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2482	2482				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2625	2625				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	391	391				
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	546	546				
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	65163	65163				
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	2678	2678				
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	2093	2093				
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	393	393				
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	145.6	145.6				
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4283	4283				
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	185	185				

*SPECIALTY ITEMS

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	SUMMARY OF QUANTITIES
DATE	U.S. RTE. 30 (LINCOLN HIGHWAY)
	SCALE : 1" = 50'
	DATE : 03/21/08
	DRAWN BY : BAE
	CHECKED BY : GB