

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 80% FED. 20% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 80% FED. 20% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 1000-2A						CODE NO	ITEM		UNIT	ROADWAY 1000-2A				
35600730	HOT-MIX ASPHALT BASE COURSE WIDENING, 13 1/2"	SO YD	235	235					70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	165	165					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	75	75					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	235	235					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5970	5970					
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	310	310					
40600300	AGGREGATE (PRIME COAT)	TON	57	57					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30070	30070					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	15	15					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1150	1150					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	210	210					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	295	295					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	205	205					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1550	1550					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2300	2300					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2375	2375					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	310	310					
42001300	PROTECTIVE COAT	SO YD	25	25					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30070	30070					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	16	16					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1150	1150					
44000100	PAVEMENT REMOVAL	SO YD	60	60					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	210	210					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	27985	27985					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	205	205					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	16	16					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	280	280					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	240	240					
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	4600	4600					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	613	613					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1500	1500					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	610	610					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1115	1115					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1790	1790					NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	9	9					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	805	805					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														

NP= Non-Participating  
\* - Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES