

ROUTE: IL Rte 83

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
IL Rte 173		N/B	1	12	100	1200	133
	Total 8 Each	N/B	1	6	12	72	64
	Total 3 Each	S/B	1	6	12	72	24
		N/B	1	4	20	80	9
	Total 5 Ea	N/B & S/B	1	12	6	72	40
		N/B	1	6	20	120	13
		N/B	1	6	12	72	8
		S/B	1	6	30	180	20
		N/B	1	6	100	600	67
		S/B	1	12	6	72	8
		N/B	1	4	20	80	9
		N/B	1	6	20	120	13
	Total 4 Ea	N/B & S/B	1	8	12	96	43
		S/B	1	6	100	600	67
	Total 2 Ea	N/B & S/B	1	6	12	72	16
	Total 6 E	S/B	1	6	12	72	48
	WISCONSIN ST LINE	S/B	1	3	50	150	17
IL Rte 173		S/B	1	6	20	120	13
	Total 2 Each	S/B	1	6	12	72	16
	Total 4 Each	N/B	1	12	6	72	32
		S/B	1	4	10	40	4
		S/B	1	4	100	400	44
		S/B	1	4	50	200	22
		S/B	C/L	4	100	400	44
		N/B	1	4	300	1200	133
		S/B	1	4	50	200	22
	Total 2	N/B & S/B	1	12	6	72	16
		S/B	1	12	8	96	11
		C.L.	1	3	150	450	50
	Total 2	S/B	1	4	25	100	22
		N/B	1	12	6	72	8
	Total 2	N/B & S/B	1	12	6	72	16
		C.L.	C.L.	3	50	150	17
	Grass Lake Rd. (Tot 2)	N/B & S/B	1	6	12	72	16
Grass Lake Road		N/B	1	4	250	1000	111
		N/B	1	6	12	72	8
		S/B	1	4	100	400	44
		S/B	1	4	100	400	44
	Total 2 Each	N/B & S/B	1	12	6	72	16
		C.L.	C.L.	3	100	300	33
		S/B	1	4	150	600	67
	Total 2 Each	S/B	1	12	6	72	16
	Total 2 Each	N/B & S/B	1	12	6	72	16

ROUTE: IL Rte 83

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
	Petite Lake (Tot 3 Ea)	N/B, Med, S/B	1	12	6	72	24
IL 132		S/B	1	6	25	150	17
	Total 2 Each	N/B & S/B	1	6	12	72	16
	Total 2 Each	N/B & S/B	1	6	12	72	16
	Total 2 Each	N/B & S/B	1	6	12	72	16
		C.L.	1	2	100	150	17
	Total 2 Each	N/B & S/B	1	12	6	72	16
		S/B	1	12	6	72	8
		S/B	1	4	10	40	4
		C.L.	C.L.	2	2000	3000	333
		S/B	1	2	100	150	17
		S/B	1	4	100	400	44
	Rollins Rd (Total 3 Ea)	N/B & S/B	1	12	6	72	24
Rollins Road		S/B	1	2	200	300	33
		N/B	1	2	200	300	33
		N/B	1	12	6	72	8
	Total 2 Each	N/B & S/B	1	12	6	72	16
	Lake Street (Tot 2 Ea)	N/B & S/B	1	2	150	225	50
		S/B	1	6	6	36	4
		C/L	C/L	2	200	300	33
		N/B	1	12	6	72	8
		N/B	1	12	6	72	8
	2 EA, TOT 4	N/B & S/B	1	12	6	72	32
		N/B	1	4	100	400	44
	Total 2 Ea	N/B & S/B	1	12	6	72	16
		S/B	1	2	50	75	8
	3EA, TOTAL 6	N/B & S/B	1	6	12	72	48
	IL Rte 137	N/B & S/B	1	6	12	72	16
IL Rte 137		S/B	1	6	10	60	7
		S/B	1	6	20	120	13
		N/B	1	4	50	200	22
	2 Each	N/B & S/B	1	12	8	96	21
		S/B	1	6	100	600	67
		N/B	1	4	50	200	22
		S/B	1	6	20	120	13
	3 Each	N/B	1	12	6	72	24
		N/B	1	4	50	200	22
	Petersen Rd	S/B	1	4	50	200	22
TOTALS					5910	2588	SY

FILE NAME =
c:\projects\dl36009\design_aa.dgn
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 6/26/2008

USER NAME = wilgreendp
DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 83
SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
VAR. 2008-047 RS LAKE 41 13
CONTRACT NO. 60E96
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT