ROUTE: US Rte. 12 (NORTHBOUND)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
PCC 2 mi n/o Volo Village Rd		NB	1	12	4	48	5
2.1 mi n/o V V Rd		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	1	12	6	72	8
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	1	4	12	48	5
		NB	CL	3	200	600	67
		NB	1	12	4	48	5
		NB	1	6	15	90	10
		NB	2	12	4	48	5
		NB	2	12	4	48	5
		NB	1	12	4	48	5
		NB	2	12	4	48	5
		NB	1	3	50	150	17
		NB	1	12	6	72	8
		NB	CL	3	200	600	67
		NB	1	12	4	48	5
		NB	1	12	4	48	5
Hartigan Rd.		NB	1	12	4	48	5
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	8	96	11
		NB	CL	3	200	600	67
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	2	12	4	48	5
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	1	12	4	48	5
		NB	2	12	4	48	5
		NB	2	6	4	24	3
IL 134	LT turn lane to Big Hollow	NB	LT LN	12	4	48	5
IL 134	***IL 59***	NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	20	12	240	27
		NB	2	4	12	48	5
		NB	2	4	12	48	5
		NB	2	4	12	48	5
	IL 59	NB	Ramp	4	12	48	5
	IL 59	NB	Ramp	4	12	48	5
		NB	CL	2	200	300	33
		NB	1	12	6	72	8

ROUTE: US Rte. 12 (NORTHBOUND)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
IL 59	***Eagle Pt/ Sayton***	NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	4	12	48	5
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	4	48	5
		NB	1	12	12	144	16
		NB	2	4	12	48	5
		NB	2	4	12	48	5
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	4	48	5
Grand Ave	***State Park Rd***	NB	2	12	12	144	16
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	4	48	5
		NB	2	12	4	48	5
		TOTALS:			18238		5161 SY

FILE NAME = c:\projects\d136008\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 6/27/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 12 (NORTHBOUND)

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-047 RS	LAKE	41	25

CONTRACT NO. 60E96

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

...\projects\d136008\design_aa.dgn 6/27/2008 7:03:46 AM User=wilgreendp