

ROADWAY REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL SQ YD	COMB C & G REMOVAL FOOT	CURB REMOVAL FOOT	CURB REMOVAL (SPECIAL) FOOT	MEDIAN REMOVAL SQ FT	MEDIAN SURF REMOVAL SQ FT	SIDEWALK REMOVAL SQ FT	DRIVEWAY PVMT REMOVAL SQ YD	PAVED SHLD. REMOVAL SQ YD	WOOD FENCE REMOVAL FOOT	FENCE REMOVAL FOOT	GUARD RAIL REMOVAL FOOT	PAVED DITCH REMOVAL SQ YD	SELECTIVE CLEARING UNITS
IL ROUTE 59														
STA 3032+25.77 TO STA 3040+50	4472	2567			1247	3319	4006	902				39		2.3
STA 3040+50 TO STA 3055+00	4429	304					634		511	346	140	1447		85.5
STA 3055+00 TO STA 3069+50	7839	1809				273	6959	1131	711	826				1.5
STA 3069+50 TO STA 3084+00	13860	1980	28	82	774		3488	863	370					
STA 3084+00 TO STA 3098+00	8388	1569			90	802	843	1133	632			152		
STA 3098+00 TO STA 3112+50	8874	801				581	385	295	1095	102				
STA 3112+50 TO STA 3127+00	8216	398					164	467					10	
STA 3127+00 TO STA 3141+50	9511	1549				1306	133	706	329					
STA 3141+50 TO STA 3153+00	3328	239						563	428	292				
STA 3153+00 TO STA 3167+50	7075	1264				2193	292	183	388	524	126			
STA 3167+50 TO STA 3182+00	8867	1220					632	701		428				
STA 3182+00 TO STA 3196+25	9105	1014	177		222	593	2684	662	149					
BLACK ROAD														
STA 13+00 TO STA 13+75	719	150	75				513							
THEODORE STREET														
STA 94+87 TO STA 98+50	643	210												
STA 101+50 TO STA 106+08	693	300												
CROSS STREET DETAILS														
MISC.	33	310												
TOTALS	96052	15684	280	82	2333	9067	20099	8240	4613	2518	140	1764	10	90

PROPOSED PAVING SCHEDULE

LOCATION	PCC PVMT 9 3/4" (JOINTED) SQ YD	AGG SUBGRADE 12" SQ YD	CORRUGATED MEDIAN SQ FT	CONC MED TY SB-6 (SPECIAL) SQ FT	CONC MED TY SB-6.24 SQ FT	CONC MED TY SB-6.12 SQ FT	CONC MED TY SM-4.06 SQ FT	CONC CURB TY B (SPECIAL) FOOT	COMB CONC C&G TY M-6.06 FOOT	COMB CONC C&G TY B-6.12 FOOT	COMB CONC C&G TY B-6.24 FOOT	PCC SIDEWALK 5" SQ FT	CONC MED SURF 4" SQ FT	HOT-MIX ASPH SHLD 6" SQ YD
IL ROUTE 59														
STA 3032+25.77 TO STA 3040+50	6,312.0	6312	924						137	171	1510	3083	428	143
STA 3040+50 TO STA 3055+00	10,604.8	10605									2924	7214		887
STA 3055+00 TO STA 3069+50	10,776.0	10776	329	557					30	173	2737	12527	117	32
STA 3069+50 TO STA 3084+00	14,852.6	14853	669	4824				61	62	408	2797	3312	549	
STA 3084+00 TO STA 3098+00	10,216.6	10217	323	3457	1702					387	2980	3356		
STA 3098+00 TO STA 3112+50	10,829.8	10830	2065	165		683				442	4294	9754		
STA 3112+50 TO STA 3127+00	10,275.3	10275	1455	1045	1077					182	4043	12618		
STA 3127+00 TO STA 3141+50	13,083.7	13084	266	2189	1703					322	3941	5834		
STA 3141+50 TO STA 3153+00	7,961.1	7961	437	843	851					123	3569	8713		
STA 3153+00 TO STA 3167+50	9,608.6	9609								507	5577	14790		
STA 3167+50 TO STA 3182+00	10,360.5	10361	291	1865	1704	143				353	3972	4129		
STA 3182+00 TO STA 3196+25	9,847.3	9847	436	1685	1704						3014	2732		
BLACK ROAD														
STA 13+00 TO STA 13+75	716.9	717						75		65	75			
THEODORE STREET														
STA 97+45 TO STA 98+50	647.6	648								211				
STA 101+50 TO STA 103+00	704.4	704								301				
CROSS STREET DETAILS														
MISC.	33.0	33								364				
CURB & GUTTER AND MEDIANS		16356												
TOTALS	126830	143186	7195	16630	8741	683	143	136	229	4009	41433	88062	1095	1061

PLAN
 DATE: _____ BY: _____
 CHECKED: _____
 DATE: _____ BY: _____
 NO. _____

PROFILE
 DATE: _____ BY: _____
 CHECKED: _____
 DATE: _____ BY: _____
 NO. _____

REVISIONS	
NAME	DATE
REVISED IL59 ALIGN.	12/22/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

ROADWAY REMOVAL SCHEDULE PROPOSED PAVING SCHEDULE

DATE: 3/18/08
 DRAWN BY: MJG
 CHECKED BY: VJD

SCALE: NONE