

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1459	4040.4 RS	COOK	25	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10					
40600300	AGGREGATE (PRIME COAT)	TON	47	47					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	50	50					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	290	290					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1970	1970					
42001300	PROTECTIVE COAT	SO YD	110	110					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	23400	23400					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	470	470					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1700	1700					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	20	20					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1020	1020					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	150	150					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	580	580					
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	12	12					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4					
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	24	24					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	300	300					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4800	4800					

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	200	200					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13700	13700					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	280	280					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170	170					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	160	160					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	7000	7000					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	200	200					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13700	13700					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	280	280					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170	170					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160	160					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450	450					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1410	1410					
* 87900200	DRILL EXISTING HANDHOLE	EACH	5	5					
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	4	4					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	140	140					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	128	128					
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	870	870					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	990	990					
NP 20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					
20048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

5/28/2008 08:11:11 AM C:\PROJECTS\62928\62928.dwg

* - Specialty Items
NP = Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
26TH STREET