F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	03-00052-00-PV	LAKE	78	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NUMBER 63002

	ITEM#	IDOT PAY ITEM CODE#	PAY ITEM	UNIT	TOTAL QUANTITY	STP eligible Participation		VILLAGE SPONSORED NON-PARTICIPATING
						Traffic Signal Y031-1F	Roadway I000-2A	
	1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,750		1,750	
	2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	628		628	
	3	20101000	TEMPORARY FENCE	FOOT	3,690		3,690	
	4	20101100	TREE TRUNK PROTECTION	EACH	43		43	
	5	20101200	TREE ROOT PRUNING	EACH	62		62	
	6	20200100	EARTH EXCAVATION	CU YD	3,595		3,595	
	7	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	CU YD	5,431		5,431	
	8	20400800	FURNISHED EXCAVATION	CU YD	5,108		5,108	
	9	20700220	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	398		398	
	10	20800150	TRENCH BACKFILL	CU YD	3,530		3,530	
*	11	21101615	TOPSOIL FURNISH AND PLACE , 4"	SQ YD	24,153		24,153	
*	12	25000210	SEEDING, CLASS 2A	ACRE	0.25		0.25	
*	13	25000312	SEEDING, CLASS 4A	ACRE	2.20		2.20	
*	14	25000314	SEEDING, CLASS 4B	ACRE	0.44		0.44	
*	15	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	260		260	
*	16	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	260		260	
*	17	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	260		260	
*	18	25100630	EROSION CONTROL BLANKET	SQ YD	13,988		13,988	
*	19	25200110	SODDING SALT TOLERANT	SQ YD	10,165		10,165	
	20	28000510	INLET FILTERS	EACH	97		97	
	21	28100101	STONE RIPRAP, CLASS A1	SQ YD	77		77	
	22	28200200	FILTER FABRIC	SQ YD	83		83	
	23	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	550		550	
	24	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	548		548	
	25	35102600	AGGREGATE BASE COURSE, TYPE B, 14"	SQ YD	895		895	
	26	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,880		2,880	
	27	40600300	AGGREGATE (PRIME COAT)	TON	43		43	
	28	40600982	HOT-MIX ASPHALT REMOVAL - BUTT JOINT	SQ YD	292		292	
	29	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	34		34	
	30	40701926	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/4"	SQ YD	28,792		28,792	
	31	42001300	PROTECTIVE COAT	SQ YD	5,255		5,255	
	32	42400800	DETECTABLE WARNINGS	SQ FT	66		66	
	33	44000100	PAVEMENT REMOVAL	SQ YD	20,618		20,618	
	34	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	955		955	
	35	44000300	CURB REMOVAL	FOOT	32		32	
	36	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	617		617	
	37	44000600	SIDEWALK REMOVAL	SQ FT	231		231	
	38	44000900	BITUMINOUS CONCRETE REMOVAL	SQ YD	529		529	
	39	48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	97		97	
	40	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8		8	
	41	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4		4	
	42	54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1		1	
	43	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	4,488		4,488	
	44	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	1,238		1,238	
	45	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	1,634		1,634	
	46	550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	412		412	
	47	55100100	STORM SEWER REMOVAL 4"	FOOT	1,362		1,362	
	48	55100200	STORM SEWER REMOVAL 6"	FOOT	1,749		1,749	
	49	55100300	STORM SEWER REMOVAL 8"	FOOT	123		123	
	50	55100500	STORM SEWER REMOVAL 12"	FOOT	1,763		1,763	
	51	60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	1,800		1,800	
	52	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	16		16	
	53	60214400	RESTRICTED DEPTH CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5		5	
	54	60214714	RESTRICTED DEPTH CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GR	EACH	25		25	
	55	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14		14	
	56	60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14		14	
	57	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	11		11	
	58	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	25		25	
	59	60500040	REMOVING MANHOLES	EACH	1		1	
	60	60500050	REMOVING CATCH BASINS	EACH	1		1	

* INDICATES SPECIALTY ITEM

PLAN
NOTE BOOK NO.
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
LAND TILE TAKE
BY
DATE

PROFILE
NOTE BOOK NO.
SURVEYED
PLOTTED
GRADES CHECKED
BRIDGE CHECKED
STRUCTURE DATA CHKD
BY
DATE

REVISIONS	
NAME	DATE

VILLAGE OF GRAYSLAKE

SHOREWOOD ROAD
IL ROUTE 83 TO ROLLINS ROAD

SUMMARY OF QUANTITIES

SCALE:
DATE: 11/06/07

DESIGNED BY: MTK
DRAWN BY: MTK/BB/GP
CHECKED BY: RPI