F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	03-00052-00-PV	LAKE	78	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NUMBER 63002

	ITEM#	IDOT PAY ITEM CODE#	PAY ITEM	UNIT	TOTAL QUANTITY	STP eligible Participation		VILLAGE SPONSORED NON-PARTICIPATING
						Traffic Signal Y031-1F	Roadway I000-2A	
	61	60500060	REMOVING INLETS	EACH	16		16	
	62	60600105	CONCRETE CURB	FOOT	32		32	
	63	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	88		88	
	64	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	15,697		15,697	
	65	60625610	ISLAND PAVEMENT (8")	SQ YD	8		8	
	66	67100100	MOBILIZATION	L SUM	1		1	
	67	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1	
	68	72000100	SIGN PANEL - TYPE 1	SQ FT	216		216	
	69	72400710	RELOCATE SIGN PANEL - TYPE 1	EACH	24		24	
*	70	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	354		354	
*	71	78000200	THERMOPLASTIC PAVEMENT MARKING - 4"	FOOT	20,018		20,018	
*	72	78000400	THERMOPLASTIC PAVEMENT MARKING - 6"	FOOT	1,559		1,559	
*	73	78000600	THERMOPLASTIC PAVEMENT MARKING - 12"	FOOT	686		686	
*	74	78000650	THERMOPLASTIC PAVEMENT MARKING - 24"	FOOT	219		219	
*	75	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	286		286	
*	76	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	10	10		
*	77	81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	1	1		
*	78	81400200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	10	10		
*	79	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
*	80	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	16	16		
*	81	87301245	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	102	102		
*	82	87301305	ELECTRICAL CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	45	45		
*	83	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4	4		
*	84	87900200	DRILL EXISTING HANDHOLE	EACH	1	1		
*	85	88500100	INDUCTIVE LOOP DETECTOR	EACH	2	2		
*	86	88600100	DETECTOR LOOP, TYPE I	FOOT	264	264		
*	87	89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	2	2		
*	88	89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1	1		
*	89	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	163	163		
*	90	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1		
*	91	A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	115		115	
*	92	A2004816	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER , BALLED AND BURLAPPED	EACH	114		114	
	93	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	72		72	
	94	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	49		49	
	95	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	16,762		16,762	
	96	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	4,200		4,200	
	97	X6700405	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10		10	
*								
	99	XX003503	FLARED END SECTION REMOVAL	EACH	7		7	
	100	XX005569	MAILBOX REMOVAL AND REINSTALLATION	EACH	6		6	
	101	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	34,031		34,031	
	102	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1	
△	103	Z0076600	TRAINEES	HOUR	500		500	
	104	X0325391	EXPANDED POLYSTYRENE FILL	CU YD	1,286		1,286	
	105	XX007517	EARTH EXCAVATION FOR OFF-SITE COMPENSATORY STORAGE	CU YD	260		260	
	106	XX006731	LEVEL SPREADER	EACH	1		1	
	107	XX007518	OBSERVATION STRUCTURE (EXISTING DRAIN TILE)	EACH	2		2	
*	108	XX007519	WARNING SIREN TO BE RELOCATED	L SUM	1		1	
	109	28000500	INLET AND PIPE PROTECTION	EACH	11		11	
	110	XX007531	RELOCATE EXISTING LIGHT POLE ONTO NEW FOUNDATION	EACH	1		1	

* INDICATES SPECIALTY ITEM

△ Y080

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / DATA VERIFIED / CADD FILE NAME / NOTE BOOK NO. — BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / DATA VERIFIED / STRUCTURE NOTATNS CHKD / NOTE BOOK NO. — BY / DATE

REVISIONS	
NAME	DATE

VILLAGE OF GRAYSLAKE

SHOREWOOD ROAD
IL ROUTE 83 TO ROLLINS ROAD

SUMMARY OF QUANTITIES

SCALE:

DATE: 11/06/07

DESIGNED BY: MTK
DRAWN BY: MTK/BB/GP
CHECKED BY: RPI