

F. A. D. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2855	08-00057-00-RS	COOK	11	02
STA.		TO STA.		
FED. ROAD DIST. NO.	KLINGSTUBBINS	FED. PROJ. NO.		

CONTRACT #63043

S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
					CONSTRUCTION TYPE CODE						
					1000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10						
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10						
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10						
	25200110	SODDING, SALT TOLERANT	SQ YD	100	100						
	35800200	AGGREGATE BASE REPAIR	TON	200	200						
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	860	860						
	40600300	AGGREGATE (PRIME COAT)	TON	100	100						
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	410	410						
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	780	780						
	40600895	CONSTRUCTION TEST STRIP	EACH	1	1						
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT , 6"	SQ YD	60	60						
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	200	200						
	42400800	DETECTABLE WARNINGS	SQ FT	70	70						
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8600	8600						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	950	950						
	44000600	SIDEWALK REMOVAL	SQ FT	200	200						
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	170	170						
	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	40	40						
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	520	520						
	56109210	WATER VALVES TO BE ADJUSTED	EACH	2	2						
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	11	11						
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME , OPEN LID	EACH	3	3						
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1						
	60255500	MANHOLES TO BE ADJUSTED	EACH	10	10						
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	2	2						
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	950	950						
	67100100	MOBILIZATION	L SUM	1	1						
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	620	620						
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	90		90					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3800		3800					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	100		100					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30		30					
	X0322752	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	300	300						
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	780	780						
	X7200400	WORK ZONE PUBLIC INFORMATION SIGNS	EACH	2	2						
	XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	50	50						

**GENERAL NOTES:**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS SURFACE IS PLACED.

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**MARSHFIELD AVENUE  
STREET RESURFACING  
SUMMARY OF QUANTITIES**

SCALE: VERT. NA  
HORIZ. NA  
DATE 05/07/08

DRAWN BY EDG  
CHECKED BY RS