

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2947	08-00148-00-RS	COOK	011	003
STA.		TO STA.		
FED. ROAD DIST. NO.	BLKNO.	FED. AID PROJECT		

CONTRACT #63044

SUMMARY OF QUANTITIES				1000 70% FED/ 30% LOCAL
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
	20100210	TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNIT	16
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20
	40600300	AGGREGATE (PRIME COAT)	TON	97
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1361
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2041
	40600895	CONSTRUCTING TEST STRIP	EACH	1
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	427
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	24300
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	80
	44000600	SIDEWALK REMOVAL	SQ FT	10165
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	642
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6 INCH	SQ YD	47
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11005
	42400800	DETECTABLE WARNING	SQ FT	272
	56500600	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED	EACH	4
	60500050	REMOVING CATCH BASINS	EACH	4
	60206905	CATCH BASIN, TYPE C WITH TYPE 1 FRAME, OPEN LID	EACH	4
	60265700	VALVE VAULT TO BE ADJUSTED	EACH	5
	67100100	MOBILIZATION	L. SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L. SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L. SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L. SUM	1
*	78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	2312
*	78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	140
*	78001180	PAINT PAVEMENT MARKING-LINE 24"	FOOT	71
	X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	1737
	X0325769	HOT-MIX ASPHALT REMOVAL, SPECIAL	SQ YD	94
	XX006209	CLASS D PATCH, (SPECIAL), 10 INCH	SQ YD	161
	XX007489	HOT-MIX ASPHALT ALLEY REMOVAL AND REPLACEMENT	SQ YD	8
	XX007490	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8 INCH	SQ YD	34
	XX007491	DRAINAGE STRUCTURE TO BE ADJUSTED WITH TYPE 1 FRAME, OPEN LID	EACH	8
	XX007492	DRAINAGE STRUCTURE TO BE ADJUSTED WITH TYPE 1 FRAME, CLOSED LID	EACH	9

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STATELINE ROAD
ROADWAY RESURFACING
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE 04/23/08

DRAWN BY PS
CHECKED BY RW