

ITEM CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
			J000
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	37
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	41
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	941
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	354
20800150	TRENCH BACKFILL	CU YD	496
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1063
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	233
* 21101665	TOPSOIL FURNISH AND PLACE, 18"	SQ YD	112
* 25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	7
* 25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	7
* 25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	7
* 25200110	SODDING, SALT TOLERANT	SQ YD	345
* 25200200	SUPPLEMENTAL WATERING	UNIT	7
28000400	PERIMETER EROSION BARRIER	FOOT	148
28000510	INLET FILTERS	EACH	7
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1445
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	15
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	1438
42001300	PROTECTIVE COAT	SQ YD	1573
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	210
42400800	DETECTABLE WARNINGS	SQ FT	26
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	105
44000600	SIDEWALK REMOVAL	SQ FT	409
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	64
550A2420	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 48"	FOOT	516
60107600	PIPE UNDERDRAINS 4"	FOOT	134
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60243800	INLET, SPECIAL, WITH TYPE 1 FRAME, OPEN LID	EACH	3
60600605	CONCRETE CURB TYPE B	FOOT	152

ITEM CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
			J000
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	330
61141600	STORM SEWERS, SPECIAL 48"	FOOT	44
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L SUM	1
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	23
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	635
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA, GALVANIZED STEEL	FOOT	71
* 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	120
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	120
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	16
* A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	2
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2 1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3
* E2024001	VINE-POLYGONUM REYNOUTRIA (DWARF FLEECE FLOWER), 1-QUART POT	EACH	115
* K0030450	PERENNIAL PLANTS, DAFFODIL BULBS	UNIT	7.6
XX000882	WOOD FENCE	FOOT	212
* XX001136	LIGHT POLE, SPECIAL	EACH	1
XX001249	ORNAMENTAL FENCE	FOOT	62
XX003360	STORM SEWERS PVC (SDR 26), 12"	FOOT	32
* XX004051	LIGHT POLE, ORNAMENTAL	EACH	1
* XX005178	HEMEROCALLIS 'CHICAGO APACHE' DAYLILY	EACH	96
XX005656	INLET FILTER CLEANING	EACH	21
* XX006002	GRASSES, PENSITUM ALOPECUROIDES 'HAMELN' (HAMELN DWARF FOUNTAIN GRASS) 3 GAL.	EACH	28
* XX006105	HEMEROCALLIS HAPPY RETURNS (HAPPY RETURNS DAYLILY) 1 GALLON	EACH	96
* XX006937	GROUND ROD, 5/8" DIA., X 10 FT	EACH	2
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.U. ROUTE 2689  
WOLF ROAD COMMUTER PARKING FACILITY EXPANSION

SUMMARY OF QUANTITIES

**JJB**  
JAMES J. BENES & ASSOCIATES, INC.  
950 Warrenville Road, Suite 101, Lisle, Illinois 60532  
Tel. (630) 719-7570 • Fax (630) 719-7589

SCALE: NTS  
DATE:

DRAWN BY: BCD  
CHECKED BY: JDM