

- NOTES:
- 1) THE ELECTRICAL CONTRACTOR SHALL MAKE THE SERVICE CONNECTION TO LIGHT A-2. THIS COST SHALL BE INCLUDED IN THE COST OF THE UNIT DUCT PAY ITEM.
 - 2) COORDINATION OF THE SERVICE CONNECTION SHALL BE MADE WITH THE ADJACENT OWNER AT 800 HILLGROVE BY CONTACTING THE VILLAGE OF WESTERN SPRINGS.
 - 3) THE COST TO BULKHEAD PIPE ENDS SHALL BE CONSIDERED INCLUDED IN THE COST OF SS RG AND SS SPECIAL.


STORM SEWER STRUCTURES

| STRUCT. NO. | STATION | OFFSET | STRUCTURE TYPE | RIM | INVERT | | | |
|-------------|---------|--------|---------------------|--------|-------------|--------|--------|--------|
| | | | | | NORTH | SOUTH | EAST | WEST |
| S-1 | 102+09 | 37 LT | INLETS SPL T1F OL | 670.90 | - | - | 665.56 | 665.56 |
| S-2 | 102+08 | 37 RT | INLETS SPL T1F OL | 671.50 | - | - | 665.49 | 665.49 |
| S-3 | 101+99 | 65 RT | INLETS SPL T1F OL | 672.30 | 665.46 | 665.46 | - | - |
| S-4 | 101+67 | 65 RT | MAN TA 5 DIA T1F CL | 672.48 | 665.46 | 665.46 | - | - |
| S-5 | 101+38 | 78 RT | EXISTING STRUCTURE | 673.64 | 665.46 (NW) | - | 665.36 | 665.46 |

STORM SEWERS

| PIPE NO. | LENGTH (FOOT) | MATERIAL | TYPE | DIA. (IN.) | SLOPE % | TBF (CU. YD.) |
|----------|---------------|---------------|------|------------|---------|---------------|
| P-1 | 129 | SS RG CL A | 1 | 48 | 0.10 | 102.5 |
| P-2 | 129 | SS RG CL A | 1 | 48 | 0.10 | 102.5 |
| P-3 | 129 | SS RG CL A | 1 | 48 | 0.10 | 102.5 |
| P-4 | 129 | SS RG CL A | 1 | 48 | 0.10 | 102.5 |
| P-5 | 44 | SS SPECIAL | 1 | 48 | 0.00 | 47.6 |
| P-6 | 32 | SS PVC SDR 26 | - | 12 | 0.00 | 20.0 |

LEGEND



| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 2689
 WOLF ROAD COMMUTER PARKING FACILITY EXPANSION
 DRAINAGE AND UTILITY PLAN

JJB JAMES J. BENES & ASSOCIATES, INC.
 950 Warrenville Road, Suite 101, Lisle, Illinois 60532
 Tel. (630) 719-7570 · Fax (630) 719-7589

SCALE: 1"=20'
 DATE: _____ DRAWN BY: BCD
 CHECKED BY: JDS