

# SCHEDULE OF QUANTITIES

**60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24**

FOOT	LOCATION	REMARKS
200.0	LT & RT Sta984+28.0 TO 990+78.0	In CCC&G section - at Engineer's discretion for sections that fall apart during any construction operations.
<b>200.0</b>	<b>TOTAL</b>	

**78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION	REMARKS
1304.0	Sta. 658+73.0 TO 665+25.0	Overlay 2 Yellow Solid Centerline
328.8	Sta. 665+25.0 TO 678+40.0	Overlay 1 Yellow Skip Dash
401.5	LT Sta. 678+40.0 TO 694+46.0	Overlay 1 Yellow Skip Dash
1606.0	RT Sta. 678+40.0 TO 694+46.0	Overlay 1 Yellow Solid Centerline
3996.0	Sta. 694+46.0 TO 714+44.0	Overlay 2 Yellow Solid Centerline
1069.0	LT Sta. 714+44.0 TO 725+13.0	Overlay 1 Yellow Solid Centerline
267.3	RT Sta. 714+44.0 TO 725+13.0	Overlay 1 Yellow Skip Dash
458.0	Sta. 725+13.0 TO 743+45.0	Overlay 1 Yellow Skip Dash
338.8	LT Sta. 743+45.0 TO 757+00.0	Overlay 1 Yellow Skip Dash
1355.0	RT Sta. 743+45.0 TO 757+00.0	Overlay 1 Yellow Solid Centerline
4400.0	Sta. 757+00.0 TO 779+00.0	Overlay 2 Yellow Solid Centerline
3050.0	LT Sta. 779+00.0 TO 809+50.0	Overlay 1 Yellow Solid Centerline
762.5	RT Sta. 779+00.0 TO 809+50.0	Overlay 1 Yellow Skip Dash
607.5	Sta. 809+50.0 TO 833+80.0	Overlay 1 Yellow Skip Dash
101.8	LT Sta. 833+80.0 TO 837+87.0	Overlay 1 Yellow Skip Dash
407.0	RT Sta. 833+80.0 TO 837+87.0	Overlay 1 Yellow Solid Centerline
10.0	Sta. 837+87.0 TO 837+92.0	Overlay 2 Yellow Solid Centerline
484.0	Sta. 837+92.0 TO 840+34.0	RR 2 Yellow Solid Centerline
732.0	Sta. 840+34.0 TO 844+00.0	Overlay 2 Yellow Solid Centerline
280.0	LT Sta. 844+00.0 TO 855+20.0	Overlay 1 Yellow Skip Dash
1120.0	RT Sta. 844+00.0 TO 855+20.0	Overlay 1 Yellow Solid Centerline
25.0	Sta. 855+20.0 TO 856+20.0	Overlay 1 Yellow Skip Dash
905.0	LT Sta. 856+20.0 TO 865+25.0	Overlay 1 Yellow Solid Centerline
226.3	RT Sta. 856+20.0 TO 865+25.0	Overlay 1 Yellow Skip Dash
368.8	Sta. 865+25.0 TO 880+00.0	Overlay 1 Yellow Skip Dash
137.5	LT Sta. 880+00.0 TO 885+50.0	Overlay 1 Yellow Skip Dash
550.0	RT Sta. 880+00.0 TO 885+50.0	Overlay 1 Yellow Solid Centerline
4080.0	Sta. 885+50.0 TO 905+90.0	Overlay 2 Yellow Solid Centerline
610.0	LT Sta. 905+90.0 TO 912+00.0	Overlay 1 Yellow Solid Centerline
152.5	RT Sta. 905+90.0 TO 912+00.0	Overlay 1 Yellow Skip Dash
250.0	Sta. 912+00.0 TO 922+00.0	Overlay 1 Yellow Skip Dash
130.0	LT Sta. 922+00.0 TO 927+20.0	Overlay 1 Yellow Skip Dash
520.0	RT Sta. 922+00.0 TO 927+20.0	Overlay 1 Yellow Solid Centerline
5660.0	Sta. 927+20.0 TO 955+50.0	Overlay 2 Yellow Solid Centerline
850.0	LT Sta. 955+50.0 TO 964+00.0	Overlay 1 Yellow Solid Centerline
212.5	RT Sta. 955+50.0 TO 964+00.0	Overlay 1 Yellow Skip Dash
184.3	Sta. 964+00.0 TO 971+37.0	Overlay 1 Yellow Skip Dash
1980.0	LT Sta. 658+73.0 TO 678+53.0	Overlay 1 White Solid Edge Line - to Arnold Grove Rd
14795.0	LT Sta. 679+25.0 TO 827+20.0	Overlay 1 White Solid Edge Line - to Dame Rd
10497.0	LT Sta. 828+64.0 TO 933+61.0	Overlay 1 White Solid Edge Line - to Stone Rd
3239.0	LT Sta. 935+12.0 TO 967+51.0	Overlay 1 White Solid Edge Line - to Lanark Ave
292.0	LT Sta. 968+45.0 TO 971+37.0	Overlay 1 White Solid Edge Line - to Arnold Grove Rd
15892.0	RT Sta. 658+73.0 TO 817+65.0	Overlay 1 White Solid Edge Line - to Vanbuskirk Rd
6657.0	RT Sta. 818+68.0 TO 885+25.0	Overlay 1 White Solid Edge Line - to Beede Rd
8448.0	RT Sta. 886+89.0 TO 971+37.0	Overlay 1 White Solid Edge Line - to end of overlay
1017.9	Sta. 979+65.5 TO 982+19.9	Overlay 2 Double Yellow Solid - Median
1906.8	Sta. 982+60.6 TO 987+37.3	Overlay 2 Double Yellow Solid - Median
200.0	RT Sta. 986+37.3 TO 987+37.3	Overlay 2 White Solid - Turn Lane
200.0	LT Sta. 988+42.3 TO 989+42.3	Overlay 2 White Solid - Turn Lane
2504.8	Sta. 988+42.3 TO 994+68.5	Overlay 2 Double Yellow Solid - Median
542.4	Sta. 995+24.1 TO 996+59.7	Overlay 2 Double Yellow Solid - Median
<b>106112.6</b>	<b>TOTAL</b>	

**70300100 SHORT-TERM PAVEMENT MARKING**

FOOT	LOCATION	REMARKS
9621.6	Sta. 658+73.0 TO 979+45.0	Yellow CL, 3 lifts
240.0	Sta. 835+28.0	X=40, RR=50 White RR & X, 3 lifts
108.0	Sta. 837+85.0	3, 12' stripes White RR Stop Bar, 3 lifts
108.0	Sta. 840+40.0	3, 12' stripes White RR Stop Bar, 3 lifts
240.0	Sta. 842+88.0	X=40, RR=40 White RR & X, 3 lifts
24.0	Sta. 965+70.0 TO 966+35.0	White Diagonal Shlder Stripe, 3 Lifts
24.0	Sta. 966+75.0 TO 967+00.0	White Diagonal Shlder Stripe, 3 Lifts
24.0	Sta. 967+25.0 TO 967+60.0	White Diagonal Shlder Stripe, 3 Lifts
42.0	Sta. 968+30.0 TO 969+45.0	White Diagonal Shlder Stripe, 3 Lifts
24.0	Sta. 970+30.0 TO 971+00.0	White Diagonal Shlder Stripe, 3 Lifts
538.2	Sta. 978+55.0 TO 987+52.0	Yellow Median, 2 strips, 3 lifts
46.2	Sta. 985+98.0 TO 987+52.0	White Turn Lane, 3 lifts
373.8	Sta. 988+11.0 TO 994+34.0	Yellow Median, 2 strips, 3 lifts
48.3	Sta. 988+11.0 TO 989+72.0	White Turn Lane, 3 lifts
69.0	Sta. 995+29.0 TO 996+44.0	Yellow Median, 2 strips, 3 lifts
588.9	Sta. 996+44.0 TO 1016+07.0	Yellow CL, 3 lifts
25.2	IL 73 Sta. +22.0 TO 1+06.0	Yellow CL, 3 lifts
<b>12145.2</b>	<b>TOTAL</b>	

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION	REMARKS
1603.6	Sta. 658+73.0 TO 979+45.0	Yellow CL, 1 lift
40.0	Sta. 835+28.0	X=40, RR=50 White RR & X, 1 lift
18.0	Sta. 837+85.0	3, 12' stripes White RR Stop Bar, 1 lift
18.0	Sta. 840+40.0	3, 12' stripes White RR Stop Bar, 1 lift
40.0	Sta. 842+88.0	X=40, RR=40 White RR & X, 1 lift
8.0	Sta. 965+70.0 TO 966+35.0	White Diagonal Shlder Stripe, 3 Lifts
8.0	Sta. 966+75.0 TO 967+00.0	White Diagonal Shlder Stripe, 3 Lifts
8.0	Sta. 967+25.0 TO 967+60.0	White Diagonal Shlder Stripe, 3 Lifts
14.0	Sta. 968+30.0 TO 969+45.0	White Diagonal Shlder Stripe, 3 Lifts
8.0	Sta. 970+30.0 TO 971+00.0	White Diagonal Shlder Stripe, 3 Lifts
89.7	Sta. 978+55.0 TO 987+52.0	Yellow Median, 2 strips, 1 lift
7.7	Sta. 985+98.0 TO 987+52.0	White Turn Lane, 1 lift
62.3	Sta. 988+11.0 TO 994+34.0	Yellow Median, 2 strips, 1 lift
8.1	Sta. 988+11.0 TO 989+72.0	White Turn Lane, 1 lift
11.5	Sta. 995+29.0 TO 996+44.0	Yellow Median, 2 strips, 1 lift
98.2	Sta. 996+44.0 TO 1016+07.0	Yellow CL, 1 lift
4.2	IL 73 Sta. +22.0 TO 1+06.0	Yellow CL, 1 lift
<b>2047.2</b>	<b>TOTAL</b>	

**78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS**

SQ FT	LOCATION	REMARKS
54.0	Sta. 835+29.0	White RR " X "
7.2	Sta. 835+29.0	2 White RR " R's "
54.0	Sta. 842+89.0	White RR " X "
7.2	Sta. 842+89.0	2 White RR " R's "
15.6	Sta. 986+12.3	White Left Turn Arrow
15.6	Sta. 986+64.8	White Left Turn Arrow
15.6	Sta. 987+17.3	White Left Turn Arrow
15.6	Sta. 988+62.3	White Left Turn Arrow
15.6	Sta. 989+04.8	White Left Turn Arrow
15.6	Sta. 989+62.3	White Left Turn Arrow
<b>216.0</b>	<b>TOTAL</b>	

**78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"**

FOOT	LOCATION	REMARKS
74.3	LT Sta. 987+51.5 TO 987+70.5	IL 73 1 White Solid - Island
<b>74.3</b>	<b>TOTAL</b>	