

MAINLINE SCHEDULE

STRUCTURE NO.				RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	HMA SURFACE REMOVAL VARIABLE DEPTH SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GAL	MIX FOR CRACKS, JOINTS & FLANGEWAYS TON	HMA SURFACE CSE MIX D, N90 TON	SHORT-TERM PAVEMENT MARKING TON
LOCATION									
M.P.	S.N.	NB/SB	N/S END						
FORD COUNTY									
258.67	027-0053	NB	N	2	347	28	1	45	39
			S	2	347	28	1	45	39
258.67	027-0052	SB	N	1	80	7	1	11	9
			S	1	80	7	1	11	9
								0	
261.80	028-0051	NB	N	2	267	22	1	35	30
			S	2	267	22	1	35	30
261.80	027-0050	SB	N	1	134	11	1	18	15
			S	1	134	11	1	18	15
SUBTOTAL				12	1656	136	8	218	186
IROQUOIS COUNTY									
282.04	038-0001	SB	N	1	80	7	1	11	9
			S	1	80	7	1	11	9
285.68	038-0168	NB	N	1	200	16	1	26	23
			S	1	200	16	1	26	23
285.68	038-0167	SB	N	2	347	28	1	45	39
			S	2	347	28	1	45	39
287.74	038-0159	NB	N	1	160	13	1	21	18
			S	1	160	13	1	21	18
287.74	038-0158	SB	N	2	320	26	1	41	36
			S	2	320	26	1	41	36
288.70	038-0011	NB	N	2	267	22	1	35	30
			S	2	267	22	1	35	30
288.70	038-0012	SB	N	2	360	29	1	47	41
			S	2	360	29	1	47	41
295.83	038-0013	NB	N	2	347	28	1	45	39
			S	2	347	28	1	45	39
SUBTOTAL				26	4162	338	16	542	470
TOTAL				38	5818	474	24	760	656

* D3 APPROACH PAVEMENT RESURFACING 2009-1
 ** IROQUOIS & FORD

FILE NAME = c:\projects\cmstr09\cm314\details.dgn	USER NAME = woodshankr1	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. 5 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	8	7
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				