

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAP 769 80 % - FED 20 % - STATE 1000 - 2A	STRUCTURE SN 059 - 0509 80 % - FED 20 % - STATE X081 - 2A		
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	36	36			
44000100	PAVEMENT REMOVAL	SQ YD	102	102			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	47	47			
44000700	APPROACH SLAB REMOVAL	SQ YD	215	215			
44004250	PAVED SHOULDER REMOVAL	SQ YD	106	106			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	89	89			
48101300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	TON	190	190			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	166	166			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50105220	PIPE CULVERT REMOVAL	FOOT	98	98			
50200100	STRUCTURE EXCAVATION	CU YD	495		495		
50300100	FLOOR DRAINS	EACH	20		20		
50300225	CONCRETE STRUCTURES	CU YD	194		194		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	451		451		