

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAP 769 80 % - FED 20 % - STATE 1000 - 2A	STRUCTURE SN 059 - 0509 80 % - FED 20 % - STATE X081 - 2A		
* 51604000	DRILLED SHAFT IN ROCK	CU YD	61		61		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24		
52100520	ANCHOR BOLTS, 1"	EACH	48		48		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4		4		
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	48	48			
54202320	PIPE CULVERTS, TYPE 3, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	108	108			
54215547	METAL END SECTIONS 12"	EACH	4	4			
54215550	METAL END SECTIONS 15"	EACH	4	4			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	85		85		
60100945	PIPE DRAINS 12"	FOOT	40	40			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	133		133		
60900215	TYPE C INLET BOX, STANDARD 609001	EACH	4	4			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	850	850			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			

*SPECIALTY ITEMS

FILE NAME *	USER NAME # loughlinc1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\Projects\653603\ie_final\8006sum01.s		DRAWN -	REVISED -						769	110B-2	MACOUPIN	98	7
PLOT SCALE = 20.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 72813				FED. ROAD DIST. NO. 6 [ILLINOIS] FED. AID PROJECT				
PLOT DATE # May-15-2008 02:45:32PM		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			