

CONCRETE BARRIER SCHEDULE								
STATION	LT/RT	TO	STATION	LT/RT	70400100 TEMPORARY CONCRETE BARRIER (FOOT)	70400200 RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	Z0030260 IMPACT ATTENUATORS, TEMPORARY (EACH)	Z0030330 IMPACT ATTENUATORS, RELOCATE (EACH)
100+70.00	5' LT		101+80.00	3.5' RT	111			
101+80.00	3.5' RT		107+00.00	3.5' RT	520			
107+00.00	3.5' RT		108+10.00	5' LT	111			
100+70.00	5' LT		101+80.00	3.5' RT		111		
101+80.00	3.5' RT		107+00.00	3.5' RT		520		
107+00.00	3.5' RT		108+10.00	5' LT		111		
STAGE 1								
100+70.00	4' LT						1	
108+10.00	4' LT						1	
STAGE 2								
100+70.00	4' RT							1
108+10.00	4' RT							1
TOTALS					742	742	2	2

RIGHT-OF-WAY SCHEDULE			
STATION	OFFSET	LT/RT	66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS
	(FEET)		(EACH)
102+00	50.00	LT	1
102+00	55.00	RT	1
103+50	150.00	LT	1
103+50	160.00	RT	1
108+00	160.00	RT	1
110+49.17	55.83	RT	1
TOTALS			6

GUARDRAIL SCHEDULE									
LOCATION			LT/RT	63000000 STEEL PLATE BEAM GUARD- RAIL, TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL		63200310 GUARDRAIL REMOVAL (FOOT)	78200410 GUARDRAIL MARKER TYPE A (EACH)	78201000 TERMINAL MARKER - DIRECT APPLIED (EACH)
STATION	TO	STATION		(FOOT)	63100167 TYPE 1, SPECIAL (TANGENT) (EACH)	63100085 TYPE 6 (EACH)	(FOOT)	(EACH)	(EACH)
101+12.50		101+62.50	LT		1				1
101+62.50		102+37.50	LT	75				1	
102+37.50		102+83.50	LT			1		1	
100+00.00		100+50.00	RT		1				1
100+50.00		102+37.50	RT	187.5				3	
102+38.00		102+83.50	RT			1		1	
105+98.50		106+44.00	LT			1		1	
106+44.00		110+19.00	LT	375				5	
105+98.50		106+44.00	RT			1		1	
106+44.00		107+31.50	RT	87.5				2	
107+31.50		107+81.50	RT			1			1
108+40.00		108+90.00	RT			1			1
108+90.00		110+15.00	RT	125.0				2	
101+00.00		102+89.00	LT				189		
101+25.00		102+89.00	RT				164		
105+92.00		110+19.00	LT				427		
105+92.00		110+15.00	RT				423		
TOTALS				850	4	4	1,203	17	4

ESTIMATED QUANTITIES	
PAY ITEM	QUANTITY
EARTH EXCAVATION FOR EROSION CONTROL	200 CU YD
AGGREGATE (EROSION CONTROL)	152 TON
PERIMETER EROSION BARRIER	1,200 FOOT
INLET AND PIPE PROTECTION	3 EACH