

SUMMARY OF QUANTITIES					
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAS 1613 80% FEDERAL 20% STATE	STRUCTURE S.N. 084-7132 80% FEDERAL 20% STATE
				CONSTRUCTION 1000-2A	TYPE CODE 4007
20200100	EARTH EXCAVATION	CU YD	730	730	
20400800	FURNISHED EXCAVATION	CU YD	70	70	
25000200	SEEDING, CLASS 2	ACRE	0.9	0.9	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.8	1.8	
25100115	MULCH, METHOD 2	ACRE	0.9	0.9	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	90	
28000400	PERIMETER EROSION BARRIER	FOOT	1197	1197	
28001000	AGGREGATE (EROSION CONTROL)	TON	20	20	
28100205	STONE RIPRAP, CLASS A3	TON	52		52
28200200	FILTER FABRIC	SQ YD	103		103
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	98	98	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0	1.0	
40600300	AGGREGATE (PRIME COAT)	TON	5.3	5.3	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	103	103	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	343	343	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	163	163	
44000100	PAVEMENT REMOVAL	SQ YD	98	98	
44004250	PAVED SHOULDER REMOVAL	SQ YD	210	210	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	213	213	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	397	397	
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	110	110	
50800105	REINFORCEMENT BARS	POUND	3890		3890
54003000	CONCRETE BOX CULVERTS	CU YD	35.0		35.0
54021205	PRECAST CONCRETE BOX CULVERT 12' X 5' (M273)	FOOT	58		58
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	174	174	
63200310	GUARDRAIL REMOVAL	FOOT	178	178	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	12	12	

SUMMARY OF QUANTITIES					
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAS 1613 80% FEDERAL 20% STATE	STRUCTURE S.N. 084-7132 80% FEDERAL 20% STATE
				CONSTRUCTION 1000-2A	TYPE CODE 4007
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	252	252	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	2050	2050	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	745	745	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
X0324118	GRANULAR CULVERT BACKFILL	CU YD	189		189
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0054517	ROCKFILL - FOUNDATION	TON	43		43

* SPECIALTY ITEMS