

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 095-0077		SN 095-0078	
				I000-2A FED 80% STATE 20%	X071-2A FED 80% STATE 20%	I000-2A FED 80% STATE 20%	X080-2A FED 80% STATE 20%
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	378	356		22	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	580	540		40	
20200100	EARTH EXCAVATION	CU YD	1145	600		545	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	120	65		55	
20300100	CHANNEL EXCAVATION	CU YD	635				635
20400800	FURNISHED EXCAVATION	CU YD	750	655		95	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	86		86		
25000100	SEEDING, CLASS 1	ACRE	0.25	0.25			
25000200	SEEDING, CLASS 2	ACRE	0.75	0.5		0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	66	43.5		22.5	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	66	43.5		22.5	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	66	43.5		22.5	
25100105	MULCH, METHOD 1	ACRE	2.5	1.5		1	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	123	71.5		51.5	
28000300	TEMPORARY DITCH CHECKS	EACH	22	15		7	
28000400	PERIMETER EROSION BARRIER	FOOT	730	450		280	
28000500	INLET AND PIPE PROTECTION	EACH	1	1			
28100107	STONE RIPRAP, CLASS A4	SQ YD	525		525		
28100109	STONE RIPRAP, CLASS A5	SQ YD	340				340
28200200	FILTER FABRIC	SQ YD	865		525		340
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	51			51	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	46	46			
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	454	254		200	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.1	0.6		0.5	
40600300	AGGREGATE (PRIME COAT)	TON	6	3		3	
40600990	TEMPORARY RAMP	SQ YD	54	27		27	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1294	652		642	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	291	157.5		133.5	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	6	6			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	220		220		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44		44		
44000100	PAVEMENT REMOVAL	SQ YD	777	509		268	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	948	374		574	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	865	468		397	

PLOT DATE = 11/28/2007
 PLOT NAME = 54.00000 / IN.
 PLOT SCALE = 54.00000 / IN.
 REFERENCE = #REF#