

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	SBR-2	WASHINGTON	97	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 095-0077		SN 095-0078	
				I000-2A FED 80% STATE 20%	X071-2A FED 80% STATE 20%	I000-2A FED 80% STATE 20%	X080-2A FED 80% STATE 20%
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	865	468		397	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1
50105220	PIPE CULVERT REMOVAL	FOOT	25.5	25.5			
50200100	STRUCTURE EXCAVATION	CU YD	505		140		365
50300100	FLOOR DRAINS	EACH	8		8		
50300225	CONCRETE STRUCTURES	CU YD	173.8		28.8		145
50300255	CONCRETE SUPERSTRUCTURE	CU YD	88.1		88.1		
50300260	BRIDGE DECK GROOVING	SQ YD	213		213		
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2		
50300300	PROTECTIVE COAT	SQ YD	281		281		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	1134		1134		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	28550		21960		6590
50800515	BAR SPLICERS	EACH	313		285		28
50900200	STEEL RAILING, TYPE 2399	FOOT	64				64
58700300	CONCRETE SEALER	SQ FT	144				144
51201600	FURNISHING STEEL PILES HP12X53	FOOT	245		245		
51202305	DRIVING PILES	FOOT	245		245		
51203600	TEST PILE STEEL HP12X53	EACH	1		1		
51500100	NAME PLATES	EACH	2		1		1
52100520	ANCHOR BOLTS, 1"	EACH	24		24		
54213453	END SECTIONS 18"	EACH	2	2			
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	25.5	25.5			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	51		51		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	138		138		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	750	375		375	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4			4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	1152	559		593	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	25	12		13	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	4.5		4.5	
67100100	MOBILIZATION	L SUM	1	0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5		0.5	

*SPECIALTY ITEMS

PLOT DATE = 11/28/2007
 PLOT SCALE = 5/8" = 1' / IN.
 REFERENCE = BREF