

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	SBR-2	WASHINGTON	97	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				3RS		RS	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION		TYPE CODE	
				SN 095-0077		SN 095-0078	
				I000-2A FED 80% STATE 20%	X071-2A FED 80% STATE 20%	I000-2A FED 80% STATE 20%	X080-2A FED 80% STATE 20%
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2	1		1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70106700	TEMPORARY RUMBLE STRIP	EACH	12	6		6	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	4.5		4.5	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10286	5276		5010	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3520	1820		1700	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	154	60		94	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3737	1879		1858	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1840		910		930
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1680		910		770
* 72000100	SIGN PANEL - TYPE 1	SQ FT	20	10		10	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	48	24		24	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5825	2694		3131	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	38			38	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	279		279		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	31	15		16	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2		
78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4		2		2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	9		9	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	4		4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1939	990		949	
X0321100	GEOTEXTILE RETAINING WALL	SQ FT		171.9			171.9
X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1				1
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	808.4		364.3		444.1
X7200200	WIDE LOAD SIGNING	L SUM	1	0.5		0.5	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		2		2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3		2		1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3		2		1
X0325916	THREE-SIDED PRECAST CONCRETE STRUCTURE 28' X 9'	FOOT	37.25				37.25
* E0007600	TRAINEES	HOURL	500	500			

©Y080 * SPECIALTY ITEMS

Rev. 2-19-08

PLOT DATE = 11/29/2007
 FILE NAME = c:\pms\proj\76949\plan\plan\01105a.dgn
 PLOT SCALE = 1"=100'
 REFERENCE = MREF*