

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	12
STA. _____ TO STA. _____		ILLINOIS FED. AID PROJECT		

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS					OVER 15 UNITS							
1450+57.90	32.5	LT				12									
1450+63.50	30.4	LT			10										
1450+63.50	30.3	LT				12									
1450+63.70	28.7	LT			10										
1450+65.90	32.9	LT	6												
1450+82.69	31.2	LT						20							
1450+98.04	31.3	LT				12									
1451+05.00	32.5	LT			10										
1451+08.90	32.8	LT	6												
1451+12.00	28.1	LT				15									
1451+13.30	28.0	LT				15									
1451+29.70	30.1	LT			10										
1451+38.80	34.2	LT				15									
1451+39.67	42.4	LT							36						
1451+40.50	34.8	LT					24								
1451+51.60	46.3	LT						30							
1451+53.20	31.5	LT			10										
1451+53.77	44.1	LT		8											
1451+54.67	31.9	LT					24								
1451+62.24	41.5	LT						30							
1451+63.48	34.5	LT					24								
1451+68.40	33.1	LT	6												
1451+71.60	33.8	LT			10										
1451+73.03	42.3	LT					18								
1451+80.05	34.9	LT	6												
1451+80.90	33.0	LT	6												
1451+84.40	37.0	LT							36						
1451+85.70	28.6	LT					18								
1452+01.20	41.0	LT		8											
1452+03.85	45.4	LT		8											
1452+16.90	38.9	LT							36						
1452+18.40	30.1	LT					18								
1452+19.17	31.3	LT					18								
1452+19.86	30.8	LT						24							
1452+20.50	46.5	LT	6												
1452+22.70	44.7	LT		8											
1452+27.89	46.4	LT		8											
1452+35.77	40.0	LT				15									
1452+36.50	42.2	LT						24							
1452+40.80	44.0	LT	6												
1452+48.92	39.5	LT	6												
1452+51.23	42.0	LT		8											
1452+53.86	40.2	LT		8											
1452+55.64	36.1	LT						24							
1452+62.53	49.4	LT	6												
1452+66.71	47.5	LT	6												
1452+75.03	31.4	LT			10										
1452+75.60	32.5	LT	6												
1452+81.28	46.7	LT			10										
1452+98.54	26.3	LT		8											
1452+99.00	26.2	LT	6												
1454+04.19	33.3	LT										44			
1454+04.64	30.8	LT				15									
1454+06.74	32.6	LT						24							
1454+13.04	31.0	LT	6												
1454+19.94	33.3	LT					18								
1456+85.80	33.0	LT				15									
1457+23.60	30.3	LT												50	
1457+43.90	34.1	LT		8											
SUB-TOTAL			78	72	80	36	90	90	20	168	60	108	44	50	
TOTAL			356					540							

SEEDING SCHEDULE

STA	STA	AREA (SQ FT)	SEEDING CLASS 2 (ACRE)	SEEDING CLASS 1 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
1449+25.00 TO	1457+50.00 LT	6370	0.15		13.16	13.16	13.16	0.15
1449+25.00 TO	1452+79.50 RT	2952		0.1	6.10	6.10	6.10	0.07
1455+92.00 TO	1458+00.00 RT	2113		0.1	4.37	4.37	4.37	0.05
1449+25.00 TO	1457+50.00 RT	9568	0.22		19.77	19.77	19.77	0.22
TOTAL			0.37	0.20	43.40	43.40	43.40	0.49

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1449+25.00 TO STA. 1452+79.50	197.3	147.9	668.1	-520.2
STA. 1453+43.50 TO STA. 1457+50.00	401.3	301.0	435.0	-134.1
TOTAL	598.6	448.9	1103.1	-654.3

EARTHWORK SCHEDULE (WIDENING)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1449+25.00 TO STA. 1452+83.00	30.5	22.9	0.0	22.9
STA. 1453+47.00 TO STA. 1457+50.00	34.3	25.7	0.0	25.7
TOTAL	64.8	48.6	0.0	48.6

ROW MARKERS SCHEDULE

STATION	LOCATION		ROW MARKERS (EA)
	SIDE	OFFSET	
1449+00.00	29.11	L+	1
1449+00.00	30.89	R+	1
1449+50.00	50.89	R+	1
1450+00.00	39.11	L+	1
1451+00.00	39.12	L+	1
1451+50.00	54.13	L+	1
1453+00.00	54.14	L+	1
1453+50.00	39.14	L+	1
1457+50.00	50.83	R+	1
1458+00.00	30.83	R+	1
1458+00.00	39.17	L+	1
1458+00.00	29.17	L+	1
TOTAL			12

S.N. 095-0077

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAS ROUTE 1832  
 SECTION 5BR-2  
 WASHINGTON COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_