

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	55
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

RESURFACING SCHEDULE

STATION	RT/LT	HOT-MIX ASPHALT BS WIDENING 9" (SQ YD)	AGGREGATE PRIME COAT (TON)	BIT. MAT'L PRIME COAT (TON)	HMA CONC BINDER SUPER, MIX "B" (TON)	HMA CONC SURF CSE, SUPER, MIX "C", N70 (TON)	SUB-BASE GRANULAR MATERIAL TY-A 12" (SQ YD)	HMA SHOULDERS 8" (SQ YD)	AGG. SHLD TYPE B 6" (SQ YD)
1508+00.00 TO 1508+90.00	RT/LT				10.08				
1507+75.00 TO 1510+52.50	RT								
1507+75.00 TO 1510+68.30	LT	97.77							
1508+00.00 TO 1510+86.00	RT/LT		1.14	0.24		64.06		190.67	190.67
1508+90.00 TO 1510+86.00	RT/LT				307.33				
1510+67.40 TO 1510+84.00	RT/LT						50.56		
1511+18.90 TO 1514+25.00	LT	102.03							
1511+16.00 TO 1513+15.00	RT/LT				312.03				
1511+09.00 TO 1514+25.00	RT								
1511+16.00 TO 1514+25.00	RT/LT		1.24	0.26		69.22		206.00	206.00
1513+15.00 TO 1514+25.00	RT/LT				12.32				
TOTAL		199.80	2.38	0.50	641.76	133.28	50.56	396.67	396.67

GUARDRAIL SCHEDULE

STATION	RT/LT	SPBGR (FT)	TBT - T1 (SPECIAL) (EA)	TBT - T6A (EA)	GUARDRAIL MRKS TY-A (EA)	BI-DIREC PRISM BARR REFLEC (EA)
1508+45.25 TO 1510+76.50	RT	137.5	1	1	3	
1509+45.25 TO 1510+89.00	LT	50	1	1	2	
1510+86.00 TO 1511+16.00	RT/LT					2
1511+22.25 TO 1513+53.50	LT	137.5	1	1	3	
1511+11.00 TO 1512+54.75	RT	50	1	1	2	
TOTAL		375	4	4	9	2

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION	RT/LT	STOP BAR	PAVEMENT MARKING			WORK ZONE PVMT REMOVAL (SQ FT)	PVMT MRKG REMOVAL (SQ FT)	
			LINE 4" PAVEMENT (FT)	LINE 6" (TEMP. BARR.) (FT)	LINE 24" PAVEMENT (FT)			
1504+95.00	RT	STOP BAR			12	24.0		
1504+70.00	LT	STOP BAR			12	24.0		
1504+70.00		1517+35.00	STAGE 2	2530		843.3		
1504+95.00 TO 1517+35.00			STAGE 1	2480		826.7		
1504+70.00 TO 1517+35.00	RT/LT						843.3	
1504+70.00 TO 1517+35.00	CL						105.4	
1507+95.00 TO 1515+64.50			STAGE 1		770			
1506+40.50 TO 1515+69.50			STAGE 2		930			
1507+51.24	MALLARD	RT			46	92.0		
1517+35.00	LT	STOP BARS			24	48.0		
SUB-TOTAL								
TOTAL				5010	1700	94	1858.0	948.7

PAVEMENT MARKING SCHEDULE

STATION	RT/LT	CL	PAVEMENT - THERMOPLASTIC				24" WHITE LINE (FT)
			4" WHITE LINE (FT)	4" YELLOW LINE (FT)	YELLOW SKIP DASH LINE 4" (FT)	DBL AMBER RSD REFL PMK (EA)	
1504+69.00 TO 1517+36.00	CL				316.75	16	
1504+69.00 TO 1517+36.00	RT/LT		2414				
1507+51.24	STOP BAR	RT					38
1509+00.00 TO 1513+00.00	CL			400.0			
SUB-TOTAL			2414	400.00	316.75	16	
TOTAL				3130.75			38

S.N. 095-0078

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAS ROUTE 1832 SECTION 5BR-2 WASHINGTON COUNTY
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____

PLOT DATE = 12/7/2007
FILE NAME = c:\p\proj\p1832\5br\p1832\p1832.dgn
PLOT SCALE = 50.0000 / 1 IN.
REFERENCE = #REF#