

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	56
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS	OVER 15 UNITS
1510+86.70	40.5	LT		16
1510+97.80	61.2	RT	12	
1510+98.40	59.5	RT	10	
1511+27.20	33.5	LT		24
SUB-TOTAL			10	12
TOTAL			22	40

SEEDING SCHEDULE

STA	STA	AREA SQ FT	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
1507+75.00	TO 1513+50.00	LT	5005	0.12	10.34	10.34	0.12
1507+75.00	TO 1513+50.00	RT	5824	0.13	12.03	12.03	0.13
TOTAL				0.25	22.37	22.37	0.25

REMOVAL SCHEDULE

LOCATION					PVMT REMOVAL		HMA SURF REMOVAL VAR. DEPTH (SQ YD)	SPBGR (FT)
FROM	OFFSET	TO	OFFSET	RT/LT	MAINLINE REMOVAL (SQ YD)	WIDENING REMOVAL (SQ YD)		
1507+75.00		1510+68.30		LT		97.77		
1508+00.00		1508+90.00		RT/LT			240.00	
1508+59.00		1510+36.00		RT			177.00	
1509+54.00		1510+83.00		LT			129.00	
1510+86.50		1511+87.50		RT			101.00	
1510+93.25		1511+17.90		RT/LT	68.14			
1511+09.50		1512+95.50		LT			186.00	
1511+18.90		1514+25.00		LT		102.03		
1512+27.00	20.6	1512+44.50	26.6	RT				
1513+00.00		1514+25.00		RT/LT			333.33	
TOTAL					68.14	199.80	573.33	593.00
						267.94		

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1507+75.00 TO STA. 1510+86.00	352.5	264.4	262.5	1.9
STA. 1511+16.00 TO STA. 1514+25.00	188.5	141.4	236.7	-95.3
TOTAL	541.0	405.8	499.2	-93.4

EARTHWORK SCHEDULE (WIDENING)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1507+75.00 TO STA. 1510+68.30	25.0	18.7	0.0	18.7
STA. 1511+18.90 TO STA. 1514+25.00	26.1	19.6	0.0	19.6
TOTAL	51.1	38.3	0.0	38.3

ROW MARKERS SCHEDULE

LOCATION				ROW MARKERS (EA)
STATION	SIDE	OFFSET		
1506+37.55	29.54	L+		1
1506+37.56	30.46	R+		1
1507+50.00	29.54	L+		1
1508+50.00	44.55	L+		1
1509+55.29	78.21	R+		1
1510+43.14	30.43	R+		1
1510+49.50	78.2	R+		1
1510+80.00	44.57	L+		1
1512+00.00	45.42	R+		1
1513+00.00	29.59	L+		1
1514+00.00	45.41	R+		1
1514+50.00	30.4	R+		1
1514+50.00	29.54	L+		1
TOTAL				13

EARTHWORK SCHEDULE (CHANNEL)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 0+40.00 TO STA. 1+80.00	632.4	474.3	241.5	232.8
TOTAL	632.4	474.3	241.5	232.8

S.N. 095-0078

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAS ROUTE 1832
 SECTION 5BR-2
 WASHINGTON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____