

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 885	107BR-1	JOHNSON	94	6
FED. ROAD DIST. NO.		ILLINOIS	CONTRACT NO. 78030	

MAINTENANCE OF TRAFFIC							
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL MARKERS	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIPS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
FAP 885 IL RTE 146							
STAGE I							
723+41.06 TO 733+14.54				1	6	2	
STA. 725+00.60 TO STA. 731+50.00	637.5		27				
STAGE II							
723+41.06 TO 733+14.54							2
STA. 725+00.60 TO STA. 731+50.00		637.5					
TOTAL	637.5	637.5	27	1	6	2	2

PAVEMENT MARKING SCHEDULE											
LOCATION	TEMPORARY				EPOXY PAVEMENT MARKING PERMANENT			WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
	24" SINGLE WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SOLID YELLOW CENTERLINE				
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT				
FAP 885 IL RTE 146											
STAGE I											
CL. STA. 723+41.06 TO CL. STA. 733+14.54									45	14	
LT. STA. 723+41.06 TO LT. STA. 733+14.54									328		
LCL. STA. 723+41.06 TO LCL. STA. 733+14.54									178		
RT. STA. 723+41.06 TO RT. STA. 733+14.54									328		
LT. STA. 723+41.06 TO LT. STA. 733+14.54	12	962						317			
RT. STA. 723+41.06 TO LT. STA. 726+00.00		259						85			
LT. STA. 726+11.90 TO LT. STA. 731+00.00		488						161			
LT. STA. 731+00.00 TO RT. STA. 733+14.54	12	215						71			
STAGE II											
LT. STA. 724+01.06 TO RT. STA. 726+00.00		199						66			
RT. STA. 726+11.90 TO RT. STA. 731+00.00		488						161			
RT. STA. 731+00.00 TO LT. STA. 733+14.54		215						68			
RT. STA. 723+41.06 TO RT. STA. 733+14.54		962						317			
LT. STA. 733+14.54								24			
RT. STA. 723+41.06								24			
LT. STA. 733+14.54											
LT. STA. 723+41.06 TO LT. STA. 733+14.54		962			962						
RT. STA. 723+41.06 TO RT. STA. 733+14.54		962			962						
LCL. STA. 723+41.06 TO LCL. STA. 733+14.54				962			962				
CL. STA. 723+41.06 TO CL. STA. 733+14.54			241			241					
SUBTOTAL	24	5712	241	962	1924	241	962	1294	879	14	
TOTAL	24		6915			3127		1294	879	14	

HAMPTON, LENZINI & RENWICK, INC.
 CIVIL & STRUCTURAL ENGINEERS
 LAND SURVEYORS

HLR

3085 STEVENSON DRIVE, SUITE 201
 SPRINGFIELD, ILLINOIS 62703
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-52-0007-1 DATE: 04/21/08
 DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: D.T.M.

SCHEDULE OF QUANTITIES

IL. ROUTE 146 OVER CACHE RIVER
F.A.P. ROUTE 885 / SECTION 107BR-1
JOHNSON COUNTY
STATION 727+23
STRUCTURE NO. 044-0014