

SUMMARY OF QUANTITIES				POPE COUNTY	POPE COUNTY
				F.A.P. 885	F.A.P. 885
				S.N. 076-0006	S.N. 076-0008
				HBP FUNDING 80% FEDERAL 20% STATE	HBP FUNDING 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE X080-2A	CONSTRUCTION TYPE CODE X080-2A
20200500	EARTH EXCAVATION (WIDENING)	CU YD	108	56	52
25000210	SEEDING, CLASS 2A	ACRE	0.16	0.08	0.08
25000350	SEEDING, CLASS 7	ACRE	0.16	0.08	0.08
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	14.4	7.2	7.2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14.4	7.2	7.2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	14.4	7.2	7.2
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.32	0.16	0.16
25100115	MULCH, METHOD 2	ACRE	0.32	0.16	0.16
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	32	16	16
28000400	PERIMETER EROSION BARRIER	FOOT	1,538	778	760
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	40	20	20
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	440	228	212
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	193	105	88
40600300	AGGREGATE (PRIME COAT)	TON	1.4	0.8	0.6
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	476	303	173
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	101.8	64.2	37.6
44000100	PAVEMENT REMOVAL	SQ YD	40	20	20
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1	1
50300225	CONCRETE STRUCTURES	CU YD	2.6	2.6	0
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	598	299	299
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,422	0	1,422
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2,921	2,921	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	360	360	0
50800515	BAR SPLICERS	EACH	6	6	0
50901050	STEEL RAILING, TYPE SM	FOOT	425	258	167
51500100	NAME PLATES	EACH	2	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	58	58	0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	525	352	173
58700300	CONCRETE SEALER	SQ FT	26	26	0

SUMMARY OF QUANTITIES				POPE COUNTY	POPE COUNTY
				F.A.P. 885	F.A.P. 885
				S.N. 076-0006	S.N. 076-0008
				HBP FUNDING 80% FEDERAL 20% STATE	HBP FUNDING 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE X080-2A	CONSTRUCTION TYPE CODE X080-2A
59000200	EPOXY CRACK INJECTION	FOOT	37	31	6
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	2	2
63200310	GUARDRAIL REMOVAL	FOOT	360	180	180
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	10	10
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	9	3	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	151	80	71
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,314	2,674	2,640
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,822	918	904
70400100	TEMPORARY CONCRETE BARRIER	FOOT	837.5	462.5	375
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	837.5	462.5	375
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,614	1,236	1,378
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	4	4
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	471	248	223
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5	3	2
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	2	1	1
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	598	299	299
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	26	26	0
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52	52	0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2



FILE NAME =
#FILE#

USER NAME = #USER#

PLOT SCALE = #SCALE#

PLOT DATE = #DATE#

DESIGNED - JMH

DRAWN - AEC

CHECKED - JMH

DATE - 04/09/08

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

*Specialty Items

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 885 SECTION 111BR-1 & 111BR-2 COUNTY POPE TOTAL SHEETS 69 SHEET NO. 3 CONTRACT NO. 78033

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT